



**OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS**

County Smith
Project No. EFL-0330(14)B LPA / 108787-701000
Road Name. Smith County Road 504

BIDS RECEIVED: FRIDAY, MAY 29, 2026 AT 10:00 AM IN THE BOARDROOM AT RALEIGH, MS

Project Description: 0.065 miles of BOX BRIDGE and APPROACHES

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 145+77.0	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	2,090.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	683.000	CY
CHANNEL EXCAVATION (FM)	257.000	CY
EXCESS EXCAVATION (FM)	300.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	466.000	CY
SIZE (I) STABILIZER AGGREGATE, COARSE	6.000	CY
HOT MIX ASPHALT, ST 12.5 MM	99.000	TON
HOT MIX ASPHALT, ST 19 MM	199.000	TON
CLASS "C" STRUCTURAL CONCRETE	60.000	CY
48" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL)	0.133	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MIL)	700.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	6.000	EA

EROSION CONTROL ITEMS:

	QUANTITY	UNIT
SOLID SODDING	175.000	SY
HYDROSEEDING	0.740	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20" DIAMETER	100.000	LF

BRIDGE ITEMS:

	QUANTITY	UNIT
TEMPORARY STREAM DIVERSION	1.000	EA
BOX BRIDGE CONCRETE, CLASS "BB"	272.530	CY
REINFORCEMENT	51,920.000	LB
LOOSE RIPRAP, 300 LB.	140.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.21-0.43 NON-WOVEN	350.000	SY