

## SECTION 900 - ADVERTISEMENT

### WASHINGTON COUNTY, MISSISSIPPI

Project No. CRSA-0616-00(002)/109113-701000

The Washington County Board of Supervisors, Washington County, Mississippi, will receive bids for the bridge replacement and approaches along Winterville-Priscilla Road for a total project length of 0.133 mile, Project No. CRSA-0616-00(002)/109113-701000 no later than 11:00 a.m., Local Time, January 30, 2026 at the Washington County Courthouse, Chancery Clerk's Office located at 900 Washington Avenue, Greenville, Mississippi. All bids so received will be publicly opened and read aloud.

The work shall consist essentially of the following items:

Removal and reconstruction of a precast concrete bridge along with improvements to the approach roadway.

The above general outline of features of the work does not in any way limit the responsibility of the contractor to perform all work and furnish all plant, labor, equipment and materials required by the specifications and the drawings referred to therein.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor. Minimum wage rates for Federal-Aid projects have been predetermined by the Secretary of Labor and are subject to Public Law 87-581 Work Hours Act of 1962, as set forth in the Contract Provisions.

The Washington County Board of Supervisors hereby notifies all Bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged and women's business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

The contract Documents are on file and may be examined at the following locations:

1. Washington County Courthouse, Office of the Chancery Clerk 900 Washington Avenue, Greenville, MS 38701
2. Hooker Engineering Services, Inc., 1000 Washington Avenue, Greenville, MS 38701

Each bid shall be accompanied by a Cashier's check, Certified Check on a solvent bank or a Bidder's Bond issued by a Surety Company licensed to operate in the State of Mississippi, in the amount of five percent (5%) of the total bid price, payable to the Washington County Board of Supervisors as bid security. Bidders shall also submit a current financial statement, if requested by the County. The successful bidder will be required to furnish a Performance Bond and a Payment bond each in the amount of one hundred percent (100%) of the contract amount.

The proposal and contract documents in its entirety shall be submitted in a sealed envelope and deposited with the Washington County Chancery Clerk, 900 Washington Avenue, Greenville, Mississippi 38701 prior to the hour and date above designated.

Printed copies of the Bidding Documents may be obtained from Hooker Engineering Services, Inc., 1000 Washington Avenue, Greenville, MS 38701, 662-334-1865, by paying a non-refundable deposit of \$125.00 for each set. Cost does not include shipping charges. Upon receipt of payment, printed Bidding Documents will be sent via the prospective Bidder's delivery service. The shipping charge amount will depend on the shipping method chosen.

For this project bids will also be received and accepted via the online electronic bid service through QuestCDN.com. Bidding documents can be downloaded under QuestCDN Project #10001880 at [www.questcdn.com](http://www.questcdn.com) for a non-refundable charge of \$42.00. Contact QuestCDN.com at 956-233-1632 or

## SECTION 900 - ADVERTISEMENT

### WASHINGTON COUNTY, MISSISSIPPI

Project No. CRSA-0616-00(002)/109113-701000

info@questcdn.com for assistance in free membership, viewing or downloading this digital project information. Online bidding will not be available until three (3) days prior to bid date.

Work to be performed shall be in accordance with the "Mississippi Standard Specifications for State Aid Road and Bridge Construction, 2004", together with all amendments and/or special provisions and/or addenda to the standards duly approved and adopted, unless otherwise noted in these specifications.

The attention of Bidders is directed to the provisions of Subsection S-102.07 pertaining to irregular proposals and rejection of bids.

PUBLISH: December 31, 2025 and January 7, 2026.

**SECTION 902 PROPOSAL (Bid Sheet No. 2-1)****PROJECT NUMBER:** CRSA-0616-00(002)/109113-701000**COUNTY:** WASHINGTON**PROJECT DESCRIPTION:** Bridge replacement and approaches along Winterville-Priscilla Road for a total project length of 0.133 mile.**I (We) agree to complete the entire project within 120 Working Days.****\*\*\* SPECIAL NOTICE TO BIDDERS \*\*\*****BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED.****BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATE LOCATED AT THE END OF THE BID SHEETS IS SIGNED**

<b>BID SCHEDULE</b>						
<b>LINE NO.</b>	<b>PAY ITEM NO.</b>	<b>PLAN QUANTITY</b>	<b>UNIT</b>	<b>DESCRIPTION</b>	<b>UNIT PRICE</b>	<b>ITEM TOTAL</b>
<b>ROADWAY ITEMS</b>						
10	S-200-A	1	LS	MOBILIZATION	XXXXXXXXXX	
20	S-201-A	1	LS	CLEARING AND GRUBBING	XXXXXXXXXX	
30	S-202-B	1	Unit	REMOVAL OF PRECAST BRIDGE (13+62)(4 @ 19' x 24' WIDE)	XXXXXXXXXX	
40	S-202-E	60	LF	REMOVAL OF PIPE (ALL SIZES)		
50	S-203-A	700	CY	UNCLASSIFIED EXCAVATION (FM)		
60	S-203-F	260	CY	CHANNEL EXCAVATION (FM)		
70	S-203-H	20	CY	EXCESS EXCAVATION (FM)		
80	S-304-D	1700	Ton	CRUSHED STONE 825 B		
90	S-603-M-A	60	LF	36" POLYMERIC COATED CORR. METAL PIPE, 14 GAGE, 3" CORRUGATION		
100	S-606-B	37.5	LF	GUARD RAIL, "W" BEAM, COMPLETE-IN-PLACE		
110	S-606-C	6.25	LF	GUARD RAIL, CABLE ANCHOR, TYPE 1		
120	S-606-D	4	EA	GUARD RAIL, BRIDGE END SECTION, TYPE "G", "W" BEAM		
130	S-606-E	3	EA	GUARD RAIL, TERMINAL END SECTIONS		
140	S-617-A	4	EA	RIGHT OF WAY MARKERS (TYPE II)		
150	S-618-A	1	LS	MAINTENANCE OF TRAFFIC	XXXXXXXXXX	
160	S-618-B	0	SF	ADDITIONAL CONSTRUCTION SIGNS		

## SECTION 902 PROPOSAL (Bid Sheet No. 2-2)

**PROJECT NUMBER:** CRSA-0616-00(002)/109113-701000

**COUNTY:** WASHINGTON

**PROJECT DESCRIPTION:** Bridge replacement and approaches along Winterville-Priscilla Road for a total project length of 0.133 mile.

170	S-621-C	0.035	MI	4" WIDE THERMOPLASTICE EDGE STRIPE (CONTINUOUS WHITE)(60 MIL)		
180	S-621-E-A	186	LF	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(90 MIL)		
190	S-630-C	4	EA	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)		
Subtotal Roadway Items						
EROSION CONTROL ITEMS						
200	901-S-212-A	1.50	Ton	AGRICULTURAL LIMESTONE		
210	S-212-B	0.75	Ton	COMMERCIAL FERTILIZER (13:13:13)		
220	S-214-A	0.75	AC	SEEDING		
230	S-215-A	2.25	Ton	VEGETATIVE MATERIALS FOR MULCH		
240	S-233-A	1362	LF	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)		
250	237-A	300	LF	WATTLES, 20"		
Subtotal Erosion Control Items						

**SECTION 902 PROPOSAL (Bid Sheet No. 2-3)****PROJECT NUMBER:** CRSA-0616-00(002)/109113-701000**COUNTY:** WASHINGTON**PROJECT DESCRIPTION:** Bridge replacement and approaches along Winterville-Priscilla Road for a total project length of 0.133 mile.

BRIDGE ITEMS						
260	S-803-A	2	EA	TEST PILE		
270	S-803-B	1	EA	CONVENTIONAL STATIC PILE LOAD TEST		
280	S-803-C	980	LF	18" PRESTRESSED CONCRETE PILING		
290	S-803-F	200	LF	22" PRE-FORMED PILE HOLE		
300	S-804-A	50	CY	BRIDGE CONCRETE, CLASS A		
310	S-805-A	8600	LB	REINFORCING STEEL		
320	S-806-A	12	EA	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR		
330	S-806-A	6	EA	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR		
340	S-806-C	6	EA	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR		
350	S-806-G	186	LF	PRECAST CONCRETE BARRIER RAIL		
360	S-815-A	210	Ton	LOOSE RIPRAP, 300 LB		
370	S-815-E	430	SY	GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43		
Subtotal Bridge Items						
TOTAL						