

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-02(01)
STRUCTURE NO. SA0200000000001 COUNTY ROAD 755
ALCORN COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-02(01) Alcorn County, MS. The Board of Supervisors of Alcorn County, MS will receive bids for the construction of **0.243 miles of Bridge and Approaches to replace Structure No. SA0200000000001 on County Road 755.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **10:00 AM on the 28th day of August, 2020** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Alcorn County Board of Supervisors Building, 305 S Fulton Drive, Corinth, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Alcorn County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Lowell Hinton, President
Alcorn County Board of Supervisors

Publish: 07-21-2020 & 07-28-2020

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-02(01) Structure No. SA0200000000001 County Road 755					
BASE BID ITEMS					
<u>Roadway Items</u>					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 36+05	1.00	UN	\$	\$
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	13,634.00	CY	\$	\$
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	3,215.00	SY	\$	\$
S-304-A	Granular Material (LVM)(Class 5, Group "C")	252.00	CY	\$	\$
S-304-C	Crushed Stone (3/4" & Down) (FM)	970.00	CY	\$	\$
S-603-C-A	24" Reinforced Concrete Pipe, Class III	40.00	LF	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$
S-617-A	Right Of Way Markers, Type II	14.00	EA	\$	\$
S-618-A	Maintenance of Traffic	1.00	LS	\$	\$
S-618-B	Additional Construction Signs	0.00	SF	\$ 10.00	\$ 0.00
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	2.00	EA	\$	\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	14.00	EA	\$	\$
<u>Erosion Control Items</u>					
901-S-212-A	Agricultural Limestone	6.50	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	3.25	TON	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-212-F	Ammonium Nitrate	0.81	TON	\$	\$
S-214-A	Seeding	3.25	AC	\$	\$
S-226-A	Solid Sodding	316.00	SY	\$	\$
S-227-A	Excelsior Blanket	15,730.00	SY	\$	\$
S-229-A	Portland Cement Concrete Paved Ditch	43.00	CY		
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	2,190.00	LF	\$	\$
234-F	Turbidity Barrier	350.00	LF	\$	\$
237-A	Wattles, 20"	400.00	LF	\$	\$
S-815-A	Loose Riprap, Size 300 Lb	40.00	TON	\$	\$
S-815-E	Geotextile Under Riprap (Type V) (AOS <0.43)	80.00	SY	\$	\$
Bridge Items 1 @ 40' - 1 @ 80' - 1 @ 100' - 1 @ 80' - 1 @ 80' - 1 @ 40' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Pile	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	0.00	EA	\$ 4000.00	\$ 0.00
S-803-C	18" Prestressed Concrete Piling	3,540.00	LF	\$	\$
S-803-F	30" Pre-formed Pile Hole	2,462.00	LF	\$	\$
901-S-804-A	Bridge Concrete, Class "A"	492.00	CY	\$	\$
901-S-804-C	40' Prestressed Concrete Beam, Type I+2	397.50	LF	\$	\$
901-S-804-C	80' Prestressed Concrete Beam, Type III	1,196.25	LF	\$	\$
901-S-804-C	100' Prestressed Concrete Beam, Type IV	498.75	LF	\$	\$
S-805-A	Reinforcement	89,784.00	LB	\$	\$
S-813-A	Concrete Railing	840.00	LF	\$	\$
S-815-A	Loose Riprap, Size 200 Lb	530.00	TON	\$	\$
S-815-E	Geotextile Under Riprap (Type V) (AOS <0.43)	980.00	SY	\$	\$
SUB-TOTAL BASE BID					\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
Additive Option 1					
S-310-D	Mixing, Shaping and Compaction	2,346.00	SY	\$	\$
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	355.00	TON	\$	\$
S-408-A	Asphalt for Prime Coat (AE-P or EA-1)	821.00	GAL	\$	\$
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.488	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	2,580.00	LF	\$	\$
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	19.00	EA	\$	\$
SUB-TOTAL ADDITIVE OPTION 1					\$

Additive Option 2					
S-606-B	Guardrail "W" Beam	50.00	LF	\$	\$
S-606-D	Guardrail, Bridge End Section , Type "I" Thrie Beam	4.00	EA	\$	\$
S-606-E	Guardrail, Terminal End Section	4.00	EA	\$	\$
SUB-TOTAL ADDITIVE OPTION 2					\$

TOTAL BID (BASE + ADDITIVE OPTION 1 + ADDITIVE OPTION 2)					\$
---	--	--	--	--	----