

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-09(01)
STRUCTURE NO. SA0900000000077 COUNTY ROAD 410
CHICKASAW COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-09(01) Chickasaw County, MS. The Board of Supervisors of Chickasaw County, MS will receive bids for the construction of **0.118 miles of Bridge and Approaches to Replace Structure No. SA0900000000077 on County Road 410.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **10:00 AM on the 30th day of July, 2020** and shortly thereafter publicly opened at the **Chickasaw County 1st District Office, One Pinson Square, Houston, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Chickasaw County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kyle Strong, Engineer of Record** of Cook Coggin Engineers, Inc., at www.cceplanroom.com upon payment of \$100.00, which is non-refundable. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at www.osarc.ms.gov/bid-calendar-erbf. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Russell Brooks, President
Chickasaw County Board of Supervisors

Publish: *July 1st & July 8th, 2020*

BID SCHEDULE

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit
ERBR-09(01) STRUCTURE NO. SA0900000000077 COUNTY ROAD 410			
BASE BID ITEMS			
Roadway Items			
S-200-A	Mobilization	1.00	LS
S-201-A	Clearing & Grubbing	1.00	LS
S-202-B	Removal of Existing Bridge @ Sta. 346+65	1.00	UN
S-202-D	Removal of Asphalt Pavement	1,262.00	SY
S-203-A	Unclassified Excavation (FM)	1,019.00	CY
S-203-H	Borrow Excavation (FME) (Contractor Furnished) (Class 9)	250.00	CY
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS < 0.43)	4,028.00	SY
S-304-A	Granular Material (FM) (Class 9, Group "B")	1,239.00	CY
S-304-A	Granular Material (LVM) (Class 5, Group "C")	109.00	CY
S-304-C	Crushed Stone (3/4" & Down) (FM)	890.00	CY
S-310-D	Mixing, Shaping and Compaction	1,500.00	SY
S-403-A	Hot Mix Asphalt, ST 9.5 mm	302.00	TON
S-408-A	Asphalt for Prime Coat (MC-70 or EA-1)	525.00	GAL
S-606-B	Guard Rail, "W" Beam	50.00	LF
S-606-D	Guard Rail, Bridge End Section, Type "I" Thrie Beam	4.00	EA
S-606-E	Guard Rail, Terminal End Section	4.00	EA
S-607-A	Roadway Construction Surveying	1.00	LS
S-618-A	Maintenance of Traffic	1.00	LS

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-618-B	Additional Construction Signs	-	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous Yellow) (60 mils)	0.237	MILE
S-621-D	4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mils)	0.118	MILE
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	265.00	LF
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	15.00	EA
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA
S-630-D	Reflectorized Traffic Deleneator Sign (Encapsulated Lens)	14.00	EA
<u>Erosion Control Items</u>			
901-S-212-A	Agricultural Limestone	4.70	TON
S-212-B	Commercial Fertilizer (13-13-13)	2.35	TON
S-212-F	Ammonium Nitrate	0.60	TON
S-214-A	Seeding	2.35	AC
S-215-A	Vegetative Materials for Mulch	4.70	TON
S-226-A	Solid Sodding	200.00	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,955.00	LF
237-A	Wattles, 20"	340.00	LF
S-815-A	Loose Riprap, 300 Lb	400.00	TON
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	740.00	SY
<u>Bridge Items STA. 49+03 - 1 @ 40'; 1 @ 100'; 1 @ 40' Prestressed Concrete Beams</u>			
S-607-B	Bridge Constuction Surveying	1.00	LS
S-803-A	Test Pile	1.00	EA
S-803-B	Conventional Static Pile Load Test	-	EA
S-803-E	10" Steel Piling	560.00	LF

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-803-F	12" Pre-formed Pile Holes	405.00	LF
901-S-804-A	Bridge Concrete, Class "B"	3.31	CY
S-805-A	Reinforcement	63.00	LB
S-806-A	19' Precast Concrete Slab Unit, 3.5' Interior	12.00	EA
S-806-A	31' Precast Concrete Slab Unit, 3.5' Interior	6.00	EA
S-806-C	19' Precast Concrete Slab Unit, 3.5' Exterior	4.00	EA
S-806-C	31' Precast Concrete Slab Unit, 3.5' Exterior	2.00	EA
S-806-G	Precast Concrete Barrier Rail	138.00	LF
S-806-I	31' Precast Concrete Cap, Intermediate Unit, Steel Pile	2.00	EA
S-806-J	31' Precast Concrete Cap, End Unit, Steel Pile	2.00	EA
S-806-M	9.25' Precast Concrete Wing	4.00	EA
S-815-A	Loose Riprap, 300 Lb	200.00	TON
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	375.00	SY