

CHICKASAW COUNTY
BOARD OF SUPERVISORS

SUMMARY OF QUANTITIES

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Chickasaw County Mississippi at the Board of Supervisors of Chickasaw County Mississippi at the Board Room, 1 Pinson Square, Houston, Mississippi, until 10 AM on the 11th day of May 2026 and shortly thereafter publicly opened for the construction of 0.072 miles of BRIDGE & APPROACHES on the Pittsboro St. (County Road 405) being known as Emergency Road And Bridge Repair Project No. ERBR-09(03) in Chickasaw County Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ROADWAY ITEMS:

	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF TANK CAR @11+38	1.000	UN
REMOVAL OF ASPHALT PAVEMENT (ALL TYPES) (ALL DEPTHS)	918.000	SY
BORROW EXCAVATION (FM) (CONTRACTOR FURNISHED) (CLASS 9)	962.000	CY
EXCESS EXCAVATION (FM)	912.000	CY
GEOTEXTILE STABILIZATION (TYPE V) (AOS <0.43) (NON-WOVEN)	759.000	SY
GRANULAR MATERIAL (FM), (CLASS 5, GROUP C)	10.000	CY
CRUSHED STONE SIZE 3/4" & DOWN (FM)	231.000	CY
ASPHALT, (ST) (9.5MM)	84.000	TON
ASPHALT, (ST), (12.5MM)	126.000	TON
ASPHALT FOR TACK COAT, (CBC-1H)	84.000	GAL
36 " REINFORCED CONCRETE PIPE, CLASS III	200.000	LF
36" REINFORCED CONCRETE PIPE, END SECTION	1.000	EA
GUARD RAIL, BRIDGE END SECTION, TYPE "I", "W" BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4 " - WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.148	MI
4 " - WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	760.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS)	8.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.300	TON
COMMERCIAL FERTILIZER (13-13-13)	0.300	TON

SEEDING	0.200	AC
VEGETATIVE MATERIALS FOR MULCH	1.000	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	400.000	LF
WATTLES, 20 "	80.000	LF

BRIDGE ITEMS:

TEST PILE, 12", STEEL	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
12" STEEL PILING	600.000	LF
16" PRE-FORMED PILE HOLES	200.000	LF
BRIDGE CONCRETE, CLASS "B"	7.000	CY
REINFORCEMENT	135.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5 ' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5 ' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, STEEL PILE,	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, STEEL PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	783.000	TON
GEOTEXTILE UNDER RIPRAP,(TYPE V, AOS 0.43) (NON-WOVEN)	1,159.000	SY

PROJECT NO. ERBR-09(03)
County Chickasaw

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Chickasaw County, Randy Hathcock, PE ,This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

Plans and Proposals may be secured from Randy Hathcock, County Engineer for Chickasaw County at www.esiplans.com. The cost is fifty dollars (\$50) for the plans and fifty dollars (\$50) for the proposal, non-refundable. Plans and Proposals may also be downloaded by Bidders for electronic bidding purposes ONLY. Questions regarding electronic bidding shall be directed to Planhouse Printing at (662)407-0193. Electronic bids will be received until the designated date and time via electronic online bid submission through www.esiplans.com. Electronic bond documents from the Surety must accompany the electronic bids. Submission of the proposal in its entirety is required.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Chickasaw County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Anderson McFarland, President

Chickasaw County Board of Supervisors

April 8th and April 15th