

SECTION 900
Bid Date: August 15, 2025

ERBR-12(03)
Clarke County, MS

The Clarke County Board of Supervisors will receive bids for a Bridge Replacement Project with Approaches on two separate sites being over Shubuta Creek, SA12-0006, and Prairie Branch, SA12-0010, on CR 250 described as Emergency Road and Bridge Repair Fund Project No. ERBR-12(03) no later than **10:00 a.m. Local Time, Friday August 15, 2025**, at the Board room at the Clarke County Courthouse located at 101 S Church Street, Quitman, Mississippi.

For the construction of: Site "A" 16' x 8' Box Bridge and Site "B" Prestressed Concrete Beam Span Bridge 1 @ 40 LF, 1 @ 60 LF, 1 @ 100 LF, 2 @ 40 LF with Approaches on 0.302 miles of County Road 250, District 2 Clarke County, MS, also known as Project No. ERBR-12(03).

Pay Item No.	Description	Approx. Quantity	Unit
Roadway Items			
S-200-A	Mobilization (Site "A")	1.0	L.S.
S-200-A	Mobilization (Site "A")	1.0	L.S.
S-201-A	Clearing and Grubbing (Site "A")	1.0	L.S.
S-201-A	Clearing and Grubbing (Site "B")	1.0	L.S.
S-202-B	Removal of Bridge (Sta. 56+32, Site "A") & (Sta. 125+35 Site "B")	2.0	Unit
S-202-D	Removal of Asphalt Pavement (All Depths)	1,902.0	Sq. Yd.
S-202-E	Removal of Pipe (All Sizes)	70.0	Lin. Ft.
S-203-A	Unclassified Excavation (F.M.)	2,338.0	Cu. Yd.
S-203-D	Muck Excavation (F.M.)	265.0	Cu. Yd.
S-203-E1	Borrow Excavation (F.M.E.)(Contractor Furnished)(Class 9)	12,053.0	Cu. Yd.
S-203-F	Channel Excavation (F.M.)	130.0	Cu. Yd.
247-A	Temporary Stream Diversion	1.0	Each
S-304-D	Crushed Stone (Size 825)	1,714.0	Ton
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	276.0	Ton
S-403-A	Hot Mix Asphalt, ST, 19 mm	670.0	Ton
S-603-C-A	18" Reinforced Concrete Pipe, Class III	112.0	Lin. Ft.
S-605-X-2	Filter Material For Filter Beds, Type A	477.0	Ton
S-606-B	Guard Rail, "W" Beam	75.0	Lin. Ft.
S-606-D	Guard Rail, Bridge End Section, Type "I", Thrie Beam	4.0	Each
S-606-E	Guard Rail, Terminal End Section	4.0	Each
S-607-A	Roadway Construction Surveying (Site "A")	1.0	L.S.
S-607-A	Roadway Construction Surveying (Site "B")	1.0	L.S.
S-618-A	Maintenance of Traffic (Site "A")	1.0	L.S.
S-618-A	Maintenance of Traffic (Site "B")	1.0	L.S.
S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.106	Mile
S-620-E-1	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	560.0	Lin. Ft.
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White)(90 mil)	0.500	Mile
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow)(90 mil)	2,640.0	Lin. Ft.
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	42.0	Each
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	2.0	Each
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	8.0	Each
630-F	Delineators, Guard Rail Bolt-On, White Double Sided	22.0	Each
S-815-E	Geotextile Under Bridge End Treatment, (AOS 0.21 - 0.43) Type V, Non-Woven	203.0	Sq. Yd.

SECTION 900
Bid Date: August 15, 2025

ERBR-12(03)
Clarke County, MS

Pay Item No.	Description	Approx. Quantity	Unit
Erosion Control Items			
S-212-A	Agricultural Limestone	6.00	Ton
S-212-B	Commercial Fertilizer (13:13:13)	3.00	Ton
S-214-A	Seeding	3.00	Acre
S-215-A	Vegetative Materials for Mulch	6.00	Ton
S-226-A	Solid Sodding	800.00	Sq. Yd.
S-229-A	Portland Cement Concrete Paved Ditch	9.00	Cu. Yd.
S-233-A	Temporary Silt Fence (Type II)(AOS 0.45 - 0.84)	3,518.0	L.F.
S-815-A	Loose Riprap, 200 Lb.	387.0	Ton
S-815-E	Geotextile Under Riprap, (AOS 0.21 - 0.43), Type V, Non-Woven	717.0	Sq. Yd.
226-A	Temporary Grassing	226.0	Acre
229-A	Erosion Mat	3.00	Sq. Yd.
237-A	Wattles, 12"	1,000.0	L.F.
Box Bridge Items			
901-S-804-B	Box Bridge Concrete, Class "BB"	208.0	Cu. Yd.
S-805-A	Reinforcement	42,097.0	LB.
Bridge Items			
S-803-A	Test Pile	2.0	Each
S-803-C	14" Prestressed Concrete Piling	1,450.0	Lin. Ft.
S-803-C	16" Prestressed Concrete Piling	275.0	Lin. Ft.
S-803-C	18" Prestressed Concrete Piling	990.0	Lin. Ft.
S-803-F	18" Preformed Pile Holes	985.0	Lin. Ft.
S-803-F	24" Preformed Pile Holes	708.0	Lin. Ft.
S-804-A	Bridge Concrete, Class "A"	317.76	Cu. Yd.
S-804-C	40' Prestressed Concrete Beam Type 1 + 2	596.25	Lin. Ft.
S-804-C	60' Prestressed Concrete Beam Type III	298.75	Lin. Ft.
S-804-C	100' Prestressed Concrete Beam Type IV	498.75	Lin. Ft.
S-805-A	Reinforcement	57,267.0	Lbs.
S-813-A	Concrete Railing	559.0	Lin. Ft.
S-815-A	Loose Riprap, 300 Lb.	871.0	Ton
S-815-E	Geotextile Under Riprap, (AOS 0.21 - 0.43), Type V, Non-Woven	1,699.0	Sq. Yd.

Contract Time: 200 Working Days