

FORREST COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Forrest County, Mississippi at the Forrest County Courthouse, Hattiesburg, Mississippi, until 10:00 A.M. on the 10th day of December and shortly thereafter publicly opened for the construction of 0.028 miles of BRIDGE REPLACEMENT on MAIN ST. in BROOKLYN, being known as Project No. ERBR-18(01) in Forrest County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS		
Mobilization	Lump Sum	Lump Sum
Clearing and Grubbing	Lump Sum	Lump Sum
Removal of Bridge @ Sta. 68+01	1.000	Unit
Removal of Asphalt Pavement, (All Depths)	253.000	Sq. Yd.
Borrow Excavation (FME) (Contractor Furnished) (Class 9)	303.000	Cu. Yd.
Granular Material (LVM) (Class 6, Group "C")	285.000	Cu. Yd.
Hot Mix Asphalt, ST, 9.5 mm Mixture	40.000	Ton
Hot Mix Asphalt, ST, 12.5 mm Mixture	84.000	Ton
Class B Structural Concrete	156.108	Cu. Yd.
Reinforcing Steel	24,106.000	Lb.
18" Reinforced Concrete Pipe, Class III	64.000	Lin. Ft.
18" Reinforced Concrete Pipe, End Section	2.000	Each
18" Branch Connection, Stub into Box Culvert	2.000	Each
18" Branch Connection, Sewer Penetration Through Box Culvert	2.000	Each
Roadway Construction Surveying	Lump Sum	Lump Sum
Right Of Way Markers, Type II	9.000	Each
Maintenance of Traffic	Lump Sum	Lump Sum
Additional Construction Signs	0.000	Sq. Ft.
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	0.056	Mile
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	300.000	Lin. Ft.
Two-Way Yellow Reflective Raised Markers	5.000	Each
EROSION CONTROL ITEMS		
Agricultural Limestone	0.400	Ton
Commercial Fertilizer (13-13-13)	0.200	Ton
Seeding	0.200	Acre

Vegetative Materials for Mulch	0.600	Ton
Temporary Silt Fence	300.000	Lin. Ft.
Wattles, 20"	300.000	Lin. Ft.
Temporary Stream Diversion	1.000	Each
Remove and Reset Rip Rap	72.000	Cu. Yd.
Loose Rip Rap 200 LB.	118.000	Ton
Geotextile Under Rip Rap, Type V, AOS 0.21 - 0.43	219.000	Sq. Yd.

NOTICE TO CONTRACTORS:

CONTRACT TIME:

90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Purchasing Clerk of Forrest County at 641 Main St., Hattiesburg, MS, and the County Engineer's office at 301 Second Ave. Hattiesburg, MS. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be downloaded from Central Bidding at www.centralbidding.com. Electronic bids may be submitted at www.centralbidding.com, but may be submitted in hard copy at the Office of the Purchasing Clerk. For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.



 David Hogan, President

Advertise: November 5, 2020
 November 12, 2020