

The Jones County Board of Supervisors will receive bids for a Bridge Replacement Project with Approaches on three structures being over Tallahala Creek, Tallahala Relief, and Reedy Branch, on Bush Dairy Road in Districts 1 & 2 also known as Emergency Road and Bridge Repair Fund Project No. ERBR-34(02) no later than 10:00 a.m. Local Time, Tuesday September 23, 2025 at the Boardroom of the Jones County Courthouse located at 415 North 5th Avenue, Laurel, MS.

For the construction of Site "A" Prestressed Concrete Beam Span Bridge 1 @ 31 LF, 2 @40 LF, 1 @110 LF, 1 @ 40 LF, 2 @31 LF; Site "B" Precast Concrete Span Bridge 3 @ 40 LF; Site "C" Precast Span Bridge 3 @ 40 LF on 0.700 miles of Bush Dairy Road, Districts 1 & 2 Jones County, MS.

Pay Item No.	Description	Approx. Quantity	Unit
ROADWAY ITEMS			
S-200-A	Mobilization	1.0	Lump Sum
S-201-A	Clearing and Grubbing	1.0	Lump Sum
S-202-A	Removal of Obstructions	1.0	Lump Sum
S-202-B	Removal of Bridge @ Sta. 20+84, Sta. 32+78, Sta. 42+76	3.0	Unit
S-202-D	Removal of Asphalt Pavement (All Depths)	4,541.0	Sq. Yd.
S-203-A	Unclassified Excavation (F.M.)	4,144.0	Cu. Yd.
S-203-E1	Borrow Excavation (F.M.E.)(Contractor Furnished) (Class 9)	6,862.0	Cu. Yd.
S-304-D	Crushed Stone, Size 825	3,744.0	Ton
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	709.0	Ton
S-403-A	Hot Mix Asphalt, ST, 12.5 mm	380.0	Ton
S-403-A	Hot Mix Asphalt, ST, 19 mm	1,140.0	Lin. Ft.
S-606-B	Guard Rail, "W" Beam, Complete-in-Place	450.0	Lin. Ft.
S-606-D	Guard Rail, Bridge End Section, Thrie Beam	12.0	Each
S-606-E	Guard Rail, Terminal End Section	12.0	Each
S-607-A	Roadway Construction Surveying	1.0	Lump Sum
S-618-A	Maintenance of Traffic	1.0	Lump Sum
S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.213	Mile
S-620-E-1	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	1,126.0	Lin. Ft.
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (90 mil)	1.168	Mile
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	6,289.0	Lin. Ft.
S-621-H-1	Thermoplastic Legend (White) (120 mil)	270.0	Lin. Ft.
S-627-J	Two-Way Clear Reflective High Performance Raised Markers	14.0	Each
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	92.0	Each
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	16.0	Each
S-630-B	Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	1.0	Each
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	12.0	Each
S-815-E	Geotextile Under Bridge End Treatment, (AOS 0.21 - 0.43)	399.0	Sq. Yd.
630-F	Delineators, 717 Guard Rail Bolt-On, White Double-Sided	66.0	Each
EROSION CONTROL ITEMS			
S-212-A	Agricultural Limestone	8.0	Ton
S-212-B	Commercial Fertilizer (13:13:13)	4.0	Ton
S-214-A	Seeding	4.0	Acre
S-215-A	Vegetative Materials for Mulch	8.0	Ton
S-226-A	Solid Sodding	200.0	Sq. Yd.

Pay Item No.	Description	Approx. Quantity	Unit
S-229-A	Portland Cement Concrete Paved Ditch	6.50	Cu. Yd.
S-233-A	Temporary Silt Fence (Type II)(AOS 0.15 - 0.84)	5,063.0	Lin. Ft.
226-A	Temporary Grassing	4.0	Acre
237-A	Wattles, 12"	500.0	Lin. Ft.
BRIDGE "A" ITEMS			
S-803-A	Test Pile	2.0	Each
S-803-C	14" Prestressed Concrete Piling	900.0	Lin. Ft.
S-803-C	16" Prestressed Concrete Piling	990.0	Lin. Ft.
S-803-C	18" Prestressed Concrete Piling	1,200.0	Lin. Ft.
S-803-F	18" Preformed Pile Holes	704.0	Lin. Ft.
S-803-F	24" Preformed Pile Holes	1,424.0	Lin. Ft.
S-804-A	Bridge Concrete, Class "A"	348.00	Cu. Yd.
S-804-C	31' Prestressed Concrete Beam Type 1 + 2	461.25	Lin. Ft.
S-804-C	40' Prestressed Concrete Beam Type 1 + 2	596.25	Lin. Ft.
S-804-C	110' Prestressed Concrete Beam Type IV	548.75	Lin. Ft.
S-805-A	Reinforcement	64,437.0	Lbs.
S-813-A	Concrete Railing	646.0	Lin. Ft.
S-815-A	Loose Riprap (300 Lb.)	440.0	Ton
S-815-E	Geotextile Under Riprap, Type V, (AOS 0.21 - 0.43)	878.0	Sq. Yd.
BRIDGE "B" ITEMS			
S-803-A	Test Pile	2.0	Each
S-803-C	14" Prestressed Concrete Piling	800.0	Lin. Ft.
S-803-F	18" Preformed Pile Holes	552.0	Lin. Ft.
S-806-A	40' Precast Concrete Slab Unit, 3.5' Interior	12.0	Each
S-806-A	40' Precast Concrete Slab Unit, 4.5' Interior	6.0	Each
S-806-A	40' Precast Concrete Slab Unit, 3.5' Exterior	6.0	Each
S-806-G	Precast Concrete Barrier Rail	240.0	Lin. Ft.
S-806-I	33.17' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.0	Each
S-806-J	33.17' Precast Concrete Cap, End Unit, Concrete Pile	2.0	Each
S-806-M	9.17' Precast Concrete Wing	4.0	Each
S-815-A	Loose Riprap (300 Lb.)	294.0	Ton
S-815-E	Geotextile Under Riprap, (AOS 0.21 - 0.43)	593.0	Sq. Yd.
BRIDGE "C" ITEMS			
S-803-A	Test Pile	2.0	Each
S-803-C	14" Prestressed Concrete Piling	850.0	Lin. Ft.
S-803-F	18" Preformed Pile Holes	599.0	Lin. Ft.
S-806-A	40' Precast Concrete Slab Unit, 3.5' Interior	12.0	Each
S-806-A	40' Precast Concrete Slab Unit, 4.5' Interior	6.0	Each
S-806-C	40' Precast Concrete Slab Unit, 3.5' Exterior	6.0	Each
S-806-G	Precast Concrete Barrier Rail	240.0	Lin. Ft.
S-806-I	33.17' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.0	Each
S-806-J	33.17' Precast Concrete Cap, End Unit, Concrete Pile	2.0	Each
S-806-M	9.17' Precast Concrete Wing	4.0	Each
S-815-A	Loose Riprap (300 Lb.)	359.0	Ton
S-815-E	Geotextile Under Riprap, (AOS 0.21 - 0.43)	723.0	Sq. Yd.

Contract Time: 180 Working Days