

NOTICE OF ADVERTISEMENT

PROJECT NO. ERBR-34(03)
JONES COUNTY, MS

The Jones County Board of Supervisors will receive bids on Tuesday, November 25, 2025 no later than 10:00 am in the board room of the Jones County Courthouse located at 415 North 5th Ave., Laurel, MS. The drawings and contract documents are on file and can be examined or purchased at the following locations: 415 North 5th Avenue, Laurel, MS 39441; Chas. N. Clark Associates, 714 Hillcrest Drive, Laurel, MS 39440; www.clarkengineersprojects.com.

For the construction of: Prestressed Concrete Beam Span Bridge 1 @ 31', 1 @ 60', 4 @ 40' with Approaches on 0.345 miles of County Road described as Pleasant Grove-Sandersville Road in Jones County, District 3, also known as ERBR-34(03).

Contract Time shall be One Hundred Forty (140) Working Days.

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
ROADWAY ITEMS				
1	S-200-A	Mobilization	1.0	Lump Sum
2	S-201-A	Clearing and Grubbing	1.0	Lump Sum
3	S-202-A	Removal of Obstructions	1.0	Lump Sum
4	S-202-B	Removal of Bridge @ Sta. 27+98	1.0	Unit
5	S-202-D	Removal of Pavement	3,846.0	Sq. Yd.
6	S-202-E	Removal of Pipe (All Sizes)	102.0	Lin. Ft.
7	S-203-A	Unclassified Excavation (F.M.)	3,821.0	Cu. Yd.
8	S-203-D	Muck Excavation (F.M.)	23.0	Cu. Yd.
9	S-203-E	Borrow Excavation (F.M.E.)(Contractor Furnished) (Class 9)	3,634.0	Cu. Yd.
10	S-304-D	Crushed Stone, Size 825	3,176.0	Ton
11	S-403-A	Hot Mix Asphalt, ST, 9.5 mm	407.0	Ton
12	S-403-A	Hot Mix Asphalt, ST, 19 mm	1,226.0	Ton
13	S-601-B	Class "B" Structural Concrete, Minor Structures	0.250	Cu. Yd.
14	S-603-C-A	15" Reinforced Concrete Pipe, Class III	64.0	Lin. Ft.
15	S-603-C-A	24" Reinforced Concrete Pipe, Class III	56.0	Lin. Ft.
16	S-603-C-B	24" Reinforced Concrete Pipe, End Section	2.0	Each
17	S-606-B	Guard Rail, "W" Beam	100.0	Lin. Ft.
18	S-606-D	Guard Rail, Bridge End Section, Type "I", Thrie Beam	4.0	Each
19	S-606-E	Guard Rail, Terminal End Section	3.0	Each
20	606-G	Special Sections, Short Radius Guard Rail	50.0	Lin. Ft.
21	S-607-A	Roadway Construction Surveying	1.0	Lump Sum
22	S-618-A	Maintenance of Traffic	1.0	Lump Sum
23	S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.095	Mile
24	S-620-E-1	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	502.0	Lin. Ft.
25	S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (90 mil)	0.596	Mile

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
26	S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	3,146.0	Lin. Ft.
27	S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	47.0	Each
28	S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	2.0	Each
29	S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	8.0	Each
30	630-F	Delineators, 717 Guard Rail Bolt-On, White Double Sided	22.0	Each
31	S-815-E	Geotextile Under Bridge End Treatment, Type V, Non-Woven	190.0	Sq. Yd.
EROSION CONTROL ITEMS				
32	S-212-A	Agricultural Limestone	7.2	Ton
33	S-212-B	Commercial Fertilizer (13:13:13)	3.6	Ton
34	S-214-A	Seeding	3.6	Acre
35	S-215-A	Vegetative Materials for Mulch	7.2	Ton
36	S-226-A	Solid Sodding	150.0	Sq. Yd.
37	S-229-A	Portland Cement Concrete Paved Ditch	5.055	Cu. Yd.
38	S-233-A	Temporary Silt Fence (Type II)(AOS - 0.15 - 0.84)	3,889.0	Lin. Ft.
39	S-237-A	Wattles, 12"	300.0	Lin. Ft.
40	226-A	Temporary Grassing	3.60	Acre
41	229-A	Erosion Mat	137.0	Sq. Yd.
BRIDGE ITEMS				
STA. 27+97: 1 @ 31 LF, 1 @ 60 LF, 4 @ 40 LF; Prestressed Concrete Beam Span 30° RT FWD Skew, 28' Clear Roadway Width				
42	S-803-A	Test Pile	2.0	Each
43	S-803-C	14" Prestressed Concrete Piling	1,670.0	Lin. Ft.
44	S-803-C	16" Prestressed Concrete Piling	700.0	Lin. Ft.
45	S-803-F	18" Preformed Pile Holes	1,015.0	Lin. Ft.
46	S-803-F	24" Preformed Pile Holes	354.0	Lin. Ft.
47	S-804-A	Bridge Concrete, Class "A"	293.12	Cu. Yd.
48	S-804-C	31' Prestressed Concrete Beam Type 1 + 2	153.75	Lin. Ft.
49	S-804-C	40' Prestressed Concrete Beam Type 1 + 2	795.0	Lin. Ft.
50	S-804-C	60' Prestressed Concrete Beam Type III	298.75	Lin. Ft.
51	S-805-A	Reinforcement	53,290.0	LBS.
52	S-813-A	Concrete Railing	502.0	Lin. Ft.
53	S-815-A	Loose Riprap, 300 Lb.	617.0	Ton
54	S-815-E	Geotextile Under Riprap, Type V, Non-Woven	1,199.0	Sq. Yd.