KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse located at 280 Veterans Street in DeKalb, Mississippi, until 10:00 a.m. on the 2nd day of December, 2026 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new 2 @ 40', 1 @ 80' and 1 @ 40' prestressed concrete beam span bridge with HMA approaches on the Kipling Road being known as Project No. ERBR-35(02) in Kemper County, Mississippi.

CONTRACT TIME: 100 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that, it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Phillip McDonald, Engineer for Kemper County, Mississippi, 1724B 23rd Avenue, Meridian, MS 39301(Phone 601-693-4234). The cost is fifty dollars ($50.00) for plans and fifty dollars ($50.00) for the proposal, which is non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Lee McDonald, President
Kemper County Board of Supervisors

Advert. 10/29/2026
11/05/2026

SECTION 902
PROPOSAL SHEET

ERBR-35(02) Kipling Road
SPECIAL NOTICE TO BIDDERS

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
		ROADWAY ITEMS						
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXX	XXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXX	XXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 130+87.00	1.000	UNIT				
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	89.000	C.Y.				
5	S-203-H	EXCESS EXCAVATION (FM)	517.000	C.Y.				
6	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	5.950	C.Y.				
7	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	300.000	C.Y.				
8	S-304-D	CRUSHED STONE, SIZE 610	110.000	C.Y.				
9	S-403-A	HOT MIX ASPHALT, ST, 12.5MM	65.000	TON				
10	S-403-A	HOT MIX ASPHALT, ST, 19MM	129.000	TON				
11	S-606-B	GUARDRAIL, W-BEAM	75.000	L.F.				
12	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA.				
13	S-606-E	GUARDRAIL, TERMINAL END SECTION	4.000	EA.				
14	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXX	XXXXXXXXXXX		
15	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
16	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.170	MILE				
17	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	900.000	L.F.				
18	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	7.000	EA.				
19	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
					ROADWAY ITEMS SUBTOTAL			
		EROSION CONTROL ITEMS						
20	S-226-A	SOLID SODDING	263.000	S.Y.				
21	S-227-A	EXCELSIOR BLANKET	500.000	S.Y.				
22	S-228-A	HYDROSEEDING	0.270	ACRE				
23	S-233-A	TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	750.000	L.F.				
24	S-235-A	WATTLES, 20"	200.000	L.F.				
25	S-815-A	LOOSE RIPRAP (200 LB.)	128.000	TON				
26	S-815-E	GEOTEXTILE UNDER 200 LB. RIPRAP, (TYPE V)(NON-WOVEN)(AOS<0.43)	300.000	S.Y.				
					EROSION CONTROL ITEMS SUBTOTAL			

SECTION 902
PROPOSAL SHEET

ERBR-35(02) Kipling Road
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
		BRIDGE ITEMS						
27	S-803-A	TEST PILES	2.000	EA.				
28	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA.	4,000	00		
29	S-803-C	14" PRESTRESSED CONCRETE PILING	1530.000	L.F.				
30	S-803-C	16" PRESTRESSED CONCRETE PILING	225.000	L.F.				
31	S-803-F	18" PRE-FORMED PILE HOLES	1350.000	L.F.				
32	S-803-F	20" PRE-FORMED PILE HOLES	175.000	L.F.				
33	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	224.490	C.Y.				
34	901-S-804-C	40 FT. PRESTRESSED CONCRETE BEAM, TYPE I + 2	596.250	L.F.				
35	901-S-804-C	80 FT. PRESTRESSED CONCRETE BEAM, TYPE III	398.750	L.F.				
36	S-805-A	REINFORCEMENT	39964.000	LB.				
37	S-813-A	CONCRETE RAILING	400.000	L.F.				
38	S-815-A	LOOSE RIPRAP (300 LB.)	344.000	TON				
39	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(NON-WOVEN)(AOS<0.43)	792.000	S.Y.				
					BRIDGE ITEMS SUBTOTAL			

TOTAL BASE BID		