

LAUDERDALE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lauderdale County, Mississippi at the Lauderdale County Courthouse Annex 11th Floor, Meridian, Mississippi, until 10:00 a.m. on Friday the 2nd day of June, 2023 and shortly thereafter publicly opened for the construction of 0.3 miles of BRIDGE & ROADWAY CONSTRUCTION on Dale Drive being known as Project No. ERBR-38(02) in Lauderdale County, Mississippi. Work involves removing existing concrete bridge and constructing a new 1@19', 1@31' and 1@19' precast concrete bridge and roadway improvements including widening. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction. Contractors have the option of submitting bids either electronically by Central Bidding, www.centralbidding.com or paper sealed bids addressed and delivered to the Lauderdale County Board of Supervisors, at the time and date noted above.

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

OFFICIAL BID DOCUMENTS may be secured from either of the following locations:

1. Richmond L. Alexander, Engineer for Lauderdale County Mississippi, at 1724-B 23rd Avenue, Meridian, MS 39301. The cost is fifty dollars (\$50.00) for the plans and fifty (\$50.00) for the proposal, non-refundable.
2. Download from Central Bidding at www.centralbidding.com. Electronic bids can be submitted at www.centralbidding.com. For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lauderdale County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Jonathan Wells, President
Lauderdale County Board of Supervisors

Advert. May 04, 2023
May 11, 2023

SECTION 902
PROPOSAL SHEET

ERBR-38(02) Dale Drive
SPECIAL NOTICE TO BIDDERS

PAGE 1 OF 3

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
BASE BID - ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 19+71.95	1.000	UNIT				
4	S-202-C	REMOVAL OF CURB	45.000	L.F.				
5	S-202-D	REMOVAL OF ASPHALT (ALL DEPTHS)	309.000	S.Y.				
6	S-202-D	REMOVAL OF CONCRETE (ALL DEPTHS)	47.000	S.Y.				
7	S-203-A	UNCLASSIFIED EXCAVATION (FM)	949.000	C.Y.				
8	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	1931.000	C.Y.				
9	S-203-H	EXCESS EXCAVATION (LVM)	899.000	C.Y.				
10	S-232-A	GEOTEXTILE FABRIC STABILIZATION, (TYPE V)(NON-WOVEN)	2621.000	S.Y.				
11	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	1040.000	C.Y.				
12	S-304-D	CRUSHED STONE, SIZE 610	1314.000	TON				
13	S-403-A	HOT MIX ASPHALT, MT, 9.5MM	602.000	TON				
14	S-403-A	HOT MIX ASPHALT, MT, 12.5MM	235.000	TON				
15	S-403-A	HOT MIX ASPHALT, MT, 19MM	283.000	TON				
16	S-403-B	HOT MIX ASPHALT, MT, 9.5MM, LEVELING	170.000	TON				
17	S-406-A	COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	813.000	S.Y.				
18	503-C	SAW CUT, ALL DEPTHS	241.000	L.F.				
19	S-603-C-A	18" REINFORCED CONCRETE PIPE, CLASS III	72.000	L.F.				
20	S-603-C-A	30" REINFORCED CONCRETE PIPE, CLASS III	96.000	L.F.				
21	S-603-C-B	30" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA.				
22	901-S-604-D	INLET REPAIR	2.000	EA.				
23	S-608-B	CONCRETE DRIVEWAY	31.000	S.Y.				
24	S-609-D	COMBINATION CONCRETE CURB AND GUTTER, TYPE 1	57.000	L.F.				
25	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA.				
26	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		
27	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
28	S-619-C	TEMPORARY 6" WIDE TRAFFIC STRIPE (CONTINUOUS WHITE)	350.000	L.F.				
29	S-619-D	TEMPORARY 6" WIDE TRAFFIC STRIPE (CONTINUOUS YELLOW)	3687.000	L.F.				
30	S-619-F	TEMPORARY DETAIL TRAFFIC STRIPE (4" EQUIVALENT LENGTH)(WHITE)	1110.000	L.F.				
31	S-621-C	6" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.784	MILE				
32	S-621-D	6" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW)(120 MIL)	0.455	MILE				

ERBR-38(02) Dale Drive
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 3

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
33	S-621-E-1	6" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	4284.000	L.F.				
34	S-621-G-1	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH)(WHITE)(90 MIL)	4172.000	L.F.				
35	S-621-G-2	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH)(YELLOW)(90 MIL)	653.000	L.F.				
36	S-621-H-1	THERMOPLASTIC LEGEND (WHITE)(120 MIL)	195.000	L.F.				
37	S-621-H-2	THERMOPLASTIC LEGEND (WHITE)(120 MIL)	720.000	S.F.				
38	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	304.000	EA.				
39	S-630-A	REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA.				
40	S-630-B	REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	4.000	EA.				
41	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
					ROADWAY ITEMS SUBTOTAL			
BASE BID - EROSION CONTROL ITEMS								
42	S-226-A	SOLID SODDING	190.000	S.Y.				
43	901-S-228-A	HYDROSEEDING	1.280	ACRE				
44	S-233-A	TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	500.000	L.F.				
45	237-A	WATTLES, 20"	200.000	L.F.				
46	S-815-A	LOOSE RIPRAP (200 LB.)	222.000	TON				
					EROSION CONTROL ITEMS SUBTOTAL			
BASE BID - BRIDGE ITEMS								
47	S-803-A	TEST PILES	2.000	EA.				
48	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA.	4,000	00		
49	S-803-C	14" PRESTRESSED CONCRETE PILING	1120.000	L.F.				
50	S-803-F	18" PRE-FORMED PILE HOLES	1010.000	L.F.				
51	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	34.600	C.Y.				
52	S-805-A	REINFORCEMENT	25042.000	LB.				
53	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	28.000	EA.				
54	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	14.000	EA.				
55	S-806-C	19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA.				
56	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA.				
57	S-806-G	PRECAST CONCRETE BARRIER RAIL	138.000	L.F.				
58	S-806-M	9.25' PRECAST CONCRETE WING	4.000	EA.				
59	S-815-A	LOOSE RIPRAP (300 LB.)	353.000	TON				
60	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(NON-WOVEN)(AOS<0.43)	850.000	S.Y.				
					BRIDGE ITEMS SUBTOTAL			

TOTAL BASE BID

ERBR-38(02) Dale Drive
SPECIAL NOTICE TO BIDDERS

PAGE 3 OF 3

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ADDITIVE ALTERNATE ITEMS								
61	S-202-D	REMOVAL OF ASPHALT (ALL DEPTHS)	142.000	C.Y.				
62	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	500.000	C.Y.				
63	S-203-H	EXCESS EXCAVATION (FM)	300.000	C.Y.				
64	S-226-A	SOLID SODDING	174.000	S.Y.				
65	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	8.000	C.Y.				
66	S-232-A	GEOTEXTILE FABRIC STABILIZATION, (TYPE V)(NON-WOVEN)	345.000	S.Y.				
67	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	322.000	C.Y.				
68	S-304-D	CRUSHED STONE, SIZE 610	192.000	TON				
69	S-403-A	HOT MIX ASPHALT, MT, 9.5MM	311.000	TON				
70	S-403-A	HOT MIX ASPHALT, MT, 12.5MM	28.000	TON				
71	S-403-A	HOT MIX ASPHALT, MT, 19MM	34.000	TON				
72	S-403-B	HOT MIX ASPHALT, MT, 9.5MM, LEVELING	50.000	TON				
73	S-406-A	COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	490.000	S.Y.				
74	503-C	SAW CUT, ALL DEPTHS	225.000	L.F.				
75	S-609-D	COMBINATION CONCRETE CURB AND GUTTER, TYPE 2	196.000	L.F.				
76	S-616-A	CONCRETE ISLAND PAVEMENT	17.000	S.Y.				
77	S-619-C	TEMPORARY 6" WIDE TRAFFIC STRIPE (CONTINUOUS WHITE)	792.000	L.F.				
78	S-619-D	TEMPORARY 6" WIDE TRAFFIC STRIPE (CONTINUOUS YELLOW)	1430.000	L.F.				
79	S-619-F	TEMPORARY DETAIL TRAFFIC STRIPE (4" EQUIVALENT LENGTH)(WHITE)	1322.000	L.F.				
80	S-619-G	TEMPORARY LEGEND (WHITE)	65.000	S.F.				
81	S-621-C	6" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.185	MILE				
82	S-621-E-1	6" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	1704.000	L.F.				
83	S-621-G-1	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH)(WHITE)(90 MIL)	5348.000	L.F.				
84	S-621-G-2	THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH)(YELLOW)(90 MIL)	648.000	L.F.				
85	S-621-H-2	THERMOPLASTIC LEGEND (WHITE)(120 MIL)	65.000	S.F.				
86	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	64.000	EA.				
87	S-630-A	REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	4.000	EA.				
88	S-630-B	REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	12.000	EA.				
89	S-815-A	LOOSE RIPRAP (200 LB.)	20.000	TON				

TOTAL ADDITIVE ALTERNATE