

SECTION 900 ADVERTISEMENT FOR BIDS

The City of Meridian will accept competitive sealed bids until **10:00 AM, Friday, June 20, 2025**, at City Hall Purchasing, 601 23rd Avenue, Meridian, Mississippi 39301 for the purpose of:

Grand Avenue Bridge Replacement Project No. ERBR-38-320(02)

Specifications may be obtained by contacting Brandon Bridges, Purchasing Agent at 601-485-1940, brandonbridges@meridianms.org, Bid specifications can also be downloaded from Central Bidding at www.centralbidding.com or Ph Bidding at www.phbidding.com or from the address above.

The City of Meridian is an equal opportunity employer and hereby notifies all bidders that it will affirmatively insure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, sex, age, disability or national origin in consideration for an award.

The City of Meridian reserves the right to reject any and or all bids, waive technicalities, informalities or irregularities in the bids received, solicit new bids or to choose that bid which is deemed to be in the best interest of the City of Meridian.

Brandon Bridges
Purchasing Agent

Publishing Dates: **05/21/2025**
05/28/2025

SECTION 902
PROPOSAL SHEET

ERBR-38-320(02) Grand Ave
SPECIAL NOTICE TO BIDDERS

PAGE 1 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 13+32.00	1.000	UNIT				
4	S-202-D	REMOVAL OF ASPHALT (ALL DEPTHS)	123.000	SQ. YD.				
5	S-202-D	REMOVAL OF CONCRETE (ALL DEPTHS)	55.000	SQ. YD.				
6	S-202-E	REMOVAL OF PIPE (ALL SIZES)	80.000	LIN. FT.				
7	S-203-A	UNCLASSIFIED EXCAVATION (FM)	845.000	CU. YD.				
8	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	500.000	CU. YD.				
9	S-203-H	EXCESS EXCAVATION (FM)	176.000	CU. YD.				
10	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	5.300	CU. YD.				
11	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	347.000	CU. YD.				
12	S-304-D	CRUSHED STONE, SIZE 610	135.000	CU. YD.				
13	S-403-A	HOT MIX ASPHALT, ST, 12.5MM	213.000	TON				
14	S-403-A	HOT MIX ASPHALT, ST, 19MM	549.000	TON				
15	S-601-A	CLASS "A" STRUCTURAL CONCRETE	2.120	CU. YD.				
16	S-601-B	CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	1.150	CU. YD.				
17	S-602-A	REINFORCING STEEL	286.000	LB.				
18	S-603-A	8" STEEL SEWER PIPE	229.000	LIN. FT.				
19	S-603-C	6" DUCTILE IRON WATER PIPE	40.000	LIN. FT.				
20	S-603-D	8" DUCTILE IRON WATER PIPE BRIDGE CROSSING WITH JOINT RESTRAINTS	224.000	LIN. FT.				
21	S-603-C-A	18" REINFORCED CONCRETE PIPE, CLASS III	104.000	LIN. FT.				
22	S-603-M-A	24" BITUMINOUS COATED CORRUGATED METAL PIPE	80.000	LIN. FT.				
23	S-603-S-E	6"-8" DUCTILE IRON MEGALUG FITTINGS (45 DEG., REDUCERS, ETC.)	4.000	EACH				
24	S-603-S-F	TIE TO EXISTING 6" DUCTILE IRON WATER LINE	2.000	EACH				
25	S-603-S-G	1" TAP ON BRIDGE CROSSING	1.000	EACH				
26	S-606-B	GUARDRAIL, W-BEAM	75.000	LIN. FT.				
27	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EACH				
28	S-606-E	GUARDRAIL, TERMINAL END SECTION	4.000	EACH				
29	S-613-E	ADJUSTMENT OF MANHOLE	2.000	EACH				
30	S-614-A	TEMPORARY PUMPING OF SEWAGE INCL. TEMP. PIPE AND TWO PUMPS	1.000	L.S.	XXXXXXXXXX	XXXXXXXXXX		

ERBR-38-320(02) Grand Ave
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
31	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
32	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SQ. FT.	10	00	0	00
33	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL.)	0.189	MILE				
34	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL.)	1000.000	LIN. FT.				
35	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	7.000	EACH				
36	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EACH				
ROADWAY ITEMS SUBTOTAL								
EROSION CONTROL ITEMS								
37	S-226-A	SOLID SODDING	261.000	SQ. YD.				
38	S-227-A	EXCELSIOR BLANKET	1000.000	SQ. YD.				
39	901-S-228-A	HYDROSEEDING	0.810	ACRE				
40	S-233-A	TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	1,750.000	LIN. FT.				
41	237-A	WATTLES, 20"	200.000	LIN. FT.				
42	S-815-A	LOOSE RIPRAP (200 LB.)	100.000	TON				
43	S-815-E	GEOTEXTILE UNDER 200 LB. RIPRAP, (TYPE V)(NON-WOVEN)(AOS<0.43)	300.000	SQ. YD.				
EROSION CONTROL ITEMS SUBTOTAL								
BRIDGE ITEMS								
44	S-803-A	TEST PILES	2.000	EACH				
45	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EACH	4,000	00		
46	S-803-C	14" PRESTRESSED CONCRETE PILING	800.000	LIN. FT.				
47	S-803-C	16" PRESTRESSED CONCRETE PILING	540.000	LIN. FT.				
48	S-803-C	18" PRESTRESSED CONCRETE PILING	990.000	LIN. FT.				
49	S-803-F	18" PRE-FORMED PILE HOLES	800.000	LIN. FT.				
50	S-803-F	20" PRE-FORMED PILE HOLES	444.000	LIN. FT.				
51	S-803-F	22" PRE-FORMED PILE HOLES	858.000	LIN. FT.				
52	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	300.040	CU. YD.				
53	901-S-804-C	31 FT. PRESTRESSED CONCRETE BEAM, TYPE I + 2	738.000	LIN. FT.				
54	901-S-804-C	100 FT. PRESTRESSED CONCRETE BEAM, TYPE IV	598.500	LIN. FT.				
55	S-805-A	REINFORCEMENT	53,627.000	LB.				
56	S-813-A	CONCRETE RAILING	672.000	LIN. FT.				
57	S-815-A	LOOSE RIPRAP (300 LB.)	369.000	TON				
58	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(NON-WOVEN)(AOS<0.43)	925.000	SQ. YD.				
BRIDGE ITEMS SUBTOTAL								
					TOTAL BID			