

The following is my (our) itemized proposal for PROJECT NO. ERBR-43(04) N. JACKSON STREET, BROOKHAVEN, MISSISSIPPI.

All quantities are estimated by the Engineer. Final quantities will be determined at the conclusion of the project.

Unit prices are to be provided in figures. All erasures, changes or alterations of any kind must be initialized by the bidder.

Unit prices shall include all labor, materials, equipment, supervision, bailing, shoring, removal, overhead, profit, insurance, etc., to cover the finished work of the several kinds called for. Bids shall include sales tax and all other applicable taxes and fees.

### Bid Form

Pay Item No.	Pay Item	Totals			
		Unit	Plan	Unit Price	Amount
	<u>Roadway Items</u>				
S-200-A	Mobilization	LS	1		
S-201-A	Clearing and Grubbing	LS	1		
S-202-B	Removal of Bridge	UN	1		
S-202-B	Removal of Inlet	UN	1		
S-202-D	Removal of Asphalt	SY	506		
S-202-E	Removal of Pipe (All Sizes)	LF	50		
S-203-A	Unclassified Excavation (FM)	CY	68		
S-203-E	Borrow Excavation (Contractor Furnished) LVM, Class 7	CY	300		
S-203-H	Excess Excavation (LVM)	CY	700		
S-206-A	Structure Excavation	CY	500		
S-208-C	Light Linear Special	LF	50		
S-304-A	Granular Material (LVM), (Class 4, Group B)	CY	500		
S-304-C	Crushed Stone 610, LVM		200		
S-403-A	Hot Mix Asphalt, ST 9.5mm	Ton	70		
S-403-A	Hot Mix Asphalt, ST 19mm	Ton	135		
S-603-C-A	12" Reinforced Concrete Pipe, Class III	LF	24		
S-603-C-A	48" Reinforced Concrete Pipe, Class III	LF	72		
S-605-X-1	Filter Material for Filter Beds, Type A	CY	400		
S-617-A	Right-of-Way Markers (II)	EA	9		
S-618-A	Maintenance of Traffic	LS	1		
S-618-B	Additional Construction Signs	SF	0	\$10.00	\$0.00
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mil)	MI	0.093		
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	LF	490		
S-630-C	Reflectorized Traffic Object Markers (Encapsulated Lens) (Type 3)	EA	4		
	<u>Erosion Control Items</u>				
S-212-B	Commercial Fertilizer (13-13-13)	Ton	0.24		

S-214-A	Seeding	Acre	0.24		
S-215-A	Vegetative Materials for Mulch	Ton	0.72		
S-226-A	Solid Sod	SF	1,000		
229-A	Erosion Mat	SY	134		
S-233-A	Temporary Silt Fence (Type II) (AOS 0.15-0.84)	LF	700		
237-A	Wattles, 20 inch	LF	160		
S-815-A	Loose Riprap, 300 Lb.	Ton	300		
S-815-E	Geotextile under Riprap, Type V, AOS 0.21-0.43	SY	435		
	<b><u>Bridge Items</u></b>				
901-S-804-B	Box Bridge Concrete, Class "BB"	CY	121		
S-805-A	Reinforcement	LB	21,750		
S-806-A	31' Precast Concrete Slab Unit, 3'-6" Interior	EA	5		
S-806-B	31' Precast Concrete Slab Unit, Curb	EA	2		
S-806-H	Beam Type Railing with Concrete Post	LF	62		
<b>Total Amount:</b>					

THE CITY OF BROOKHAVEN reserves the right to reject any or all bids.

I (We) further propose to execute the Contract Agreement as bound herein within ten calendar days after receipt of Contract Forms from the Owner. I (We) further propose to complete the construction within ninety (90) working days from the date of the Notice to Proceed. I (We) agree to pay as liquidated damages the sum of \$250.00 for each consecutive working day thereafter as provided in the Contract Documents.

In addition to the amounts provided for liquidated damages, Contractor, in the event of such default, shall pay to the Owner the actual costs reasonably incurred by Owner for engineering and inspection forces employed on the work after the time stipulated for completion of the work.

I, (We) also propose to execute a Performance Bond and a Payment Bond, as shown in the Specifications, each in an amount of not less than 100 percent of the total of my (our) Bid. These Bonds shall not only serve to guarantee the completion of the Work on my (our) part, but also to guarantee the excellence of both workmanship and materials until the Work is finally accepted.

Bidder acknowledges receipt of the following Addenda:

No. \_\_\_\_\_ Dated \_\_\_\_\_ No. \_\_\_\_\_ Dated \_\_\_\_\_  
 No. \_\_\_\_\_ Dated \_\_\_\_\_ No. \_\_\_\_\_ Dated \_\_\_\_\_