

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
REBID PROJECT NO. ERBR-48(01)
BARTAHATCHIE ROAD BRIDGE NO. 136
MONROE COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: REBID Project No. ERBR-48(01) Monroe County, MS. The Board of Supervisors of Monroe County, MS will receive bids for the construction of **0.189 miles of Bridge and Approaches to Replace Bridge No. 136 on Bartahatchie Road.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **9 AM on the 23rd day of February, 2024** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Monroe County Chancery Building, 201 West Commerce Street, Aberdeen, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Monroe County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kyle Strong, Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ruble West, President
Monroe County Board of Supervisors

Publish: *January 24 & 31, 2024*

REBID PROJECT NO. ERBR-48(01)
BID ITEMS

Item No.	Item Description	Estimated Quantity	Unit
REBID ERBR-48(01) SA480000000136			
BASE BID ITEMS			
Roadway Items			
S-200-A	Mobilization	1.000	LS
S-201-A	Clearing & Grubbing	1.000	LS
S-202-B	Removal of Existing Bridge @ Sta. 114+75	1.000	UNIT
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9-6)	1,125.000	CY
S-203-H	Excess Excavation (LVM)	707.000	CY
S-232-A	Geotextile Under Roadway (Type V) (Non-Woven) (AOS <0.43)	2,650.000	SY
S-304-A	Granular Material (LVM) (Class 5, Group "C")	148.000	CY
S-304-C	Crushed Stone (3/4" & Down) (FM)	668.000	CY
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	210.000	TON
S-408-A	Asphalt for Prime Coat (EA-1) OR (AE-P)	480.000	GAL
S-606-B	Guardrail "W" Beam	200.000	LF
S-606-D	Guardrail Bridge End Section, Type I, Thrie Beam	4.000	EA
S-606-E	Guardrail, Terminal End Section	4.000	EA
901-S-607-A	Roadway Construction Surveying	1.000	LS
907-S-618-D	Construction and Removal of Detour	1.000	LS
S-618-A	Maintenance of Traffic	1.000	LS
S-618-B	Additional Construction Signs	-	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.377	MI
S-621-D	4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 Mils)	0.189	MI
S-621-H-1	Thermoplastic Legend (White) (120 Mil) (24" Wide)	24.000	LF
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	14.000	EA
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	4.000	EA
S-630-B	Reflectorized Traffic Regulatory Sign (Encapsulated Lens)	1.000	EA
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.000	EA

BID ITEMS

Item No.	Item Description	Estimated Quantity	Unit
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	14.000	EA
<u>Erosion Control Items</u>			
901-S-212-A	Agricultural Limestone	1.20	TON
S-212-B	Commercial Fertilizer (13-13-13)	0.60	TON
S-212-F	Ammonium Nitrate	0.15	TON
S-214-A	Seeding	0.60	AC
S-215-A	Vegetative Materials for Mulch	1.20	TON
S-226-A	Solid Sodding	100.000	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,300.000	LF
234-F	Turbidity Barrier	330.000	LF

BID ITEMS

Item No.	Item Description	Estimated Quantity	Unit
Bridge Items 40' - 100' - 100' - 150' - 100' - 40' - 31' Prestressed Concrete Beam Spans			
901-S-607-B	Bridge Constuction Surveying	1.00	LS
S-803-A	Test Pile	4.00	EA
S-803-B	Conventional Static Pile Load Test	-	EA
S-803-C	14" Prestressed Concrete Piling	850.00	LF
S-803-C	18" Prestressed Concrete Piling	2,600.00	LF
S-803-F	18" Pre-Formed Pile Holes	750.00	LF
S-803-F	24" Pre-Formed Pile Holes	1,970.00	LF
901-S-804-A	Bridge Concrete, Class "A"	594.00	CY
901-S-804-C	31' Prestressed Concrete Beam Type I+2	154.00	LF
901-S-804-C	40' Prestressed Concrete Beam Type I+2	398.00	LF
901-S-804-C	100' Prestressed Concrete Beam, Type IV	1,496.00	LF
901-S-804-C	150' Prestressed Concrete Beam, FIB-63	749.00	LF
S-805-A	Reinforcement	104,584.00	LB
S-813-A	Concrete Railing	1,122.00	LF
S-815-A	Loose Riprap, 300 Lb	975.00	TON
S-815-E	Geotextile Under Riprap, (Type V), Non Woven, AOS <0.43	950.00	SY