

NOXUBEE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Noxubee County, Mississippi at the Noxubee County Courthouse, Macon, Mississippi, until 10:00 a.m. on the 1st day of March, 2021 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new Double 14' x 8' Box Bridge within a 550' project on the Butler Road being known as Project No. ERBR-52(02) in Noxubee County, Mississippi.

CONTRACT TIME: 90 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Noxubee County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Noxubee County, Mississippi, 1724B 23rd Avenue, Meridian, MS 39301. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Noxubee County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ James Eddie Coleman, President
Noxubee County Board of Supervisors

Advert. January 28, 2021
February 4, 2021

SECTION 902
PROPOSAL SHEET

ERBR-52(02) Butler Road
SPECIAL NOTICE TO BIDDERS

PAGE 1 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 36+40	1.000	UNIT				
4	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	6,039.000	C.Y.				
5	S-203-D	MUCK EXCAVATION (F.M.)	390.000	C.Y.				
6	247-A	TEMPORARY STREAM DIVERSION (FOR BOX BRIDGE)	1.000	EA.				
7	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	1,691.000	C.Y.				
8	S-310-A-1	SIZE I STABILIZER AGGREGATE, COARSE	133.000	C.Y.				
9	901-S-401-A	HOT MIX ASPHALT BASE COURSE (BB-1)	182.000	TON				
10	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	102.000	TON				
11	S-605-X-1	FILTER MATERIAL FOR FILTER BEDS, TYPE C (F.M.E.)	290.000	C.Y.				
12	S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA.				
13	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
14	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
15	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.208	MILE				
16	S-621-D	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW)(120 MIL)	0.104	MILE				
17	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	165.000	L.F.				
ROADWAY ITEMS SUBTOTAL								
EROSION CONTROL ITEMS								
18	901-S-212-A	AGRICULTURAL LIMESTONE	4.200	TON				
19	S-212-B	COMMERCIAL FERTILIZER (13:13:13)	1.100	TON				
20	S-212-F	AMMONIUM NITRATE	0.300	TON				
21	S-214-A	SEEDING	2.200	ACRE				
22	S-215-A	VEGETATIVE MATERIALS FOR MULCH	4.400	TON				
23	S-226-A	SOLID SODDING	86.000	S.Y.				
24	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,366.000	L.F.				
25	237-A	WATTLES, 20"	240.000	L.F.				
26	S-239-A	TEMPORARY SLOPE DRAINS	280.000	L.F.				
27	S-815-A	LOOSE RIPRAP, 100 LB.	220.000	TON				

SECTION 902
PROPOSAL SHEET

ERBR-52(02) Butler Road
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
EROSION CONTROL ITEMS (CONTINUED FROM PAGE 1)								
28	S-815-A	LOOSE RIPRAP, 300 LB.	273.000	TON				
29	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, TYPE V, AOS 0.21-0.43	214.000	S.Y.				
					EROSION CONTROL ITEMS SUBTOTAL			
BOX BRIDGE ITEMS								
30	901-S-804-B	BOX BRIDGE CONCRETE, CLASS "BB"	204.940	C.Y.				
31	S-805-A	REINFORCEMENT	37,184.000	LB.				
					BOX BRIDGE ITEMS SUBTOTAL			
					TOTAL BASE BID			

ADDITIVE ALTERNATE								
32	S-601-B	CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	6.460	C.Y.				
					TOTAL BASE BID & ADDITIVE ALTERNATE			