

SHARKEY COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Sharkey County, Mississippi at the Sharkey County Courthouse, Rolling Fork, Mississippi, until 10:00 am on the 7th day of December 2020 and shortly thereafter publicly opened for the construction of 0.085 miles of BRIDGE REPLACEMENT AND APPROACHES on the OMEGA ROAD being known as Project No. ERBR-63(01) in Sharkey County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of SHARKEY County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sharkey County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

William Newsom, President
Sharkey County Board of Supervisors

Advertise: November 5, 2020
November 12, 2020

SECTION 902
PROPOSAL SHEET

Project No. ERBR-63(01)
Sharkey County , Mississippi

For the construction of: 0.085 miles of Bridge Replacement and Approaches on Omega Road, Sharkey County, MS

I (We) agree to complete the entire project within 120 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE STA. 14+97	1	Unit		
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	100	Cu.Yd.		
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	1400	Cu.Yd.		
6	S-203-F	CHANNEL EXCAVATION (FM)	310	Cu.Yd.		
7	S-304-D	CRUSHED STONE	550	Ton		
8	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	8	Each		
9	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
10	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
11	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4	Each		
Subtotal Roadway Items:						

SECTION 902
PROPOSAL SHEET

Project No. ERBR-63(01)
Sharkey County , Mississippi

Erosion Control Items						
12	901-S-212-A	AGRICULTURAL LIMESTONE	2	Ton		
13	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	1	Ton		
14	S-214-A	SEEDING	1	Acre		
15	S-215-A	VEGETATIVE MATERIALS FOR MULCH	3	Ton		
16	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	905	Lin.Ft.		
17	907-237-A	WATTLES, 20"	100	Lin.Ft.		
Subtotal Erosion Control Items:						
Bridge Items						
18	S-803-A	TEST PILE	2	Each		
19	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		
20	S-803-C	14" PRESTRESSED CONCRETE PILING	1000	Lin.Ft.		
21	S-803-F	18" PRE-FORMED PILE HOLE	200	Lin.Ft.		
22	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12	Each		
23	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	6	Each		
24	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6	Each		
25	S-806-G	PRECAST CONCRETE BARRIER RAIL	186	Lin.Ft.		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-63(01)
Sharkey County , Mississippi

26	S-806-I	33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2	Each		
27	S-806-J	33' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2	Each		
28	S-806-M	9.25' PRECAST CONCRETE WING	4	Each		
29	S-815-A	LOOSE RIPRAP, 300 LB.	300	Ton		
30	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	500	Sq. Yd.		
Subtotal Bridge Items:						
Total Bid:						