#### SIMPSON COUNTY BOARD OF SUPERVISORS

#### SECTION 900

## **NOTICE TO CONTRACTORS:**

Sealed bids will be received by the Board of Supervisors of Simpson County, Mississippi at the Simpson County Courthouse, Mendenhall, Mississippi, until 9:00 a.m. on the 15<sup>th</sup> day of July, 2019 and shortly thereafter publicly opened for the construction of 0.028 miles of BRIDGE REHABILITATION on the ROCKPORT-NEW HEBRON road being known as Project No. ERBR-64(02) in Simpson County, Mississippi.

## PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS		
MOBILIZATION	LUMP SUM	LS
UNCLASSIFIED EXCAVATION (FM)	105.00	CY
BORROW EXCAVATION (F.M.E.)	150.000	CY
(CONTRACTOR FURNISHED)(CLASS 9)		
GRANULAR MATERIAL, (LVM),	125.000	CY
(CLASS 5, GROUP C)		
HOT MIX ASPHALT, ST. 12.5mm	18.000	TON
HOT MIX ASPHALT, ST. 19 mm	32.000	TON
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.064	MI
(CONTINUOUS WHITE)(60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	340.000	LF
STRIPE (CONTINUOUS YELLOW)(90 MILS)		
REFLECTORIZED TRAFFIC OBJECT MARKER	4.00	EA
(ENCAPSULATED LENS)(TYPE 3)		
EROSION CONTROL ITEMS:		
COMMERCIAL FERTILIZER (13-13-13)	0.200	TON
AMMONIUM NITRATE	0.020	TON
SEEDING	0.050	AC
VEGETATIVE MATERIALS FOR MULCH	0.200	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.8	4) 100.000	LF
WATTLES, 20"	80.00	LF

# **BRIDGE ITEMS:**

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,500.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
19' PRECAST CONCRETE SLAB UNIT,	25.000	EA
3'-6' INTERIOR (SALVAGE AND REINSTALLATION)		
31' PRECAST CONCRETE SLAB UNIT,	5.000	EA
3'-6' INTERIOR (SALVAGE AND REINSTALLATION)		
19' PRECAST CONCRETE SLAB UNIT, CURB UNIT	10.000	EA
(SALVAGE AND REINSTALLATION)		
31' PRECAST CONCRETE SLAB UNIT, CURB UNIT	2.000	EA
(SALVAGE AND REINSTALLATION)		
BEAM TYPE RAILING WITH	252.00	EA
CONCRETE POSTS (SALVAGE AND REINSTALLATION)		
25.5' PRECAST CONCRETE CAP	5.000	EA
INTERMEDIATE UNIT, CONCRETE PILE		
25.5' PRECAST CONCRETE CAP,	2.000	EA
END UNIT, CONCRETE PILE		
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	295.000	TON
GEOTEXTILE UNDER LOOSE RIPRAP	680.000	SY
TYPE V, AOS 0.21-0.43		

NOTICE TO CONTRACTORS:

CONTRACT TIME:

60 Working Days

**BASIS OF AWARD** 

The award, if made, will be to the lowest qualified bidder on the basis of the published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notified all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for this award.

PLANS AND SPECIFICATIONS are on file at the office of the Project Engineer. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Wolverton Engineering, Inc., Project Engineer, at 57 Wolverton Drive, Collins, Mississippi. The Cost is one hundred dollars (\$ 100.00) for plans and one hundred dollars (\$ 100.00) for the proposal non –refundable.

Certified check or bid bond for five percent (%5) of the total bid, made payable to Simpson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied the letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Mickey Berry, President Simpson County Board of Supervisors

Advertise: June 12, 2019

June 19, 2019