

SIMPSON COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Simpson County, Mississippi at the Simpson County Courthouse, Mendenhall, Mississippi, until 9:00 a.m. on the 6th day of February, 2023 and shortly thereafter publicly opened for the construction of 0.057 miles of BRIDGE REHABILITATION on the HARRISVILLE - BRAXTON Road being known as Project No. ERBR-64(04) in Simpson County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
UNCLASSIFIED EXCAVATION (FM)	105.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED)(CLASS 9)	150.000	CY
GRANULAR MATERIAL, (LVM), (CLASS 5, GROUP C)	125.000	CY
HOT MIX ASPHALT, ST. 12.5mm	18.000	TON
HOT MIX ASPHALT, ST. 19 mm	32.000	TON
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(60 MIL)	0.114	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	600.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
COMMERCIAL FERTILIZER (13-13-13)	0.200	TON
AMMONIUM NITRATE	0.020	TON
SEEDING	0.050	AC
VEGETATIVE MATERIALS FOR MULCH	0.200	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	100.000	LF
WATTLES, 20"	80.000	LF

SECTION 900
 PROJECT NO. ERBR-64(04)
 SIMPSON COUNTY, MS

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,220.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
25.5' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	5.000	EA
25.5' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
PRECAST CONCRETE WING	4.000	EA
19' PRECAST CONCRETE SLAB UNIT 3.5' INTERIOR (SALVAGE & REINSTALLATION)	25.000	EA
31' PRECAST CONCRETE SLAB UNIT 3.5' INTERIOR (SALVAGE & REINSTALLATION)	5.000	EA
19' PRECAST COCNRETE SLAB UNIT CURB (SALVAGE & REINSTALLATION)	10.000	EA
31' PRECAST CONCRETE SLAB UNIT CURB (SALVAGE & REINSTALLATION)	2.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS (SALVAGE & REINSTALLATION)	252.0000	LF
LOOSE RIPRAP, 300 LB.	210.000	TON
GEOTEXTILE FABRIC UNDER LOOSE RIPRAP TYPE V, AOS 0.21-0.43	600.000	SY

NOTICE TO CONTRACTORS:

PROJECT NO. ERBR-64(04)
SIMPSON COUNTY, MS

CONTRACT TIME: 70 Working Days

BASIS OF AWARD

The award, if made, will be to the lowest qualified bidder on the basis of the published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notified all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for this award.

PLANS AND SPECIFICATIONS are on file at the office of the Project Engineer. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Wolverton Engineering, Inc., Project Engineer, at 57 Wolverton Drive, Collins, Mississippi. The Cost is one hundred dollars (\$ 100.00) for plans and one hundred dollars (\$ 100.00) for the proposal non –refundable.

Certified check or bid bond for five percent (%5) of the total bid, made payable to Simpson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied the letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Brian Kennedy, President
Simpson County Board of Supervisors

Advertise: December 29, 2022
January 5, 2023