

# SMITH COUNTY BOARD OF SUPERVISORS

## SECTION 900

### NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Smith County, Mississippi at the Smith County Courthouse, Raleigh, Mississippi, until 10:00 a.m. on the 5th day of October, 2020 and shortly thereafter publicly opened for the replacement of a deficient bridge with new Prestressed Concrete Beam Span structure and paved approaches on County Road 19 (Spring Street) being known as Project No. ERBR-65(01) in Smith County, Mississippi. Work involves removing existing precast concrete bridge and construction of a new 3@40' prestressed concrete beam bridge.

CONTRACT TIME: 110 Working Days

### BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Smith County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Smith County, Mississippi, 1724B 23<sup>rd</sup> Avenue, Meridian, MS 39301. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Smith County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Dwight Norris, President  
Smith County Board of Supervisors

Advert. September 3, 2020  
September 10, 2020

Proposal (Page 1)

For the Construction of: Prestressed Concrete Beam Span Bridge and Paved Approaches on 0.075 mile(s) of county road known as COUNTY ROAD 19 (SPRING STREET) in Smith County, Mississippi.

I (We) agree to complete the entire project within 110 Working Days.

\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

**BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED**

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED								
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>BASE BID</b>								
<b>ROADWAY ITEMS</b>								
1	S-200-A	MOBILIZATION	1.00	LS	XXXXXXXXXX	XXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.00	LS	XXXXXXXXXX	XXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 13+05.61	1.00	UNIT				
4	S-203-A	UNCLASSIFIED EXCAVATION (F.M.)	300.00	C.Y.				
5	S-203-E1	BORROW EXCAVATION (FME)(CONTRACTOR FURNISHED)(CLASS 9)	150.00	C.Y.				
6	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	357.000	C.Y.				
7	901-S-401-A	HOT BITUMINOUS PAVEMENT BASE COURSE (BB-1)	62.000	TON				
8	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	64.000	TON				
9	S-606-B	GUARD RAIL, W-BEAM	75.000	L.F.				
10	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA.				
11	S-606-E	GUARD RAIL, TERMINAL END SECTIOIN	4.000	EA.				
12	S-618-A	MAINTENANCE OF TRAFFIC	1.000	LS	XXXXXXXXXX	XXXXXXXXXX		
13	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00		
14	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.181	MILE				
15	S-621-E-1	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS YELLOW)(120 MIL)	1000.000	L.F.				
16	S-627-L	TWO-WAY YELLOW RELFLECTIVE HIGH PERFORMANCE RAISED MARKERS	15.000	EA.				
17	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
<b>Subtotal Roadway Items</b>								
<b>EROSION CONTROL ITEMS</b>								
18	901-S-212-A	AGRICULTURAL LIMESTONE	1.440	TON				
19	S-212-B	COMMERCIAL FERTILIZER (13:13:13)	0.720	TON				
20	S-212-F	AMMONIUM NITRATE	0.110	TON				
21	S-214-A	SEEDING	0.720	ACRE				
22	S-215-A	VEGETATIVE MATERIALS FOR MULCH	2.160	TON				
23	S-226-A	SOLID SODDING	135.520	S.Y.				
24	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	3.000	C.Y.				
25	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,020.000	L.F.				
26	237-A	WATTLES, 20"	100.000	L.F.				
27	S-815-A	LOOSE RIPRAP, 200 LB	178.000	TON				
28	S-815-E	GEOTEXTILE UNDER 200 LB. RIPRAP (TYPE V)(AOS 0.21-0.43)	350.000	S.Y.				
<b>Subtotal Erosion Control Items</b>								

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>BOX BRIDGE ITEMS</b>								
29	S-803-A	TEST PILES	2.00	EA.				
30	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.00	EA.				
31	S-803-C	14" PRESTRESSED CONCRETE PILING	720.00	L.F.				
32	S-803-C	16" PRESTRESSED CONCRETE PILING	405.00	L.F.				
33	S-803-F	18" PRE-FORMED PILE HOLES	660.00	L.F.				
34	S-803-F	20" PRE-FORMED PILE HOLES	228.000	L.F.				
35	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	139.290	C.Y.				
36	901-S-804-C	40' PRESTRESSED CONCRETE BEAM, TYPE 1 & 2	596.250	L.F.				
37	S-805-A	REINFORCEMENT	24,702.000	LB.				
38	S-813-A	CONCRETE RAILING	240.000	L.F.				
39	S-815-A	LOOSE RIPRAP, 300 LB	248.000	TON				
40	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP (TYPE V)(AOS 0.21-0.43)	616.000	S.Y.				
<b>Subtotal Box Bridge Items</b>								
<b>TOTAL BASE BID</b>								
<b>ADDITIVE ALTERNATE NO. 1</b>								
41	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	200.000	TON				
42	S-621-C	4" THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.378	MILE				
43	S-621-E-1	4" THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	1,000.000	L.F.				
44	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	20.000	EA.				
<b>TOTAL ADDITIVE ALTERNATE NO. 1</b>								
<b>ADDITIVE ALTERNATE NO. 2</b>								
45	S-815-A	LOOSE RIPRAP, 300 LB.	258.000	TON				
46	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP (TYPE V)(AOS 0.21-0.43)	600.000	S.Y.				
<b>TOTAL ADDITIVE ALTERNATE NO. 2</b>								