

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
STONE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Stone County, Mississippi at the Stone County Courthouse, Wiggins, Mississippi, until 10:00 am on the 16th day of March, 2020 and shortly thereafter publicly opened for the construction of 0.076 miles of BRIDGE REPLACEMENT & APPROACHES on the INDA ROAD EAST being known as Project No. ERBR-66(03) in Stone County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 10+78)	1.000	UN
REMOVAL OF EXISTING PAVEMENT	804.000	SY
BORROW EXCAVATION (F.M.E.)	945.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GRANULAR MATERIAL (LVM)	448.000	CY
(CLASS 6, GROUP C)		
CRUSHED STONE (SIZE 610) (LVM)	90.000	CY
HOT MIX ASPHALT, ST, 9.5mm	82.000	TON
HOT MIX ASPHALT, ST, 12.5mm	186.000	TON
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE "I" THRIE BEAM		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	10.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.151	MI
(CONTINUOUS WHITE) (60 MIL)		
4" WIDE THERMOPLASTIC TRAFFIC	800.000	LF
STRIPE (CONTINUOUS YELLOW) (90 MIL)		
THERMOPLASTIC LEGEND	132.000	LF
(WHITE) (120 MIL)		
THERMOPLASTIC LEGEND	63.000	SF
(WHITE) (120 MIL)		
REFLECTORIZED TRAFFIC WARNING SIGN	1.000	EA
(ENCAPSULATED LENS)		
REFLECTORIZED TRAFFIC OBJECT MARKER	4.000	EA
(ENCAPSULATED LENS)(TYPE 3)		
REFLECTORIZED ADVANCED WARNING SIGN	1.000	EA
(ENCAPSULATED LENS)		
REFLECTORIZED TRAFFIC REGULATORY	1.000	EA
SIGN WITH SUPP. PLATE		
(ENCAPSULATED LENS)		

SECTION 900
PROJECT NO. ERBR-66(03)
STONE COUNTY

GEOTEXTILE UNDER CRUSHED STONE (TYPE V) (AOS 0.21-0.43)	152.000	SY
--	---------	----

EROSION CONTROL ITEMS

SOLID SODDING	200.000	SY
EXCELSIOR BLANKET	200.000	SY
HYDROSEEDING	0.650	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	937.000	LF
LOOSE RIPRAP, 200 LB.	112.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (AOS 0.21-0.43)	175.000	SY
WATTLES, 20"	600.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	750.000	LF
18" PRE-FORMED PILE HOLES	372.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	138.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	210.000	TON
GEOTEXTILE UNDER RIPRAP (TYPE V) (AOS 0.21-0.43)	380.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Stone County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Jonathan K. Bond, County Engineer for Stone County, Mississippi, P. O. Box 369, Wiggins. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable Certified check or bid bond for five percent (5%) of the total bid, made payable to Stone County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Lance Pearson, President
Stone County Board of Supervisors