

MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
STONE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Stone County, Mississippi at the Stone County Courthouse, Wiggins, Mississippi, until 10:00 am on the 6th day of May 2024 and shortly thereafter publicly opened for the construction of 0.294 miles of BRIDGE REPLACEMENT & APPROACHES on the NEW HOPE ROAD being known as Project No. ERBR-66(04) in Stone County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 16+12)	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	120.000	LF
REMOVAL OF EXISTING PAVEMENT	2,758.000	SY
UNCLASSIFIED EXCAVATION (FM)	975.000	CY
MUCK EXCAVATION (FM)	180.000	CY
BORROW EXCAVATION (F.M.E.)	2,862.000	CY
(CONTRACTOR FURNISHED) (CLASS 9-8)		
GRANULAR MATERIAL (LVM)	3,004.000	CY
(CLASS 6, GROUP C)		
CRUSHED STONE (SIZE 610) (LVM)	100.000	CY
STABILIZER AGGREGATE, MEDIUM (LVM)	275.000	CY
HOT MIX ASPHALT, ST, 9.5mm	380.000	TON
HOT MIX ASPHALT, ST, 12.5mm	822.000	TON
18" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
24" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
58" X 36" REINFORCED CONCRETE ARCH PIPE, CLASS III	48.000	LF
58" X 36" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
GUARD RAIL, "W" BEAM	275.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	23.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	0.000	SF
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.587	MI

SECTION 900  
 PROJECT NO. ERBR-66(04)  
 STONE COUNTY

---

4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	3,100.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	40.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	10.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
GEOTEXTILE FABRIC UNDER CRUSHED STONE (TYPE V) (NON-WOVEN) (AOS < 0.43)	152.000	SY

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	500.000	CY
SOLID SODDING	500.000	SY
EXCELSIOR BLANKET	500.000	SY
HYDROSEEDING	2.560	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,810.000	LF
LOOSE RIPRAP, 200 LB.	18.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP (TYPE V) (NON-WOVEN) (AOS < 0.43)	22.000	SY
WATTLES, 20 IN.	1,000.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,660.000	LF
18" PRE-FORMED PILE HOLES	1,000.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	4.000	EA
19' PRECAST CONCRETE SLAB UNIT, 4'-6" INTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	16.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4'-6" INTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 4'-6" INTERIOR	2.000	EA

SECTION 900  
 PROJECT NO. ERBR-66(04)  
 STONE COUNTY

---

19' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	366.000	LF
33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	3.000	EA
33.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
33' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
10.0' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	220.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, (TYPE V) (NON-WOVEN) (AOS < 0.43)	392.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 160 Working Days

BASIS OF AWARD:

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Stone County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Jonathan K. Bond, County Engineer for Stone County, Mississippi, P. O. Box 369, Wiggins. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Stone County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ronald Howard, President  
Stone County Board of Supervisors