

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
SUNFLOWER COUNTY BOARD OF SUPERVISORS

SECTION 900 - "RE-BID"

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Sunflower County, Mississippi at the Sunflower County Courthouse, Indianola, Mississippi, until **10:00 a.m.** on the **7th day of December, 2020**, and shortly thereafter publicly opened for the construction of 0.073 miles of REPLACE BRIDGE AND APPROACHES on the Tindall Road being known as Project No. ERBR-67(3) in Sunflower County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS</u>		
MOBILIZATION	Lump Sum	LS
CLEARING AND GRUBBING	Lump Sum	LS
REMOVAL OF BRIDGE @ STA. 106+62	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	824.000	CY
CRUSHED STONE	150.000	TON
BRIDGE CONSTRUCTION SURVEYING	Lump Sum	LS
MAINTENANCE OF TRAFFIC	Lump Sum	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS</u>		
AGRICULTURAL LIMESTONE	0.600	TON
COMMERCIAL FERTILIZER (13:13:13)	0.090	TON
AMMONIUM NITRATE	0.030	TON
SEEDING	0.300	AC
VEGETATIVE MATERIALS FOR MULCH	1.000	TON
EXCELSIOR BLANKET	100.000	SY

SECTION 900

PROJECT NO. ERBR-67(3)

SUNFLOWER COUNTY

TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 -
0.84)

300.000 LF

LOOSE RIPRAP, 200 LB

600.000 TON

GEOTEXTILE UNDER RIPRAP, TYPE V, AOS
0.21 - 0.43

1,290.000 SY

WATTLES, 20"

400.000 LF

BRIDGE ITEMS

TEST PILES

3.000 EA

CONVENTIONAL STATIC PILE LOAD TEST

0.000 EA

18" PRESTRESSED CONCRETE PILING

1,740.000 LF

24" PRE-FORMED PILE HOLES

200.000 LF

PILING CUTOFF (18" CONCRETE PILE)

0.000 EA

BRIDGE CONCRETE, CLASS "A"

98.840 CY

REINFORCEMENT

18,054.000 LB

19' PRECAST CONCRETE SLAB UNIT, 3.5'

INTERIOR, 30° SKEW, RT. FWD

6.000 EA

31' PRECAST CONCRETE SLAB UNIT, 3.5'

INTERIOR, 30° SKEW, RT. FWD

36.000 EA

19' PRECAST CONCRETE SLAB UNIT, 3.5'

EXTERIOR, 30° SKEW, RT. FWD

2.000 EA

31' PRECAST CONCRETE SLAB UNIT, 3.5'

EXTERIOR, 30° SKEW, RT. FWD

12.000 EA

PRECAST CONCRETE BARRIER RAIL

410.000 LF

SECTION 900
PROJECT NO. ERBR-67(3)
SUNFLOWER COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME 90 WORKING DAYS

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND PROPOSALS may be secured from Ronald Cassada, County Engineer for Sunflower County, Mississippi, P.O. Drawer A, Indianola, MS. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sunflower County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Riley Rice, President
Sunflower County Board of Supervisors