

WASHINGTON COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Washington County, Mississippi at the Washington County Courthouse, Greenville, Mississippi, until 10:00 am on the 4th day of March, 2020 and shortly thereafter publicly opened for the construction of 0.120 miles of BRIDGE REPLACEMENT AND APPROACHES on the PRICILLA ROAD being known as Project No. ERBR-76(01) in Washington County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of WASHINGTON County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

For this project bids will also be received and accepted via the online electronic bid service through QuestCDN.com. Bidding documents can be downloaded under QuestCDN Project # 6687569 at www.questcdn.com for a non-refundable charge of \$50.00. Contact QuestCDN.com at 956-233-1632 or info@questcdn.com for assistance in free membership, viewing or downloading this digital project information. Online bidding will not be available until three (3) days prior to bid date.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Washington County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Carl McGee, President
Washington County Board of Supervisors

Advertise: February 1, 2020
February 8, 2020

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(01)
Washington County , Mississippi

For the construction of: 0.099 miles of Bridge Replacement and Approaches on Pricilla Road, Washington County, MS

I (We) agree to complete the entire project within 180 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF WOOD BRIDGE (STA. 14+03 LT)	1	Unit		
4	S-202-B	REMOVAL OF BRIDGE (STA. 15+02)	1	Unit		
5	S-202-D	REMOVAL OF ASPHALT PAVEMENT	750	Sq. Yd.		
6	S-202-E	REMOVAL OF PIPE (ALL SIZES)	125	Lin.Ft.		
7	S-203-A	UNCLASSIFIED EXCAVATION (FM)	308	Cu.Yd.		
8	S-203-F	CHANNEL EXCAVATION (FM)	520	Cu.Yd.		
9	S-203-H	EXCESS EXCAVATION (FM)	40	Cu.Yd.		
10	S-304-D	CRUSHED STONE	940	Ton		
11	S-403-A	HOT MIX ASPHALT, ST, 12.5 mm	140	Ton		
12	S-403-A	HOT MIX ASPHALT, ST, 25 mm	225	Ton		
13	S-603-M-A	18" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORR.	100	Lin.Ft.		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(01)
Washington County , Mississippi

14	S-603-M-A	42" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORR.	145	Lin.Ft.		
15	S-606-B	GUARD RAIL,"W" BEAM, COMPLETE-IN-PLACE	100	Lin.Ft.		
16	S-606-C	GUARD RAIL, CABLE ANCHOR, TYPE 1	12.5	Lin.Ft.		
17	S-606-D	GUARD RAIL, BRIDGE END SECTION TYPE "G", "W" BEAM	4	Each		
18	S-606-E	GUARD RAIL, ROUNDED "W" END SECTION	2	Each		
19	S-606-E	GUARD RAIL, TERMINAL END SECTION	2	Each		
20	S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	4	Each		
21	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
22	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
23	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) (60 mil)	0.2	Mile		
24	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW) (90 mil)	1050	Lin.Ft.		
25	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4	Each		
Subtotal Roadway Items:						
Erosion Control Items						
26	901-S-212-A	AGRICULTURAL LIMESTONE	1.44	Ton		
27	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	0.72	Ton		
28	S-214-A	SEEDING	0.72	Acre		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(01)
Washington County , Mississippi

29	S-215-A	VEGETATIVE MATERIALS FOR MULCH	2.16	Ton		
30	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	855	Lin.Ft.		
31	907-237-A	WATTLES, 20"	100	Lin.Ft.		
32	S-815-A	LOOSE RIPRAP, 300 LB.	20	Ton		
33	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	34	Sq. Yd.		
Subtotal Erosion Control Items:						
Bridge Items						
34	S-803-A	TEST PILE	2	Each		
35	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		
36	S-803-C	14" PRESTRESSED CONCRETE PILING	1320	Lin.Ft.		
37	S-803-F	18" PRE-FORMED PILE HOLE	200	Lin.Ft.		
38	S-806-D	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	20	Each		
39	S-806-D	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	10	Each		
40	S-806-F	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	10	Each		
41	S-806-G	PRECAST CONCRETE BARRIER RAIL	310	Lin.Ft.		
42	S-806-I	33.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	4	Each		
43	S-806-J	33.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2	Each		

44	S-806-M	9.25' PRECAST CONCRETE WING	4	Each		
45	S-815-A	LOOSE RIPRAP, 300 LB.	275	Ton		
46	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	530	Sq. Yd.		
Subtotal Bridge Items:						
Total Bid:						