

WASHINGTON COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Washington County, Mississippi at the Washington County Courthouse, Greenville, Mississippi, until 10:00 am on the 4th day of March, 2022 and shortly thereafter publicly opened for the construction of 0.180 miles of BRIDGE REPLACEMENT AND APPROACHES on the MURPHY ROAD being known as Project No. ERBR-76(04) in Washington County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of WASHINGTON County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

For this project bids will also be received and accepted via the online electronic bid service through QuestCDN.com. Bidding documents can be downloaded under QuestCDN Project #8117917 at www.questcdn.com for a non-refundable charge of \$55.00. Contact QuestCDN.com at 956-233-1632 or info@questcdn.com for assistance in free membership, viewing or downloading this digital project information. Online bidding will not be available until three (3) days prior to bid date.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Washington County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Carl McGee, President
Washington County Board of Supervisors

Advertise: February 2, 2022
February 9, 2022

SECTION 902
PROPOSAL SHEET

Project No.

ERBR-76(04) - Murphy Road
Washington County , Mississippi

For the construction of: 0.180 miles of Bridge Replacement and Approaches on Murphy Road, Washington County, MS

I (We) agree to complete the entire project within 180 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE STA. 13+07	1	Unit		
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	300	Cu.Yd.		
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	400	Cu.Yd.		
6	S-203-F	CHANNEL EXCAVATION (FM)	400	Cu.Yd.		
7	S-304-D	CRUSHED STONE	1200	Ton		
8	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	4	Each		
9	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
10	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
11	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4	Each		
Subtotal Roadway Items:						

SECTION 902
PROPOSAL SHEET

Project No.

ERBR-76(04) - Murphy Road
Washington County , Mississippi

Erosion Control Items						
12	901-S-212-A	AGRICULTURAL LIMESTONE	1.7	Ton		
13	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	0.85	Ton		
14	S-214-A	SEEDING	0.85	Acre		
15	S-215-A	VEGETATIVE MATERIALS FOR MULCH	2.55	Ton		
16	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1500	Lin.Ft.		
17	907-237-A	WATTLES, 20"	200	Lin.Ft.		
Subtotal Erosion Control Items:						
Landslide Stablization Items						
18	S-203-A	UNCLASSIFIED EXCAVATION (FM)	40	Cu.Yd.		
19	S-803-E	14" STEEL PILING	1350	Lin.Ft.		
20	901-S-804-A	BRIDGE CONCRETE, CLASS AA	35	Cu.Yd.		
21	S-805-A	REINFORCEMENT	4000	Lb.		
Subtotal Landslide Stablization Items:						
Bridge Items						
22	S-803-A	TEST PILE	2	Each		
23	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		

SECTION 902
PROPOSAL SHEET

Project No.

ERBR-76(04) - Murphy Road
Washington County , Mississippi

24	S-803-C	14" PRESTRESSED CONCRETE PILING	1400	Lin.Ft.		
25	S-803-C	16" PRESTRESSED CONCRETE PILING	2200	Lin.Ft.		
26	S-803-F	20" PRE-FORMED PILE HOLE	200	Lin.Ft.		
27	901-S-804-A	BRIDGE CONCRETE, CLASS A	320	Cu.Yd.		
28	901-S-804-A	BRIDGE CONCRETE, CLASS B	10	Cu.Yd.		
29	S-804-C	31' PRESTRESSED CONCRETE BEAM, TYPE I + 2	307.5	Lin. Ft.		
30	S-804-C	110' PRESTRESSED CONCRETE BEAM, TYPE IV	1097.5	Lin. Ft.		
31	S-805-A	REINFORCEMENT	58000	Lb.		
32	S-813-A	CONCRETE RAILING	564	Lin.Ft.		
33	S-815-A	LOOSE RIPRAP, 300 LB.	400	Ton		
34	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS 0.21-0.43	700	Sq. Yd.		
					Subtotal Bridge Items:	
					Total Bid:	