

WASHINGTON COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Washington County, Mississippi at the Washington County Courthouse, Greenville, Mississippi, until 10:30 am on the 12th day of September, 2019 and shortly thereafter publicly opened for the construction of 0.095 miles of BRIDGE REPLACEMENT AND APPROACHES on the PETES DUMP ROAD being known as Project No. ERBR-76(05) in Washington County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of WASHINGTON County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

For this project bids will also be received and accepted via the online electronic bid service through QuestCDN.com. Bidding documents can be downloaded under QuestCDN Project #6472425 at www.questcdn.com for a non-refundable charge of \$50.00. Contact QuestCDN.com at 956-233-1632 or info@questcdn.com for assistance in free membership, viewing or downloading this digital project information. Online bidding will not be available until three (3) days prior to bid date.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Issaquena County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Carl McGee, President
Washington County Board of Supervisors

Advertise: August 9, 2019
August 16, 2019

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(05)
Washington County , Mississippi

For the construction of: 0.104 miles of Bridge Replacement and Approaches on Pete's Dump Road, Washington County, MS

I (We) agree to complete the entire project within 120 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE (STA. 13+00)	1	Unit		
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	300	Cu.Yd.		
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	700	Cu.Yd.		
6	S-203-F	CHANNEL EXCAVATION (FM)	250	Cu.Yd.		
7	S-304-D	CRUSHED STONE	600	Ton		
8	S-603-M-C	28" x 20" POLYMERIC COATED CORRUGATED METAL PIPE 14 GAGE, 2-2/3" x 1/2" CORR.	80	Lin.Ft.		
9	S-603-M-C	35" x 24" POLYMERIC COATED CORRUGATED METAL PIPE 14 GAGE, 2-2/3" x 1/2" CORR.	80	Lin.Ft.		
10	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	4	Each		
11	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
12	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
13	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4	Each		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(05)
Washington County , Mississippi

Subtotal Roadway Items:						
Erosion Control Items						
14	901-S-212-A	AGRICULTURAL LIMESTONE	1.5	Ton		
15	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	0.75	Ton		
16	S-214-A	SEEDING	0.75	Arce		
17	S-215-A	VEGETATIVE MATERIALS FOR MULCH	2.25	Ton		
18	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	900	Lin.Ft.		
19	237-A	WATTLES, 20"	200	Lin.Ft.		
20	S-815-A	LOOSE RIPRAP, 300 LB.	100	Ton		
21	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	200	Sq.Yd.		
Subtotal Erosion Control Items:						
Bridge Items						
22	S-803-A	TEST PILE	2	Each		
23	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		
24	S-803-C	14" PRESTRESSED CONCRETE PILING	1040	Lin.Ft.		
25	S-803-F	18" PREFORMED PILE HOLES	200	Lin.Ft.		
26	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4	Each		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-76(05)
Washington County , Mississippi

27	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2	Each		
28	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12	Each		
29	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	6	Each		
30	S-806-C	19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2	Each		
31	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6	Each		
32	S-806-G	PRECAST CONCRETE BARRIER RAIL	224	Lin.Ft.		
33	S-806-I	33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	3	Each		
34	S-806-J	33' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2	Each		
35	S-806-M	9.25' PRECAST CONCRETE WING	4	Each		
36	S-815-A	LOOSE RIPRAP, 300 LB.	200	Ton		
37	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	400	Sq.Yd.		
Subtotal Bridge Items:						
Total Bid:						