

## WASHINGTON COUNTY BOARD OF SUPERVISORS

### SECTION 900

Sealed bids will be received by the Board of Supervisors of Washington County, Mississippi at the Washington County Courthouse, Greenville, Mississippi, until 10:00 am on the 4th day of March, 2020 and shortly thereafter publicly opened for the construction of 0.051 miles of BRIDGE REPLACEMENT AND APPROACHES on the EIFLING ROAD being known as Project No. ERBR-76(07) in Washington County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of WASHINGTON County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

For this project bids will also be received and accepted via the online electronic bid service through QuestCDN.com. Bidding documents can be downloaded under QuestCDN Project # 6687540 at [www.questcdn.com](http://www.questcdn.com) for a non-refundable charge of \$50.00. Contact QuestCDN.com at 956-233-1632 or [info@questcdn.com](mailto:info@questcdn.com) for assistance in free membership, viewing or downloading this digital project information. Online bidding will not be available until three (3) days prior to bid date.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Washington County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Carl McGee, President  
Washington County Board of Supervisors

Advertise: February 1, 2020  
February 8, 2020

SECTION 902  
PROPOSAL SHEET

Project No. ERBR-76(07)  
Washington County , Mississippi

For the construction of: 0.051 miles of Bridge Replacement and Approaches on Eifling Road, Washington County, MS

I (We) agree to complete the entire project within 180 Working Days

\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

|                         |              |  |                  |          | Unit Price      | Item Total      |
|-------------------------|--------------|--|------------------|----------|-----------------|-----------------|
| Ref. No.                | Pay Item No. | Description  | Approx. Quantity | Unit     | Dollars & Cents | Dollars & Cents |
| Roadway Items           |              |  |                  |          |                 |                 |
| 1                       | S-200-A      | MOBILIZATION   | Lump Sum         | Lump Sum |                 |                 |
| 2                       | S-201-A      | CLEARING AND GRUBBING  | Lump Sum         | Lump Sum |                 |                 |
| 3                       | S-202-B      | REMOVAL OF BRIDGE (STA. 11+80)   | 1                | Unit     |                 |                 |
| 4                       | S-203-A      | UNCLASSIFIED EXCAVATION (FM)   | 45               | Cu.Yd.   |                 |                 |
| 5                       | S-203-E1     | BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)                    | 426              | Cu.Yd.   |                 |                 |
| 6                       | S-203-F      | CHANNEL EXCAVATION (FM)  | 1091             | Cu.Yd.   |                 |                 |
| 7                       | S-304-D      | CRUSHED STONE  | 273              | Ton      |                 |                 |
| 8                       | S-603-M-C    | 49"x33" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORR. | 80               | Lin.Ft.  |                 |                 |
| 9                       | S-617-A      | RIGHT-OF-WAY MARKERS (TYPE II)   | 4                | Each     |                 |                 |
| 10                      | S-618-A      | MAINTENANCE OF TRAFFIC   | Lump Sum         | Lump Sum |                 |                 |
| 11                      | S-618-B      | ADDITIONAL CONSTRUCTION SIGNS  | 0                | Sq. Ft.  |                 |                 |
| 12                      | S-630-C      | REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)              | 4                | Each     |                 |                 |
| Subtotal Roadway Items: |              |  |                  |          |                 |                 |

SECTION 902  
PROPOSAL SHEET

Project No. ERBR-76(07)  
Washington County , Mississippi

| Erosion Control Items           |             |  |     |         |  |  |
|---------------------------------|-------------|--|-----|---------|--|--|
| 13                              | 901-S-212-A | AGRICULTURAL LIMESTONE                           | 1   | Ton     |  |  |
| 14                              | S-212-B     | COMMERCIAL FERTILIZER ( 13 : 13 : 13 )           | 0.5 | Ton     |  |  |
| 15                              | S-214-A     | SEEDING  | 0.5 | Acre    |  |  |
| 16                              | S-215-A     | VEGETATIVE MATERIALS FOR MULCH                   | 1.5 | Ton     |  |  |
| 17                              | S-233-A     | TEMPORARY SILT FENCE (TYPE II ) (AOS 0.15-0.84 ) | 550 | Lin.Ft. |  |  |
| 18                              | 237-A       | WATTLES, 20"                                     | 100 | Lin.Ft. |  |  |
| 19                              | S-815-A     | LOOSE RIPRAP, 300 LB.                            | 24  | Ton     |  |  |
| 20                              | S-815-E     | GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43   | 45  | Sq.Yd.  |  |  |
| Subtotal Erosion Control Items: |             |  |     |         |  |  |
| Bridge Items                    |             |  |     |         |  |  |
| 21                              | S-803-A     | TEST PILE  | 1   | Each    |  |  |
| 22                              | S-803-B     | CONVENTIONAL STATIC PILE LOAD TEST               | 0   | Each    |  |  |
| 23                              | S-803-C     | 14" PRESTRESSED CONCRETE PILING                  | 470 | Lin.Ft. |  |  |
| 24                              | S-803-F     | 18" PRE-FORMED PILE HOLE                         | 200 | Lin.Ft. |  |  |
| 25                              | S-806-A     | 31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR    | 8   | Each    |  |  |
| 26                              | S-806-A     | 31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR    | 4   | Each    |  |  |

SECTION 902  
PROPOSAL SHEET

Project No. ERBR-76(07)  
Washington County , Mississippi

|                        |         |  |     |         |  |  |
|------------------------|---------|--|-----|---------|--|--|
| 27                     | S-806-C | 31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR      | 4   | Each    |  |  |
| 28                     | S-806-G | PRECAST CONCRETE BARRIER RAIL                      | 124 | Lin.Ft. |  |  |
| 29                     | S-806-I | 33' CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE | 1   | Each    |  |  |
| 30                     | S-806-J | 33' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE  | 2   | Each    |  |  |
| 31                     | S-806-M | 9.25' PRECAST CONCRETE WING                        | 4   | Each    |  |  |
| 32                     | S-815-A | LOOSE RIPRAP, 300 LB.                              | 135 | Ton     |  |  |
| 33                     | S-815-E | GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43     | 275 | Sq.Yd.  |  |  |
| Subtotal Bridge Items: |         |  |     |         |  |  |
| Total Bid:             |         |  |     |         |  |  |