

## PROJECT PAY ITEMS AND DESCRIPTION

PROJECT NO. ERBR-77(02)  
WAYNE COUNTY, MS

Sealed bids will be received by the Wayne County Board of Supervisors in the boardroom at the Wayne County Courthouse, Waynesboro, MS until 10:00 a.m. on Thursday, October 17, 2019.

For the construction of: Precast Span Bridge 1 @ 19', 1 @ 31', 1 @ 19' Skew 30 Degree Left Forward with Approaches on 0.055 miles of County Road described as Hiwannee-Chapparral Road in Wayne County, District 3, also known as ERBR-77(02).

Plans and Contract Documents can be obtained on the website of the Engineer of Record at [www.clarkengineersprojects.com](http://www.clarkengineersprojects.com)

Contract Time shall be Eighty (80) Working Days

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
<b>ROADWAY ITEMS</b>				
1	S-200-A	Mobilization	Lump Sum	L.S.
2	S-201-A	Clearing and Grubbing	Lump Sum	L.S.
3	S-202-B	Removal of Bridge @ Sta. 12 + 82.92	1.0	Unit
4	S-203-A	Unclassified Excavation (F.M.)	280.0	Cu. Yd.
5	S-203-E	Borrow Excavation (F.M.E.)(Contractor Furnished) (Class 9-6)	807.0	Cu. Yd.
6	S-304-A	Crushed Stone (Size 825)	160.0	Ton
7	S-403-A	Hot Mix Asphalt, (ST)(9.5 mm)(Surface)	49.0	Ton
8	S-403-A	Hot Mix Asphalt, (ST)(9.5 mm)(Base)	16.0	Ton
9	S-603-PE	60" Corrugated Polyethylene Pipe	80.0	L.F.
10	S-617-A	Right-of-Way Markers (Type II)	10.0	Each
11	S-618-A	Maintenance of Traffic	Lump Sum	L.S.
12	S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	8.0	Each
13	S-630-C	Reflectorized Traffic Object Markers (Encapsulated Lens)(Type 3)	4.0	Each
14	S-815-A	Loose Riprap (300 Lb.)	18.0	Ton
15	S-815-E	Geotextile Under Crushed Stone, Type V, (AOS 0.21 - 0.43)	828.0	Sq. Yd.
<b>EROSION CONTROL ITEMS</b>				
16	S-212-A	Agricultural Limestone	0.88	Ton
17	S-212-B	Commercial Fertilizer (13:13:13)	0.44	Ton
18	S-212-F	Ammonium Nitrate	0.04	Ton

## PROJECT PAY ITEMS AND DESCRIPTION

PROJECT NO. ERBR-77(02)  
WAYNE COUNTY, MS

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
19	S-214-A	Seeding	0.44	Acre
20	S-215-A	Vegetative Materials for Mulch	0.88	Ton
21	S-233-A	Temporary Silt Fence (Type II)	630.0	L.F.
<b>BRIDGE ITEMS</b>				
<b>STA. 12+67.67, 1 @ 19 LF, 1 @ 31 LF, 1 @ 19 LF Precast Spans 26' - 6" Clear Roadway Width 30 Degree Skew, Left Forward</b>				
22	S-803-A	Test Pile	2.0	Each
23	S-803-C	14" Prestressed Concrete Piling	520.0	L.F.
24	S-803-F	16" Pre-Formed Pile Holes	403.0	L.F.
25	S-806-D	19' Prestressed Concrete Slab Unit, 3.5', Interior, 30° Skew, Left Fwd.	12.0	Each
26	S-806-D	31' Prestressed Concrete Slab Unit, 3.5', Interior, 30° Skew, Left Fwd.	6.0	Each
27	S-806-E	19' Prestressed Concrete Slab Unit, Curb, 30° Skew Left Fwd.	4.0	Each
28	S-806-E	31' Prestressed Concrete Slab Unit, Curb, 30° Skew Left Fwd.	2.0	Each
29	S-806-H	Beam Type Railing with Concrete Posts	138.0	L.F.
30	S-806-K	33.5' Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30° Skew, Left Fwd.	2.0	Each
31	S-806-L	33.5' Precast Concrete Cap, End Unit, Concrete Pile, 30° Skew, Left Fwd.	2.0	Each
32	S-806-M	7.5' Precast Concrete Wing	4.0	Each
33	S-815-A	Loose Riprap (300 Lb.)	57.0	Ton
34	S-815-E	Geotextile Under Riprap, Type V, (AOS 0.21 - 0.43)	129.0	Sq. Yd.