

Sealed bids will be received by the Wayne County Board of Supervisors in the boardroom at the Wayne County Courthouse, Waynesboro, MS, until 10:00 a.m. on Thursday, August 15, 2019.

For the construction of: Bridge Maintenance Project on an existing 2 @ 40', 1 @ 280', 1 @ 40' Steel Beam/Continuous Grider Bridge with Guard Rail Replacement and Approach work on 0.170 miles of County Road described as Buckatunna-Chicora-Clara Road (BCC Road) in Wayne County, District One, also known as Project No. ERBR-77(03).

Contract Time shall be One Hundred Fifty (150) Working Days.

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit
ROADWAY ITEMS				
1	S-200-A	Mobilization	Lump Sum	L.S.
2	S-201-A	Clearing and Grubbing	0.20	Acre
3	S-202-B	Removal of Guard Rail (Texas Twist)	1.0	Unit
4	S-203-A	Unclassified Excavation (F.M.)	185.0	Cu. Yd.
5	S-304-A	Crushed Stone (Size 825)	189.0	Ton
6	S-606-B	Guard Rail, "W" Beam	275.0	L.F.
7	S-606-D	Guard Rail, Bridge End Section, Type "C"	4.0	Each
8	S-606-E	Guard Rail, Terminal End Section	4.0	Each
9	S-618-A	Maintenance of Traffic	Lump Sum	L.S.
10	S-620-C	4" Wide Cold Plastic Edge Stripe (Continuous White)	0.150	Mile
11	S-620-E-2	4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	0.150	Mile
12	S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	13.0	Each
13	S-630-C	Reflectorized Traffic Object Markers (Encapsulated Lens)(Type 3)	4.0	Each
14	S-630-D	Reflectorized Traffic Delineator Sign (Encap. Lens)	22.0	Each
EROSION CONTROL ITEMS				
15	S-212-B	Commercial Fertilizer (13:13:13)	0.50	Ton
16	S-214-A	Seeding	0.50	Acre
17	S-215-A	Vegetative Materials for Mulch	1.00	Ton
18	S-233-A	Temporary Silt Fence (Type II)(AOS 0.15 - 0.84)	1,000.0	L.F.
19	907-237-A	Wattles, 12"	400.0	L.F.
BRIDGE ITEMS				
STA. 10+33, 3 Spans @ 40 LF Wide Flange Beam; 1 Span @ 280 LF Continuous Plate Girder; 28.0 Ft Clear Roadway Width				
20	907-229-A	Erosion Mat	68.0	Sq. Yd.
21	S-810-C	Miscellaneous Bridge Appurtenances	Lump Sum	L.S.
22	S-815-A	Loose Riprap (300 Lb.)	474.0	Ton
23	S-815-E	Geotextile Under Riprap, Type V, (AOS 0.21 - 0.43)	902.0	Sq. Yd.
24	S-816-C	Maintenance Painting of Bridge @ Sta. 10+33	Lump Sum	L.S.
25	907-826-A	Waterproofing Membrane	1,244.0	Sq. Yd.