

The Wayne County Board of Supervisor will receive bids for the construction of a bridge replacement project on Dew Mills Road, District Four Wayne County also known as Emergency Road and Bridge Repair Fund Project ERBR-77(06). Proposals must be submitted no later than 10:00 a. m. on Tuesday, September 16, 2025 at the boardroom of the Wayne County Courthouse located at 609 Azalea Drive, Waynesboro, MS.

For the construction of: Single Cell 14' x 6' Box Bridge and approaches on 0.142 miles of county road known as Dew Mills Road.

Plans and Contract Documents can be viewed and obtained online via the website of the Engineer of Record, Lawrence R. Clark, P.E. at [www.clarkengineersprojects.com](http://www.clarkengineersprojects.com).

Pay Item No.	Description	Approx. Quantity	Unit
<b>ROADWAY ITEMS</b>			
S-200-A	Mobilization	1.0	Lump Sum
S-201-A	Clearing and Grubbing	1.0	Lump Sum
S-202-A	Removal of Obstructions	1.0	Lump Sum
S-202-B	Removal of Bridge @ Sta. 14+81	1.0	Unit
S-202-E	Removal of Pipe (All Sizes)	60.0	Lin. Ft.
S-203-A	Unclassified Excavation (F.M.)	1,562.0	Cu. Yd.
S-203-D	Muck Excavation (F.M.)	213.0	Cu. Yd.
S-203-E	Borrow Excavation (F.M.E.)(Contractor Furnished) (Class 9)	3,188.0	Cu. Yd.
S203-F	Channel Excavation (F.M.)	51.0	Cu. Yd.
247-A	Temporary Stream Diversion	1.0	Each
S-304-D	Crushed Stone, Size 825	954.0	Ton
S-403-A	Hot Mix Asphalt, (ST) (9.5 mm)	154.0	Ton
S-403-A	Hot Mix Asphalt, (ST) (19 mm)	454.0	Ton
S-603-C-A	18" Reinforced Concrete Pipe, Class III	112.0	Lin. Ft.
S-605-X-2	Filter Material for Filter Beds, Type "A", Crushed Stone Size 57	287.0	Ton
S-607-B	Roadway Construction Surveying	1.0	Lump Sum
S-618-A	Maintenance of Traffic	1.0	Lump Sum
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (90 mils)	0.284	Mile
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	1,500.0	Lin. Ft.
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	20.0	Each
S-630-A	Reflectorized Traffic Warning Sign (Encapsulated Lens)	2.0	Each
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	4.0	Each
<b>EROSION CONTROL ITEMS</b>			
S-212-A	Agricultural Limestone	4.0	Ton
S-212-B	Commercial Fertilizer (13:13:13)	2.0	Ton
S-214-A	Seeding	2.0	Acre

Pay Item No.	Description	Approx. Quantity	Unit
S-215-A	Vegetative Materials for Mulch	4.0	Ton
S-226-A	Solid Sodding	200.0	Sq. Yd.
226-A	Temporary Grassing	2.0	Acre
S-233-A	Temporary Silt Fence (Type II)(AOS - 0.15 - 0.84)	1,510.0	Lin. Ft.
237-A	Wattles, 12"	200.0	Lin. Ft.
S-815-A	Loose Riprap, 200 LB	200.0	Ton
S-815-E	Geotextile Under Riprap, Type V, (AOS 0.21 - 0.43)	370.0	Sq. Yd.
<b>BOX BRIDGE ITEMS</b>			
901-S-804-A	Box Bridge Concrete, Class "BB"	156.0	Cu. Yd.
S-805-A	Reinforcement	29,911.00	LB.

Contract Time 100 Working Days