

ISSAQUENA COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Issaquena County, Mississippi at the Issaquena County Courthouse, Mayersville, Mississippi, until 11:00 am on 22nd day of May, 2020 and shortly thereafter publicly opened for the construction of 0.242 miles of BRIDGE REPLACEMENT AND APPROACHES on the WILLETTE ROAD being known as Project No. ERBR-BR-1512(2)B in Issaquena County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of ISSAQUENA County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Issaquena County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

William Holcomb, III, President
Issaquena County Board of Supervisors

Advertise: April 23, 2020
April 30, 2020

SECTION 902
PROPOSAL SHEET

Project No. ERBR-BR-1512(2)B
Issaquena County , Mississippi

For the construction of: 0.242 miles of Bridge Replacement and Approaches on Willette Road, Issaquena County, MS

I (We) agree to complete the entire project within 180 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantitiy	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE STA. 22+09	1	Unit		
4	S-202-B	REMOVAL OF BRIDGE STA. 162+51	1	Unit		
5	S-202-D	REMOVAL OF PAVEMENT (ALL TYPES)	2106	Sq.Yd.		
6	S-202-E	REMOVAL OF PIPES (ALL SIZES)	25	Lin.Ft.		
7	S-203-A	UNCLASSIFIED EXCAVATION (FM)	1428	Cu.Yd.		
8	S-203-E1	BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	1885	Cu.Yd.		
9	S-203-F	CHANNEL EXCAVATION (FM)	292	Cu.Yd.		
10	S-240-A	GEOGRID, BIAXIAL BX1200	940	Sq.Yd.		
11	S-240-A	GEOGRID, TRIAXIAL TX130S	570	Sq.Yd.		
12	S-304-D	CRUSHED STONE	2125	Ton		
13	S-403-A	HOT MIX ASPHALT, ST, 12.5 mm	280	Ton		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-BR-1512(2)B
Issaquena County , Mississippi

14	S-403-A	HOT MIX ASPHALT, ST, 25 mm	570	Ton		
15	S-603-M-A	36" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORRUGATION	40	Lin.Ft.		
16	S-6030M-C	142" x 91" POLYMERIC COATED CORRUGATED METAL ARCH PIPE, 10 GAGE, 5" x 1" CORRUGATION	240	Lin.Ft.		
17	S-606-B	GUARD RAIL,"W" BEAM, COMPLETE-IN-PLACE	275	Lin.Ft.		
18	S-606-D	GUARD RAIL, BRIDGE END SECTION TYPE "I", THRIE BEAM	4	Each		
19	S-606-E	GUARD RAIL, TERMINAL END SECTION	4	Each		
20	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	15	Each		
21	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
22	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
23	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) (60 mil)	0.49	Mile		
24	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW)(60 mil)	2550	Lin.Ft.		
25	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4	Each		
Subtotal Roadway Items:						
Erosion Control Items						
26	901-S-212-A	AGRICULTURAL LIMESTONE	4.62	Ton		
27	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	2.31	Ton		
28	S-214-A	SEEDING	2.31	Acre		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-BR-1512(2)B
Issaquena County , Mississippi

29	S-215-A	VEGETATIVE MATERIALS FOR MULCH	4.62	Ton		
30	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2363	Lin.Ft.		
31	907-237-A	WATTLES, 20"	225	Lin.Ft.		
32	S-815-A	LOOSE RIPRAP, 300 LB	75	Ton		
33	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	140	Sq.Yd.		
Subtotal Erosion Control Items:						
Bridge Items						
34	S-803-A	TEST PILE	2	Each		
35	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		
36	S-803-E	14" STEEL PILING	2300	Lin.Ft.		
37	S-803-F	22" PRE-FORMED PILE HOLE	125	Lin.Ft.		
38	901-S-804-A	BRIDGE CONCRETE, CLASS A	101	Cu.Yd.		
39	S-805-A	REINFORCEMENT	14804	Lb.		
40	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	24	Each		
41	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	12	Each		
42	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	12	Each		
43	S-806-G	PRECAST CONCRETE BARRIER RAIL	372	Lin.Ft.		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-BR-1512(2)B
Issaquena County , Mississippi

44	S-815-A	LOOSE RIPRAP, 300 LB.	210	Ton		
45	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	410	Sq. Yd.		
Subtotal Bridge Items:						
Total Bid:						