

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-LSBP-02(23)
COUNTY ROAD 331 & COUNTY ROAD 420
ALCORN COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-LSBP-02(23) Alcorn County, MS. The Board of Supervisors of Alcorn County, MS will receive bids for the construction of **0.171 miles of SITE A – Box Culvert to replace Bridge No. 115 on County Road 420 and SITE B – Precast Bridge to replace Bridge No. 126 on County Road 331.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **2:00 PM on the 7th day of June, 2019** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Alcorn County Board of Supervisors Building, 305 S Fulton Drive, Corinth, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Alcorn County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jimmy Tate Waldon, President
Alcorn County Board of Supervisors

Publish: *May 8th & 15th, 2019*

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-LSBP-02(23) Site "A" - County Road 420 & Site "B" - County Road 331					
BASE BID ITEMS					
Roadway Items					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 38+88	1.00	UN	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 47+26	1.00	UN	\$	\$
S-202-D	Removal of Pavement (All Thickness)	363.00	SY	\$	\$
S-203-A	Unclassified Excavation (FM)	4,138.00	CY	\$	\$
S-203-E-1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	981.00	CY	\$	\$
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	2,776.00	SY	\$	\$
247-A	Temporary Stream Diversion	1.00	EA	\$	\$
S-304-A	Granular Material (LVM)(Class 5, Group "B")	92.00	CY	\$	\$
S-304-C	Crushed Stone Size 3/4" & Down (FM)	779.00	CY	\$	\$
S-310-D	Mixing, Shaping and Compaction	2,129.00	SY	\$	\$
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	323.00	TON	\$	\$
S-408-A	Asphalt for Prime Coat (EA-1) or (AE-P)	746.00	GAL	\$	\$
S-601-A	Class "B" Structural Concrete	166.50	CY	\$	\$
S-602-A	Reinforcing Steel	28,374.00	LB	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-603-C-A	24" Reinforced Concrete Pipe, Class III	80.00	LF	\$	\$
S-603-C-B	24" Reinforced Concrete Pipe, End Section	2.00	LF	\$	\$
S-603-C-D	28" x 18" Reinforced concrete Pipe, Class III	40.00	LF	\$	\$
S-603-C-E	28" x 18" Reinforced Concrete Pipe, End Section	2.00	EA	\$	\$
S-603-PE	18" Corrugated Polyethylene Pipe	64.00	LF	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$
S-617-A	Right Of Way Markers, Type II	22.00	EA	\$	\$
S-618-A	Maintenance of Traffic	1.00	LS	\$	\$
S-618-B	Additional Construction Signs	0.00	SF	\$ 10.00	\$ 0.00
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.300	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	1,586.00	LF	\$	\$
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	12.00	EA	\$	\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
S-630-G	Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	2.00	EA	\$	\$
Erosion Control Items					
901-S-212-A	Agricultural Limestone	2.24	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	1.12	TON	\$	\$
S-212-F	Ammonium Nitrate	0.28	TON	\$	\$
S-214-A	Seeding	1.12	AC	\$	\$
S-226-A	Solid Sodding	200.00	SY	\$	\$
S-227-A	Excelsior Blanket	5,934.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	990.00	LF	\$	\$
237-A	Wattles, 20"	260.00	LF	\$	\$
S-815-A	Loose Riprap, 200 Lb	70.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	270.00	SY	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
Bridge Items 3 @ 40' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Pile	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	0.00	EA	\$ 4000.00	\$ 0.00
S-803-E	14" Steel Piling	760.00	LF	\$	\$
901-S-804-A	Bridge Concrete, Class "A"	11.06	CY	\$	\$
901-S-804-A	Bridge Concrete, Class "B"	18.28	CY	\$	\$
S-805-A	Reinforcement	3,317.00	LB	\$	\$
S-806-A	40' Precast Concrete Slab Unit, 3.5' Interior	18.00	EA	\$	\$
S-806-C	40' Precast Concrete Slab Unit, 3.5' Exterior	6.00	EA	\$	\$
S-806-G	Precast Concrete Barrier Rail	240.00	LF	\$	\$
S-806-I	31.17' Precast Concrete Cap, Intermediate Unit, Steel P	1.00	EA	\$	\$
S-806-J	31.17' Precast Concrete Cap, End Unit, Steel Pile	1.00	EA	\$	\$
S-806-M	9.17' Precast Concrete Wing	4.00	EA	\$	\$
S-815-D	Concrete Slope Paving	44.00	CY	\$	\$
TOTAL BASE BID					\$