

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of George County, Mississippi at their office located at 329 Ratliff Street, Lucedale, Mississippi, until **10:00 am. (local time) on May 22, 2019** and shortly thereafter publicly opened for the construction of a Three Span Precast Concrete Bridge on Salem Campground Road, being known as **Project No. ERBR-LSBP-20(13)** in George County, Mississippi.

Contractors have the option of submitting their bids sealed in an envelope or electronically. If a sealed envelope bid is submitted by mail, the address of the Chancery Clerk is 355 Cox Street, Lucedale, MS 39452. For electronic bid, documents can be downloaded from Central Bidding. Electronic bids shall be submitted at [www.centralbidding.com](http://www.centralbidding.com). For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

PLANS AND SPECIFICATIONS are on file and may be reviewed in the Office of the Purchase Clerk or online at [www.centralbidding.com](http://www.centralbidding.com).. This project allows for a Contract Time of 50 Working Days and shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured online from the reference website or obtained from the office of Batson & Brown, Inc., 11267 Old 63 South, Lucedale, MS 39452 upon payment of \$100.00 (non-refundable) for each set.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

Larry McDonald, President  
George County Board of Supervisors

Publication dates:

April 26, 2019

April 30, 2019

*[Note: This advertisement must be published in the legal section of the Clarion-Ledger, being a paper of state-wide circulation.]*

**EMERGENCY ROAD AND BRIDGE REPAIR PROJECT FOR  
THE GEORGE COUNTY BOARD OF SUPERVISORS  
PROJECT NO. ERBR-LSBP - 20(13)  
SALEM CAMPGROUND ROAD  
GEORGE COUNTY, MISSISSIPPI**

For the construction of: Bridge Replacement Project on 0.133 miles of Salem Campground Road  
in George County, Mississippi, also known as Project No. ERBR-LSBP-20(13)

Pay Item No.	PAY ITEM	Plan Quantity	UNIT	UNIT PRICE	AMOUNT
<b>ROADWAY ITEMS</b>					
S-200-A	MOBILIZATION	LUMP SUM	LUMP SUM		
S-201-A	CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		
S-202-B	REMOVAL OF BRIDGE AT STATION 146+56	1	UNIT		
S-202-D	REMOVAL OF ASPHALT (ALL DEPTHS)	1429	SQ. YD.		
S-203-A	UNCLASSIFIED EXCAVATION (FM)	1415	CU. YD.		
S-203-E	BORROW EXCAVATION (CONTRACTOR FURNISHED) (LVM) (CLASS 5)	1425	CU. YD.		
S-304-C	CRUSHED STONE (SIZE 610) (LVM)	586	CU. YD.		
S-403-A	HOT MIX ASPHALT, ST, 9.5 MM	240	TON		
S-403-A	HOT MIX ASPHALT, ST, 12.5 MM	400	TON		
S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	10	EACH		
S-618-A	MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		
S-618-B	ADDITIONAL CONSTRUCTION SIGNS		SQ. FT.	10	0
S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER(ENCAPSULATED LENS) TYPE	4	EACH		
S-815-E	GEOTEXTILE UNDER BRIDGE END TREATMENT, TYPE V, A.O.S. 0.21 - 0.43	92	SQ. YD.		
<b>EROSION CONTROL ITEMS</b>					
901-S-212-A	AGRICULTURAL LIMESTONE	3.48	TON		
S-212-B	COMMERCIAL FERTILIZER (13-13-13)	1.74	TON		
S-214-A	SEEDING	1.74	ACRE		
S-215-A	VEGETATIVE MATERIALS FOR MULCH	5.22	TON		
S-226-A	SOLID SODDING	200	SQ. YD.		
S-233-A	TEMPORARY SILT FENCE (TYPE I), (A.O.S. 0.15-0.84)	1500	L.F.		
237-A	WATTLES, 20"	200	L.F.		
<b>BRIDGE ITEMS</b>					
<b>3 @ 31' PRECAST CONCRETE SPANS, 26'-6" ROADWAY</b>					
S-803-A	TEST PILES	2	EACH		
S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	EACH	4000	0
S-803-C	14" PRESTRESSED CONCRETE PILING	670	L.F.		
S-803-F	18" PRE-FORMED PILE HOLE	448	L.F.		
S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18	EACH		
S-806-B	31' PRECAST CONCRETE SLAB UNIT, CURB	6	EACH		
S-806-H	BEAM TYPE RAILING WITH CONCRETE POSTS	186	L.F.		
S-806-I	29.0' PRECAST CONCRETE CAP INTERMEDIATE UNIT, CONC. PILE	2	EACH		
S-806-J	29.0' PRECAST CONCRETE CAP END UNIT, CONC. PILE	2	EACH		
S-806-M	7.5' PRECAST CONC. WING	4	EACH		
S-815-A	LOOSE RIPRAP, 300 LB.	124	TON		
S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, A.O.S. 0.21 - 0.43	185	SQ. YD.		