

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-LSBP-29(34)
MT PLEASANT ROAD
ITAWAMBA COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-LSBP-29(34) Itawamba County, MS. The Board of Supervisors of Itawamba County, MS will receive bids for the construction of **0.099 miles of Precast Concrete Bridge and Approaches to Replace Bridge No. 109 on Mt. Pleasant Road.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **10:00 AM on the 25th day of June, 2019** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Itawamba County Courthouse, 201 West Main Street, Fulton, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Itawamba County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Carson Neal, PE, Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Eric "Tiny" Hughes, President
Itawamba County Board of Supervisors

Publish: *May 22nd, 2019 & May 29th, 2019*

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-LSBP-29(34) MT PLEASANT ROAD					
BASE BID ITEMS					
Roadway Items					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge	1.00	UN	\$	\$
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	2,290.00	CY	\$	\$
S-232-A	Geotextile Fabric Stabilization, Type V, AOS <0.43	1,298.00	SY	\$	\$
S-304-A	Granular Material (LVM) (Class 5, Group "C")	59.00	CY	\$	\$
S-304-C	Crushed Stone Size 3/4" & Down (FM)	342.00	CY	\$	\$
S-310-D	Mixing, Shaping and Compaction	939.00	SY	\$	\$
S-403-A	Hot Mix Asphalt, (ST) (9.5 mm)	142.00	TON	\$	\$
S-408-A	Asphalt for Prime Coat (EA-1) or (AE-P)	329.00	GAL	\$	\$
S-603-C-A	24" Reinforced Concrete Pipe, Class III	80.00	LF	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$
S-617-A	Right Of Way Markers, Type II	8.00	EA	\$	\$
S-618-A	Maintenance of Traffic	1.00	LS	\$	\$
S-618-B	Additional Construction Signs	-	SF	\$ \$ 10.00	\$ \$ -
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.199	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	1,050.00	LF	\$	\$
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	7.00	EA	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
Erosion Control Items					
901-S-212-A	Agricultural Limestone	2.00	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	1.00	TON	\$	\$
S-214-A	Seeding	1.00	AC	\$	\$
S-226-A	Solid Sodding	100.00	SY	\$	\$
S-227-A	Excelsior Blanket	3,852.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	625.00	LF	\$	\$
907-237-A	Wattles, 20"	280.00	LF	\$	\$
Bridge Items 4 @ 40' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Pile	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	-	EA	\$ 4000.00	\$ 0.00
S-803-C	14" Pre-stressed Concrete Piling	870.00	LF	\$	\$
S-803-F	24" Pre-Formed Pile Holes	732.00	LF	\$	\$
S-806-D	40' Precast Concrete Slab Unit, 3.5' Interior, 30 Degree Skew, Rt Fwd	24.00	EA	\$	\$
S-806-F	40' Precast Concrete Slab Unit, 3.5' Exterior, 30 Degree Skew, Rt Fwd	8.00	EA	\$	\$
S-806-G	Precast Concrete Barrier Rail	320.00	LF	\$	\$
S-806-K	36.25' Precast Concrete Cap, Intermediate Unit, Concrete Pile, 30 Degree Skew, Rt Fwd	3.00	EA	\$	\$
S-806-L	36' Precast Concrete Cap, End Unit, Concrete Pile, 30 Degree Skew, Rt Fwd	2.00	EA	\$	\$
S-806-M	11' Precast Concrete Wing	4.00	EA	\$	\$
S-815-A	Loose Riprap, 200 Lb	174.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	322.00	SY	\$	\$
TOTAL BASE BID					\$