

ADVERTISEMENT FOR BIDS

JEFFERSON COUNTY BOARD OF SUPERVISORS – Sealed bids will be received by the Board of Supervisors of Jefferson County, Mississippi at the Jefferson County Courthouse, Fayette, Mississippi until 2:00 pm on the 13th day of June, 2019 and shortly thereafter publicly opened for the construction of 0.123 miles of EMERGENCY ROAD AND BRIDGE REPAIR on the BRADY ROAD being known as Project No. ERBR-LSBP-32(9) in Jefferson County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson County, and the County Engineer's office at 204 W. Leake Street, Clinton, Mississippi 39056. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Mike McKenzie, County Engineer for Jefferson County, Mississippi, P. O. Box 318, Clinton, MS (601-925-4444). The cost is seventy five dollars (\$75.00) for plans and seventy five dollars (\$75.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

James Wells, President
Jefferson County Board of Supervisors

Please publish on Monday, May 13 and May 20, 2019.

SECTION 902
PROPOSAL SHEET (2-A)

PROJECT NO. ERBR-LSBP-32(9)
JEFFERSON COUNTY, MISSISSIPPI

For the construction of: EMERGENCY ROAD AND BRIDGE REPAIR on 0.123 mile(s) of county road known as BRADY ROAD in Jefferson County, Mississippi under Local System Bridge Program Project No. ERBR-LSBP-32(9)

I (We) agree to complete the entire project within 90 Working Days.

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
Roadway Items								
1	S-200-A	MOBILIZATION	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
3	S-202-B	REMOVAL OF EXISTING BRIDGE @ STA. 12+72.86	1.000	UN				
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	1,500.000	CY				
5	S-304-A	GRANULAR MATERIAL (LVM), (CLASS 4, GROUP E)	630.000	CY				
6	901-S-607-A	BRIDGE CONSTRUCTION SURVEYING	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
7	901-S-607-A	ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
8	S-617-A	RIGHT-OF-WAY MARKERS (TYPE I)	18.000	EA				
9	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	LS	XXXXXXXXXX	XXXXXXXXXX		
10	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF	10	00	0	00
11	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA				
Subtotal Roadway Items								
Erosion Control Items								
12	901-S-212-A	AGRICULTURAL LIMESTONE	3.100	TON				
13	S-212-B	COMMERCIAL FERTILIZER (13:13:13)	1.550	TON				
14	S-212-F	AMMONIUM NITRATE	1.000	TON				
15	S-214-A	SEEDING	1.550	AC				
16	S-215-A	VEGETATIVE MATERIALS FOR MULCH	4.650	TON				
17	226-A	TEMPORARY GRASSING	1.550	AC				
18	S-227-A	EXCELSIOR BLANKET	500.000	SY				

SECTION 902

PROJECT NO. ERBR-LSBP-32(9)
JEFFERSON COUNTY, MISSISSIPPI

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
19	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,700.000	LF				
20	237-A	WATTLES, 12"	1,800.000	LF				
21	237-A	WATTLES, 20"	1,560.000	LF				
22	S-815-A	LOOSE RIPRAP, 100 LB.	140.000	TON				
23	S-815-A	LOOSE RIPRAP, 200 LB.	520.000	TON				
24	S-815-E	GEOTEXTILE UNDER LOOSE RIP RAP (TYPE V) (AOS 0.21-0.43)	643.000	SY				
Subtotal Erosion Control Items								
Bridge Items								
25	S-803-A	TEST PILE	4.000	EA				
26	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA	4,000	00	0	00
27	S-803-C	14" PRESTRESSED CONCRETE PILING	990.000	LF				
28	S-803-C	18" PRESTRESSED CONCRETE PILING	1,100.000	LF				
29	S-803-F	14" PRE-FORMED PILE HOLES	990.000	LF				
30	S-803-F	18" PRE-FORMED PILE HOLES	1,000.000	LF				
31	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	203.600	CY				
32	901-S-804-C	40' PRESTRESSED CONCRETE BEAM TYPE I+2	397.500	LF				
33	901-S-804-C	100' PRESTRESSED CONCRETE BEAM TYPE IV	498.750	LF				
34	S-805-A	REINFORCEMENT	36,082.000	LB				
35	S-813-A	CONCRETE RAILING	360.000	LF				
36	S-815-A	LOOSE RIPRAP, 300 LB.	580.000	TON				
37	S-815-E	GEOTEXTILE UNDER LOOSE RIP RAP (TYPE V) (AOS 0.21-0.43)	955.000	SY				
Subtotal Bridge Items								
Total Bid								