

**EMERGENCY ROAD AND BRIDGE REPAIR PROJECT FOR
THE LINCOLN COUNTY BOARD OF SUPERVISORS
PROJECT NO. ERBR-LSBP-43(43)
SUMMERS LANE SE
LINCOLN COUNTY, MISSISSIPPI**

For the construction of: Bridge Replacement Project on 0.073 miles of Summers Lane over Walkers Creek in Lincoln County, Mississippi, also known as Project No. ERBR-LSBP-43(43).

Pay Item No.	Pay Item	Unit	Plan Quantity	Unit Price	Amount
Roadway Items					
S-200-A	Mobilization	Lump Sum	L.S.		
S-201-A	Clearing & Grubbing	Lump Sum	L.S.		
S-202-B	Removal of Bridge @ Station 11+74.12	Unit	1		
S-203-A	Unclassified Excavation (FM)	Cu. Yd.	700		
S-203-E1	Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 7)	Cu. Yd.	800		
S-206-A	Structure Excavation	Cu. Yd.	785		
247-A	Temporary Stream Diversion	Each	1		
S-304-A	Granular Material (LVM), (Class 4, Group B)	Cu. Yd.	720		
S-310-A-1	Size II Stabilizer Aggregate, Coarse	Cu. Yd.	275		
S-403-A	Hot Mix Asphalt, ST, 12.5mm	Ton	97.29		
S-403-A	Hot Mix Asphalt, ST, 25mm	Ton	214.15		
S-408-A	Asphalt for Prime Coat	Gallon	340.69		
S-603-C-A	18" Reinforced Concrete Pipe, Class III	Lin. Ft.	32		
S-607-A	Roadway Construction Surveying	Lump Sum	L.S.		
S-617-A	Right-Of-Way Markers (Type II)	Each	13		
S-618-A	Maintenance Of Traffic	Lump Sum	L.S.		
S-618-B	Additional Construction Signs	Sq. Ft.	0	\$10.00	\$ 0.00
S-627-L	Two-way Yellow Reflective High Performance Raised Markers	Each	11		
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	Each	4		
627-D	Barbed Wire Fence, 5 Strand	Lin. Ft.	880		
Erosion Control Items					
S-212-B	Commercial Fertilizer (13-13-13)	Ton	0.8		
S-214-A	Seeding	Acre	0.8		
S-215-A	Vegetative Materials For Mulch	Ton	2.4		
S-226-A	Solid Sodding	Sq. Yd.	200		
S-233-A	Temporary Silt Fence (Type II) (AOS 0.15-0.84)	Lin. Ft.	900		
237-A	Wattles, 20 inch	Lin. Ft.	160		

S-815-A	Loose Riprap, 300 Lb.	Ton	300		
S-815-E	Geotextile Under Loose Riprap, Type V AOS 0.21-0.43	Sq. Yd.	300		
Box Bridge Items					
901-S-804-B	Box Bridge Concrete, Class "BB"	Cu. Yd.	227.04		
S-805-A	Reinforcement	Pound	42,503		
Total Amount					