

BOARD OF ALDERMEN
CITY OF MACON, MISSISSIPPI

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Aldermen of the City of Macon, Noxubee, Mississippi at the City of **Macon City Hall**, 339 Pulaski Street, Macon, Mississippi 39341 (P.O. Box 29, Macon, MS 39341) until 5:00 p.m. on the 6th day of August, 2024 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new box Bridge and approaches on North Street being known as Project No. ERBR-LSBP-52(21) in the City of Macon, Noxubee County, Mississippi.

CONTRACT TIME: 80 Working Days

BASIS OF AWARD:

The Board of Aldermen hereby notifies all bidders that, it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the City Clerk of the City of Macon and the Project Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Engineering Plus, Inc, 1724B 23rd Avenue, Meridian, MS 39301, Phone (601) 693-4234. The cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to the City of Macon must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Phillip McGuire, Mayor
City of Macon

Advert. 7/04/2024
7/11/2024

ERBR-LSBP-52(21) North Street
SPECIAL NOTICE TO BIDDERS

PAGE 1 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 17+54.73	1.000	UNIT				
4	S-203-A	UNCLASSIFIED EXCAVATION (F.M.)	567.000	C.Y.				
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	1,917.000	C.Y.				
6	S-203-F	CHANNEL EXCAVATION (F.M.)	1,200.000	C.Y.				
7	S-203-H	EXCESS EXCAVATION (FM)	500.000	C.Y.				
8	S-206-A	STRUCTURE EXCAVATION	5,320.000	C.Y.				
9	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	626.000	C.Y.				
10	901-S-401-A	HOT MIX ASPHALT BASE COURSE (BB-1)	220.000	TON				
11	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	106.000	TON				
12	S-601-A	CLASS "C" STRUCTURAL CONCRETE	40.000	C.Y.				
13	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	11.000	EA				
14	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
15	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
16	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.148	M				
17	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	782.320	L.F.				
18	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	7.000	EA				
					ROADWAY ITEMS SUBTOTAL			
EROSION CONTROL ITEMS								
19	901-S-212-A	AGRICULTURAL LIMESTONE	3.400	TON				
20	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	1.700	TON				
21	S-214-A	SEEDING	1.700	ACRE				
22	S-215-A	VEGETATIVE MATERIALS FOR MULCH	5.100	TON				
23	S-226-A	SOLID SODDING	136.000	S.Y.				
24	S-233-A	TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	1,200.000	L.F.				
25	237-A	WATTLES, 20"	150.000	L.F.				

ERBR-LSBP-52(21) North Street
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
32	S-815-A	LOOSE RIPRAP (300 LB.)	260.000	TON				
33	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(AOS 0.21-0.43)	350.000	S.Y.				
					EROSION CONTROL ITEMS SUBTOTAL			
BOX BRIDGE ITEMS								
34	901-S-804-B	BOX BRIDGE CONCRETE, CLASS "BB"	415.570	C.Y.				
35	S-805-A	REINFORCEMENT	70,979.000	LB.				
					BOX BRIDGE ITEMS SUBTOTAL			

TOTAL BID			
-----------	--	--	--