

## **NOTICE OF ADVERTISEMENT**

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT  
PROJECT NO. ERBR-LSBP-71(16)  
COUNTY ROAD 68  
TISHOMINGO COUNTY, MISSISSIPPI**

**NOTICE TO CONTACTORS: Project No. ERBR-LSBP-71(16) Tishomingo County, MS.** The Board of Supervisors of Tishomingo County, MS will receive bids for the construction of **0.122 miles of Box Bridge and Approaches to Replace Bridge No. 70 on County Road 68.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **10:00 AM on the 19<sup>th</sup> day of August, 2019** and shortly thereafter publicly opened at the **Tishomingo County Courthouse, 1008 Battleground Drive, Iuka, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Tishomingo County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at [www.cceplanroom.com](http://www.cceplanroom.com) upon payment of \$100.00, which is non-refundable. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at [www.osarc.ms.gov/bid-calendar-erbf](http://www.osarc.ms.gov/bid-calendar-erbf). The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Greg Collier, President  
Tishomingo County Board of Supervisors

Publish: *July 11<sup>th</sup> and July 18, 2019*

## BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

**Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.**

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit
<b>ERBR-LSBP-71(16) COUNTY ROAD 68</b>			
<b>BASE BID ITEMS</b>			
<b>Roadway Items</b>			
S-200-A	Mobilization	1.00	LS
S-201-A	Clearing & Grubbing	1.00	LS
S-202-B	Removal of Existing Bridge	1.00	UN
S-203-A	Unclassified Excavation (FM)	1,212.00	CY
S-203-E1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	1,056.00	CY
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	2,528.00	SY
S-304-A	Granular Material (Class 5, Group "C")(LVM)	78.00	CY
S-304-C	Crushed Stone Size 3/4" & Down (FM)	656.00	CY
S-310-D	Mixing, Shaping and Compaction	1,722.00	SY
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	259.00	TON
S-408-A	Asphalt for Prime Coat (EA-1) or (AE-P)	603.00	GAL
S-603-PE	24" Corrugated Polyethylene Pipe	32.00	LF
S-607-A	Roadway Construction Surveying	1.00	LS
S-617-A	Right Of Way Markers, Type I	10.00	EA
S-618-A	Maintenance of Traffic	1.00	LS
S-618-B	Additional Construction Signs	-	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.265	MI
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	1,400.00	LF

# BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	15.00	EA
S-630-G	Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	2.00	EA
247-A	Temporary Stream Diversion	1.00	EA
<b>Erosion Control Items</b>			
901-S-212-A	Agricultural Limestone	1.84	TON
S-212-B	Commercial Fertilizer (13-13-13)	0.92	TON
S-212-F	Ammonium Nitrate	0.23	TON
S-214-A	Seeding	0.92	AC
S-226-A	Solid Sodding	100.00	SY
S-227-A	Excelsior Blanket	2,808.00	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,400.00	LF
S-815-A	Loose Riprap, 300 Lb	100.00	TON
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	100.00	SY
237-A	Wattles, 20"	200.00	LF
<b>Box Bridge Items @ 24+76.42 44' - 12' x 6' Double Box Bridge 2:1 Wings; Rt. Fw</b>			
901-S-804-B	Box Bridge Concrete, Class "BB"	139.31	CY
S-805-A	Reinforcement	27,654.00	LB