

## **NOTICE OF ADVERTISEMENT**

EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT  
**PROJECT NO. ERBR-LSBP-71(18)**  
**STRUCTURE NO. SA710000000010 COUNTY ROAD 291**  
**TISHOMINGO COUNTY, MISSISSIPPI**

**NOTICE TO CONTACTORS: Project No. ERBR-LSBP-71(18) Tishomingo County, MS.** The Board of Supervisors of Tishomingo County, MS will receive bids for the construction of **Bridge and Approaches to Replace Structure No. SA710000000010 on County Road 291.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **9:00 AM on the 18<sup>th</sup> day of May, 2026** and shortly thereafter publicly opened at the **Tishomingo County Courthouse, 1008 Battleground Drive, Iuka, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Tishomingo County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at [www.cceplanroom.com](http://www.cceplanroom.com). Project information is also available on the website of the Mississippi Office of State Aid Road Construction at [www.osarc.ms.gov/bid-calendar-erbf](http://www.osarc.ms.gov/bid-calendar-erbf). The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Michael Busby, President  
Tishomingo County Board of Supervisors

Publish: *April 9<sup>th</sup> and April 16, 2026*

## ERBR-LSBP-71(18) ESTIMATED QUANTITIES

Item No.	Item Description	Estimated Quantity	Unit
<b>ERBR-LSBP-71(18) COUNTY ROAD 291</b>			
<b>BASE BID ITEMS</b>			
<b>Roadway Items</b>			
S-200-A	Mobilization	1.0	LS
S-201-A	Clearing and Grubbing	1.0	LS
S-202-B	Removal of Existing Bridge @ Sta. 25+07.03	1.0	UN
S-202-D	Removal of Pavement (All Depth)	847.0	SY
S-203-A	Unclassified Excavation (PM)	257.0	CY
S-203-E1	Borrow Excavation (PM) (Contractor Furnished) (Class 9)	1,505.0	CY
S-203-H	Excess Excavation (PM)	56.0	CY
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	1,743.0	SY
S-304-A	Granular Material (PM) (Class 5, Group"C")	52.0	CY
S-304-C	Crushed Stone (3/4" & down) (PM)	572.0	CY
S-403-A	Hot Mix Asphalt, 9.5 mm	494.0	TON
S-408-A	Asphalt for Prime Coat (EA-1) or (AE-P)	442.0	GAL
S-603-PE	24" Corrugated Polyethylene Pipe	35.0	LF
S-603-PE	36" Corrugated Polyethylene Pipe	40.0	LF
S-606-B	Guardrail, "W" Beam	112.5	LF
S-606-D	Guardrail, Bridge End Section, Type I Thrie Beam (Complete in Place)	3.0	EA
S-606-E	Guardrail, (Terminal End Section)	3.0	EA
901-S-607-A	Roadway Construction Surveying	1.0	LS
607-D	Barbed Wire Fence (5 Strands, 12 1/2 Gage Galvanized Barbed Wire, Barbs 14 Gage Round 4 Point (5" O.C.))	1,050.0	LF
607-G	Gate (16' Galvanized 2" Steel Tube, 50" High)	1.0	EA
607-PI	Line Post (6'-6", Galvanized Steel Rail Studded "T" Section)	16.0	EA
607-P2	Brace Post (8'-0", 4"x 6" Timber Post)	5.0	EA
607-P2	Brace Post (8'-0", 6"x 6" Timber Post)	5.0	EA
607-P3	Gate Post (8'-0", 6"x 6" Timber Post)	4.0	EA
607-Z	Concrete Anchors	9.0	EA
S-617-A	Right of Way Markers (Type I)	12.0	EA
S-618-A	Maintenance of Traffice	1.0	LS
S-618-B	Additional Construction Signs	0.0	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	0.236	MI

Item No.	Item Description	Estimated Quantity	Unit
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	1,250.0	LF
S-627-L	Two- Way Yellow Reflective High Performance Raised Markers	10.0	EA
S-630-A	Relectorized Traffic Warning Sign (Encapsulated Lens)	5.0	EA
S-630-C	Relectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.0	EA
S-630-G	Reflectorized Traffic Warning Sign with Supp. Plate (Encapsulated Lens)	2.0	EA
<b>Erosion Control Items</b>			
901-S-212-A	Agricultural Limestone	1.0	TON
S-212-B	Commerical Fertilizer (13-13-13)	0.5	TON
S-212-F	Ammonium Nitrate	0.13	TON
S-214-A	Seeding	0.5	ACRE
S-226-A	Solid Sodding	100.0	SY
S-227-A	Excelsior Blanket	2,420.0	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,225.0	LF
237-A	Wattles, 20"	160.0	LF
S-815-A	Loose Riprap, 200 Lb.	90.0	TON
S-815-E	Geotextile Under Riprap (Type V) (AOS <0.43)	100.0	SY
<b>Bridge Items STA. 25+05.17, 1 @ 31', 1 @ 40', 1 @ 31' Precast Concrete Span Bridge, 28' Clear Roadway</b>			
901-S-607-B	Bridge Construction Surveying	1.0	LS
S-803-A	Test Pile	2.0	EA
S-803-B	Conventional Static Pile Load Test	0.0	EA
S-803-E	14" Steel Piling	720.0	LF
S-803-F	18" Pre-Formed Pile Hole	400.0	LF
901-S-804-A	Bridge Concrete, Class "A"	53.0	CY
S-805-A	Reinforcement	8,760.0	Lbs
S-806-A	31' Precast Concrete Slab Unit, 3.5 Interior	12.0	EA
S-806-A	40' Precast Concrete Slab Unit, 3.5 Interior	6.0	EA
S-806-C	31' Precast Concrete Slab Unit, 3.5 Exterior	4.0	EA
S-806-C	40' Precast Concrete Slab Unit, 3.5 Exterior	2.0	EA
S-806-G	Precast Concrete Barrier Rail	204.0	LF
S-815-A	Loose Riprap, 300 Lb.	335.0	TON
S-815-E	Geotextile Under Riprap (Type V Non-Woven), AOS <0.43	339.0	SY