

NOTICE OF ADVERTISEMENT

EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-SAP-05(56)
STRUCTURE NO. SA0500000000035 BECK SPRINGS ROAD
BENTON COUNTY, MISSISSIPPI

NOTICE TO CONTACTORS: Project No. ERBR-SAP-05(56) Benton County, MS. The Board of Supervisors of Benton County, MS will receive bids for the construction of **0.171 miles of Bridge and Approaches to Replace Structure No. SA0500000000035 on Beck Springs Road.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **9:00 AM on the 18th day of September, 2023** and shortly thereafter publicly opened at the **Benton County Courthouse, 190 Ripley Avenue, Ashland, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Benton County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at www.cceplanroom.com upon payment of \$100.00, which is non-refundable. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at www.osarc.ms.gov/bid-calendar-erbf. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ricky Pipkin, President
Benton County Board of Supervisors

Publish: *August 16th & August 23, 2023*

PROJECT NO. ERBR-SAP-05(56)
STRUCTURE NO. SA050000000035 BECK SPRINGS ROAD
BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
ERBR-SAP-05(56) BECK SPRINGS ROAD			
BASE BID ITEMS			
Roadway Items			
S-200-A	Mobilization	1.00	LS
S-201-A	Clearing & Grubbing	1.00	LS
S-202-B	Removal of Existing Bridge @ Sta. 382+70	1.00	UN
S-202-B	Removal of Drainage Structures	3.00	UN
S-202-E	Removal of Pipe, All Sizes	221.00	LF
S-203-A	Unclassified Excavation (FM)	2,065.00	CY
S-203-E	Borrow Material (FME)	100.00	CY
S-303-H	Excess Excavation (LVM)	2,093.00	CY
S-232-A	Geotextile Under Riprap, (Type V) (AOS <0.43)	3,230.00	SY
S-304-A	Granular Material (LVM)(Class 5, Group "C")	227.00	CY
S-304-C	Crushed Stone (3/4" & Down) (FM)	766.00	CY
S-310-D	Mixing, Shaping and Compaction	2,023.00	SY
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	363.00	TON
S-408-A	Asphalt for Prime Coat (AE-P or EA-1)	648.00	GAL
S-601-B	Class "B" Structural Concrete , Minor Structures	1.779	CY
S-602-A	Reinforcing Steel	119.300	LB
S-603-C-A	24" Reinforced Concrete Pipe, Class III	102.00	LF
S-603-C-A	36" Reinforced Concrete Pipe, Class III	180.00	LF
S-604-A	Castings	244.00	LB
S-604-B	Gratings	200.00	LB
S-606-B	Guardrail "W" Beam	100.00	LF
S-606-D	Guardrail, Bridge End Section , Type "I" Thrie Beam	4.00	EA
S-606-E	Guardrail, Terminal End Section	4.00	EA
S-607-A	Roadway Construction Surveying	1.00	LS
S-617-A	Right of Way Markers, Type II	11.00	EA

PROJECT NO. ERBR-SAP-05(56)
STRUCTURE NO. SA050000000035 BECK SPRINGS ROAD
BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-618-A	Maintenance of Traffic	1.00	LS
S-618-B	Additional Construction Signs	0.00	SF
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.341	MILE
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 Mils)	1,800.000	LF
S-627-L	Two Way Yellow Reflective High Performance Raised Markers	14.000	EA
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	14.00	EA
Erosion Control Items			
901-S-212-A	Agricultural Limestone	2.66	TON
S-212-B	Commercial Fertilizer (13-13-13)	1.33	TON
S-212-F	Ammonium Nitrate	0.19	TON
S-214-A	Seeding	1.40	AC
S-215-A	Vegetative Materials for Mulch	2.66	TON
S-226-A	Solid Sodding	100.00	SY
S-227-A	Excelsior Blanket	1,250.00	SY
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	800.00	LF
S-815-A	Loose Riprap, Size 200 Lb	368.00	TON
S-815-E	Geptextile Under Riprap (Type V) Non-Woven, AOS <0.43	371.00	SY
237-A	Wattles, 20"	300.00	LF
Bridge Items Sta. 382+56 - 3 @ 40' Precast Concrete Beam Bridge			
S-607-B	Bridge Constuction Surveying	1.00	LS
S-803-A	Test Pile	2.00	EA
S-803-B	Conventional Static Pile Load Test	0.00	EA
S-804-C	14" Prestressed Concrete Piling	896.40	LF
S-803-F	18" Pre-Formed Pile Holes	696.76	LF
901-S-804-A	Bridge Concrete, Class "A"	46.04	CY
S-805-A	Reinforcement	9,152.00	LB

PROJECT NO. ERBR-SAP-05(56)
STRUCTURE NO. SA050000000035 BECK SPRINGS ROAD
BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit
S-806-A	40' Precast Concrete Slab Unit, 3.5' Interior	18.00	EA
S-806-C	40' Precast Concrete Slab Unit, 3.5' Exterior	6.00	EA
S-806-G	Precast Concrete Barrier Rail	240.00	LF
S-815-A	Loose Riprap, Size 200 Lb	536.00	TON
S-815-E	Geotextile Under Riprap (Type V) (AOS <0.43)	605.00	SY