

KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:30 a.m. on the 16th day of August, 2024 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new structure and approaches – 3 @ 40' on the Warren Town Road being known as Project No. ERBR-SAP-35(74) in Kemper County, Mississippi.

CONTRACT TIME: 90 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that, it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Kemper County, Mississippi, 1724B 23rd Avenue, Meridian, MS 39301. The cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Scott Johnson, President
Kemper County Board of Supervisors

Advert. July 18, 2024
July 25, 2024

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
ROADWAY ITEMS								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 141+94.00	1.000	UNIT				
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	653.000	C.Y.				
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	4,095.000	C.Y.				
6	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	303.000	C.Y.				
7	S-304-C	CRUSHED STONE, SIZE 610 (L.V.M.)	132.000	C.Y.				
8	901-S-401-A	HOT MIX ASPHALT BASE COURSE (BB-1)	349.000	TON				
9	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	134.000	TON				
10	S-603-C-A	24" REINFORCED CONCRETE PIPE, CLASS III	120.000	L.F.				
11	S-606-B	GUARDRAIL, W-BEAM	75.000	L.F.				
12	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA.				
13	S-606-E	GUARDRAIL, TERMINAL END SECTION	4.000	EA.				
14	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA.				
15	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
16	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
17	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.303	MILE				
18	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	1,600.000	L.F.				
19	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	18.000	EA.				
20	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
					ROADWAY ITEMS SUBTOTAL			
EROSION CONTROL ITEMS								
21	S-226-A	SOLID SODDING	192.000	S.Y.				
22	901-S-228-A	HYDROSEEDING	1.290	ACRE				
23	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	5.680	C.Y.				
24	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,500.000	L.F.				
25	237-A	WATTLES, 20"	200.000	L.F.				
26	S-815-A	LOOSE RIPRAP, 200 LB.	178.000	TON				
27	S-815-E	GEOTEXTILE UNDER 200 LB. RIPRAP, TYPE V, NON-WOVEN <0.43	410.000	S.Y.				
					EROSION CONTROL ITEMS SUBTOTAL			

SECTION 902
PROPOSAL SHEET

ERBR-SAP-35(74) Warren Town Road
SPECIAL NOTICE TO BIDDERS

PAGE 2 OF 2

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
BRIDGE ITEMS								
28	S-803-A	TEST PILES	2.000	EA.				
29	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA.	4,000	00		
30	S-803-C	14" PRESTRESSED CONCRETE PILING	950.000	L.F.				
31	S-803-F	18" PRE-FORMED PILE HOLES	880.000	L.F.				
32	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	139.290	C.Y.				
33	901-S-804-C	40 FT. PRESTRESSED CONCRETE BEAM, TYPE I + 2	596.250	L.F.				
34	S-805-A	REINFORCEMENT	24,702.000	L.B.				
35	S-813-A	CONCRETE RAILING	240.000	L.F.				
36	S-815-A	LOOSE RIPRAP (300 LB.)	276.000	TON				
37	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(NON-WOVEN)(<0.43)	650.000	S.Y.				
					BRIDGE ITEMS SUBTOTAL			

TOTAL BASE BID	
-----------------------	--