

KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:00 a.m. on the 16<sup>th</sup> day of February, 2023 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new structure and approaches – 2@31', 1@100' and 2@31' on the Firetower Road being known as Project No. ERBR-SAP-35(75) in Kemper County, Mississippi.

CONTRACT TIME: 140 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that, it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Kemper County, Mississippi, 1724B 23<sup>rd</sup> Avenue, Meridian, MS 39301. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ James "Pat" Granger, President  
Kemper County Board of Supervisors

Advert. December 29, 2022  
January 5, 2023

ERBR-SAP-35(75) Firetower Road  
\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>ROADWAY ITEMS</b>								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 73+71.00	1.000	UNIT				
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	564.000	C.Y.				
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	6,869.000	C.Y.				
6	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	849.000	C.Y.				
7	S-310-A-1	SIZE I STABILIZER AGGREGATE, COARSE	23.000	C.Y.				
8	901-S-401-A	HOT MIX ASPHALT BASE COURSE (BB-1)	565.000	TON				
9	901-S-403-D	HOT BITUMINOUS PAVEMENT SURFACE COURSE (SC-1)(TYPE 8)	190.000	TON				
10	S-603-C-A	24" REINFORCED CONCRETE PIPE, CLASS III	48.000	L.F.				
11	S-603-C-B	24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA.				
12	S-606-B	GUARDRAIL, W-BEAM	75.000	L.F.				
13	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA.				
14	S-606-E	GUARDRAIL, TERMINAL END SECTION	4.000	EA.				
15	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	9.000	EA.				
16	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
17	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
18	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.454	MILE				
19	S-621-D	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW)(120 MIL)	0.227	MILE				
20	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	665.000	L.F.				
21	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	15.000	EA.				
22	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
<b>ROADWAY ITEMS SUBTOTAL</b>								
<b>EROSION CONTROL ITEMS</b>								
23	S-226-A	SOLID SODDING	218.000	S.Y.				
24	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	8.020	C.Y.				
25	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,300.000	L.F.				
26	237-A	WATTLES, 20"	200.000	L.F.				
27	S-815-A	LOOSE RIPRAP, 200 LB.	128.000	TON				
28	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, TYPE V, AOS 0.21-0.43	300.000	S.Y.				

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>EROSION CONTROL ALTERNATES (SELECT ONLY ONE)</b>								
<b>ALTERNATE NO. 1</b>								
29	901-S-212-A	AGRICULTURAL LIMESTONE	3.560	TON				
30	S-212-B	COMMERCIAL FERTILIZER (13-13-13)	1.780	TON				
31	S-212-F	AMMONIUM NITRATE	0.500	TON				
32	S-214-A	SEEDING	1.780	ACRE				
33	S-215-A	VEGETATIVE MATERIALS FOR MULCH	5.340	TON				
					<b>TOTAL ALT. NO. 1</b>			
<b>ALTERNATE NO. 2</b>								
34	901-S-228-A	HYDROSEEDING	1.780	ACRE				
					<b>TOTAL ALT. NO. 2</b>			
					<b>EROSION CONTROL ITEMS SUBTOTAL</b>			
<b>BRIDGE ITEMS</b>								
35	S-803-A	TEST PILES	2.000	EA.				
36	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA.	4,000	00		
37	S-803-C	14" PRESTRESSED CONCRETE PILING	810.000	L.F.				
38	S-803-C	16" PRESTRESSED CONCRETE PILING	500.000	L.F.				
39	S-803-C	18" PRESTRESSED CONCRETE PILING	900.000	L.F.				
40	S-803-F	18" PRE-FORMED PILE HOLES	720.000	L.F.				
41	S-803-F	20" PRE-FORMED PILE HOLES	360.000	L.F.				
42	S-803-F	22" PRE-FORMED PILE HOLES	720.000	L.F.				
43	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	248.660	C.Y.				
44	901-S-804-C	31 FT. PRESTRESSED CONCRETE BEAM, TYPE I + 2	615.000	L.F.				
45	901-S-804-C	100 FT. PRESTRESSED CONCRETE BEAM, TYPE IV	498.750	L.F.				
46	S-805-A	REINFORCEMENT	44,404.000	L.B.				
47	S-813-A	CONCRETE RAILING	448.000	L.F.				
48	S-815-A	LOOSE RIPRAP (300 LB.)	610.000	TON				
49	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, (TYPE V)(NON-WOVEN)(<0.43)	1,170.000	LB.				
					<b>BRIDGE ITEMS SUBTOTAL</b>			

<b>TOTAL BASE BID</b>		
-----------------------	--	--