

# LAUDERDALE COUNTY BOARD OF SUPERVISORS

## SECTION 900

### NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lauderdale County, Mississippi at the Lauderdale County Government Center located at 612 22<sup>nd</sup> Avenue South (2<sup>nd</sup> Floor), Meridian, Mississippi, until 10:00 a.m. on Friday the 12th day of January, 2024 and shortly thereafter publicly opened for the construction of 0.169 miles of BRIDGE & ROADWAY CONSTRUCTION on Pine Springs Road being known as Project No. ERBR-SAP-38(98) in Lauderdale County, Mississippi. Work involves removing two (2) existing concrete bridges and constructing a new 3@40' prestressed concrete beam bridge and roadway approaches. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction. Contractors have the option of submitting bids either electronically by Central Bidding, [www.centralbidding.com](http://www.centralbidding.com) or paper sealed bids addressed and delivered to the Lauderdale County Board of Supervisors, at the time and date noted above.

### BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

OFFICIAL BID DOCUMENTS may be secured from either of the following locations:

1. Richmond L. Alexander, Engineer for Lauderdale County Mississippi, at 1724-B 23<sup>rd</sup> Avenue, Meridian, MS 39301. The cost is fifty dollars (\$50.00) for the plans and fifty (\$50.00) for the proposal, non-refundable.
2. Download from Central Bidding at [www.centralbidding.com](http://www.centralbidding.com). Electronic bids can be submitted at [www.centralbidding.com](http://www.centralbidding.com). For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lauderdale County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ Jonathan Wells, President  
Lauderdale County Board of Supervisors

Advert. December 12, 2023  
December 19, 2023

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>ROADWAY ITEMS</b>								
1	S-200-A	MOBILIZATION	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
3	S-202-B	REMOVAL OF BRIDGE AT STA. 20+13.11 AND STA. 23+93.18	2.000	UNIT				
4	S-202-E	REMOVAL OF PIPE (ALL SIZES)	140.000	L.F.				
5	S-203-A	UNCLASSIFIED EXCAVATION (FM)	5,715.000	C.Y.				
6	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	2,283.000	C.Y.				
7	S-203-H	EXCESS EXCAVATION (FM)	500.000	C.Y.				
8	S-304-A	GRANULAR MATERIAL (L.V.M.)(CLASS 9, GROUP B)	1,251.000	C.Y.				
9	S-304-C	CRUSHED STONE, SIZE 610 (L.V.M.)	120.000	C.Y.				
10	S-403-A	HOT MIX ASPHALT, ST, 9.5MM	218.000	TON				
11	S-403-A	HOT MIX ASPHALT, ST, 19MM	439.000	TON				
12	S-601-B	CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	3.550	C.Y.				
13	S-603-C-A	36" REINFORCED CONCRETE PIPE, CLASS III	48.000	L.F.				
14	S-603-C-A	48" REINFORCED CONCRETE PIPE, CLASS III	128.000	L.F.				
15	S-606-B	GUARDRAIL, W-BEAM	75.000	L.F.				
16	S-606-D	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM	4.000	EA.				
17	S-606-E	GUARDRAIL, TERMINAL END SECTION	4.000	EA.				
18	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA.				
19	S-618-A	MAINTENANCE OF TRAFFIC	1.000	L.S.	XXXXXXXXXXXX	XXXXXXXXXXXX		
20	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	S.F.	10	00	0	00
21	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE)(90 MIL)	0.340	MILE				
22	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)(120 MIL)	1,800.000	L.F.				
23	S-627-L	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	17.000	EA.				
24	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA.				
<b>ROADWAY ITEMS SUBTOTAL</b>								
<b>EROSION CONTROL ITEMS</b>								
25	S-226-A	SOLID SODDING	155.000	S.Y.				
26	901-S-228-A	HYDROSEEDING	2.060	ACRE				
27	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	3.550	C.Y.				
28	S-233-A	TEMPORARY SILT FENCE (TYPE II)(AOS 0.15-0.84)	1,600.000	L.F.				
29	237-A	WATTLES, 20"	200.000	L.F.				
30	S-815-A	LOOSE RIPRAP (200 LB.)	270.000	TON				
<b>EROSION CONTROL ITEMS SUBTOTAL</b>								

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total		
					Dollars	Cents	Dollars	Cents	
<b>BRIDGE ITEMS</b>									
31	S-803-A	TEST PILES	2.000	EA.					
32	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA.	4,000	00			
33	S-803-C	14" PRESTRESSED CONCRETE PILING	630.000	L.F.					
34	S-803-C	16" PRESTRESSED CONCRETE PILING	320.000	L.F.					
35	S-803-F	18" PRE-FORMED PILE HOLES	500.000	L.F.					
36	S-803-F	20" PRE-FORMED PILE HOLES	200.000	L.F.					
37	901-S-804-A	BRIDGE CONCRETE, CLASS "A"	140.130	C.Y.					
38	901-S-804-C	40 FT. PRESTRESSED CONCRETE BEAM, TYPE I & 2	596.250	L.F.					
39	S-805-A	REINFORCEMENT	25,552.000	LB.					
40	S-813-A	CONCRETE RAILING	240.000	L.F.					
41	S-815-A	LOOSE RIPRAP (300 LB.)	345.000	TON					
42	S-815-E	GEOTEXTILE UNDER 300 LB. RIPRAP, TYPE V, NON WOVEN, AOS<0.43	780.000	S.Y.					
					BRIDGE ITEMS SUBTOTAL				
					<b>TOTAL BID</b>				