

## SHARKEY COUNTY BOARD OF SUPERVISORS

### SECTION 900

Sealed bids will be received by the Board of Supervisors of Sharkey County, Mississippi at the Sharkey County Courthouse, Rolling Fork, Mississippi, until 10:00 am on the 17th day of May 2024 and shortly thereafter publicly opened for the construction of 0.308 miles of BRIDGE REPLACEMENT AND APPROACHES on the LOW WATER BRIDGE ROAD being known as Project No. ERBR-SAP-63(26) in Sharkey County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of SHARKEY County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sharkey County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Leroy Smith, President  
Sharkey County Board of Supervisors

Advertise: April 18, 2024  
April 25, 2024

For the construction of: 0.308 miles of Bridge Replacement and Approaches on Low Water Bridge Road, Sharkey County, MS

I (We) agree to complete the entire project within 220 Working Days

\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price	Item Total
					Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE STA. (40+70)	1	Unit		
4	S-202-D	REMOVAL OF PAVEMENT	2435	Sq.Yd.		
5	S-203-A	UNCLASSIFIED EXCAVATION (FM)	250	Cu.Yd.		
6	S-203-E1	BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	10500	Cu.Yd.		
7	S-203-F	CHANNEL EXCAVATION (FM)	100	Cu.Yd.		
8	S-304-D	CRUSHED STONE	2100	Ton		
9	S-403-A	HOT MIX ASPHALT, ST, 12.5 mm	325	Ton		
10	S-403-A	HOT MIX ASPHALT, ST, 25 mm	600	Ton		
11	S-606-B	GUARD RAIL,"W" BEAM, COMPLETE-IN-PLACE	50	Lin.Ft.		
12	S-606-C	GUARD RAIL, CABLE ANCHOR, TYPE 1	25	Lin.Ft.		
13	S-606-D	GUARD RAIL, BRIDGE END SECTION TYPE "G", "W" BEAM	4	Each		

14	S-606-E	GUARD RAIL, ROUNDED "W" END SECTION	4	Each		
15	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	24	Each		
16	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
17	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
18	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) (60 mil)	0.616	Mile		
19	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW) (60 mil)	3250	Lin.Ft.		
20	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4	Each		
Subtotal Roadway Items:						
Erosion Control Items						
21	901-S-212-A	AGRICULTURAL LIMESTONE	2.4	Ton		
22	S-212-B	COMMERCIAL FERTILIZER ( 13 : 13 : 13 )	1.2	Ton		
23	S-214-A	SEEDING	1.2	Acre		
24	S-215-A	VEGETATIVE MATERIALS FOR MULCH	3.6	Ton		
25	S-233-A	TEMPORARY SILT FENCE (TYPE II ) (AOS 0.15-0.84 )	1800	Lin.Ft.		
26	907-237-A	WATTLES, 20"	400	Lin.Ft.		
Subtotal Erosion Control Items:						

Bridge Items						
27	S-803-A	TEST PILE	4	Each		
28	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	1	Each		
29	S-803-E	14" STEEL PILING	8000	Lin.Ft.		
30	S-803-F	18" PRE-FORMED PILE HOLE	320	Lin.Ft.		
31	901-S-804-A	BRIDGE CONCRETE, CLASS A	350	Cu.Yd.		
32	S-805-A	REINFORCEMENT	38000	Lb.		
33	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4	Each		
34	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2	Each		
35	S-806-A	40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	56	Each		
36	S-806-A	40' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	28	Each		
37	S-806-C	19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2	Each		
38	S-806-C	40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	28	Each		
39	S-806-G	PRECAST CONCRETE BARRIER RAIL	1158	Lin.Ft.		
40	S-815-A	LOOSE RIPRAP, 300 LB.	400	Ton		
41	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	700	Sq. Yd.		
					Subtotal Bridge Items:	
					<b>Total Bid:</b>	