

SHARKEY COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Sharkey County, Mississippi at the Sharkey County Courthouse, Rolling Fork, Mississippi, until 10:00 am on the 30th day of August 2024 and shortly thereafter publicly opened for the construction of 0.307 miles of BRIDGE REPLACEMENT AND APPROACHES on the LOW WATER BRIDGE ROAD being known as Project No. ERBR-SAP-63(26) in Sharkey County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Sharkey County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sharkey County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Leroy Smith, President
Sharkey County Board of Supervisors

Advertise: August 1, 2024
August 8, 2024

SECTION 902
PROPOSAL SHEET

Project No. ERBR-SAP-63(26)
Sharkey County , Mississippi

For the construction of: 0.307 miles of Bridge Replacement and Approaches on Low Water Bridge Road, Sharkey County, MS

I (We) agree to complete the entire project within 220 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Dollars & Cents	Dollars & Cents
ROADWAY ITEMS						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE STA. (40+70)	1	Unit		
4	S-202-D	REMOVAL OF PAVEMENT	2435	Sq.Yd.		
5	S-203-A	UNCLASSIFIED EXCAVATION (FM)	250	Cu.Yd.		
6	S-203-E1	BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	10500	Cu.Yd.		
7	S-203-F	CHANNEL EXCAVATION (FM)	100	Cu.Yd.		
8	S-304-D	CRUSHED STONE	2100	Ton		
9	S-403-A	HOT MIX ASPHALT, ST, 12.5 mm	325	Ton		
10	S-403-A	HOT MIX ASPHALT, ST, 25 mm	600	Ton		
11	S-606-B	GUARD RAIL,"W" BEAM, COMPLETE-IN-PLACE	50	Lin.Ft.		
12	S-606-C	GUARD RAIL, CABLE ANCHOR, TYPE 1	25	Lin.Ft.		
13	S-606-D	GUARD RAIL, BRIDGE END SECTION TYPE "G", "W" BEAM	4	Each		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-SAP-63(26)
Sharkey County , Mississippi

14	S-606-E	GUARD RAIL, ROUNDED "W" END SECTION	4	Each		
15	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	24	Each		
16	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
17	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq.Ft.		
18	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) (60 mil)	0.616	Mile		
19	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW) (60 mil)	3250	Lin.Ft.		
20	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4	Each		
Subtotal Roadway Items:						
EROSION CONTROL ITEMS						
21	901-S-212-A	AGRICULTURAL LIMESTONE	2.4	Ton		
22	S-212-B	COMMERCIAL FERTILIZER (13 : 13 : 13)	1.2	Ton		
23	S-214-A	SEEDING	1.2	Acre		
24	S-215-A	VEGETATIVE MATERIALS FOR MULCH	3.6	Ton		
25	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1800	Lin.Ft.		
26	907-237-A	WATTLES, 20"	400	Lin.Ft.		
Subtotal Erosion Control Items:						

BRIDGE ITEMS						
27	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	4	Each		
28	S-806-A	19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	2	Each		
29	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	72	Each		
30	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	36	Each		
31	S-806-C	19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2	Each		
32	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	36	Each		
33	S-806-G	PRECAST CONCRETE BARRIER RAIL	1158	Lin.Ft.		
34	S-815-A	LOOSE RIPRAP, 300 LB.	400	Ton		
35	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	700	Sq. Yd.		
Subtotal Bridge Items:						
CONCRETE AND STEEL PILING						
36	S-803-A	TEST PILE	6	Each		
37	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	1	Each		
38	S-803-C	18" CONCRETE PILING	5200	Lin.Ft.		
39	S-803-E	14" STEEL PILING	3300	Lin.Ft.		
40	S-803-F	24" PRE-FORMED PILE HOLE	400	Lin.Ft.		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-SAP-63(26)
Sharkey County , Mississippi

41	901-S-804-A	BRIDGE CONCRETE, CLASS A	375	Cu.Yd.		
42	S-805-A	REINFORCEMENT	47000	Lb.		
Subtotal Concrete and Steel Piling Items:						

ALTERNATE BID - STEEL PILING						
43	S-803-A	TEST PILE	6	Each		
44	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	1	Each		
45	S-803-E	14" STEEL PILING	9500	Lin.Ft.		
46	S-803-F	18" PRE-FORMED PILE HOLE	400	Lin.Ft.		
47	901-S-804-A	BRIDGE CONCRETE, CLASS A	440	Cu.Yd.		
48	S-805-A	REINFORCEMENT	45000	Lb.		
Subtotal ALTERNATE BID - Steel Piling Items:						
Total Bid:						