

ISSAQUENA COUNTY BOARD OF SUPERVISORS

SECTION 900

Sealed bids will be received by the Board of Supervisors of Issaquena County, Mississippi at the Issaquena County Courthouse, Mayersville, Mississippi, until 11:00 am on 15th day of December, 2020 and shortly thereafter publicly opened for the construction of 0.175 miles of BRIDGE REPLACEMENT AND APPROACHES on the GREENFIELD ROAD being known as Project No. ERBR-STP-BR-0553(6)B in Issaquena County, Mississippi.

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of ISSAQUENA County and the Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Hooker Engineering Services, Inc., P. O. Box 368, Greenville, MS 38702. The cost is one hundred twenty-five dollars (\$125.00) for plans and proposals, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Issaquena County must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

William Holcomb, III, President
Issaquena County Board of Supervisors

Advertise: November 12, 2020
November 19, 2020

SECTION 902
PROPOSAL SHEET

Project No. ERBR-STP-BR-0553(6)B
Issaquena County , Mississippi

For the construction of: 0.175 miles of Bridge Replacement and Approaches on Greenfield Road, Issaquena County, MS

I (We) agree to complete the entire project within 180 Working Days

SPECIAL NOTICE TO BIDDERS

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

					Unit Price	Item Total
Ref. No.	Pay Item No.	Description	Approx. Quantitiy	Unit	Dollars & Cents	Dollars & Cents
Roadway Items						
1	S-200-A	MOBILIZATION	Lump Sum	Lump Sum		
2	S-201-A	CLEARING AND GRUBBING	Lump Sum	Lump Sum		
3	S-202-B	REMOVAL OF BRIDGE (STA. 15+99.64)	1	Unit		
4	S-203-A	UNCLASSIFIED EXCAVATION (FM)	1900	Cu. Yd.		
5	S-203-E1	BORROW EXCAVATION (F.M.E.)(CONTRACTOR FURNISHED)(CLASS 9)	1100	Cu. Yd.		
6	S-203-F	CHANNEL EXCAVATION (FM)	56	Cu. Yd.		
7	S-304-D	CRUSHED STONE	1850	Ton		
8	S-403-A	HOT MIX ASPHALT, ST, 12.5 mm	300	Ton		
9	S-403-A	HOT MIX ASPHALT, ST, 25 mm	600	Ton		
10	S-603-M-A	36" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORRUGATION	60	Lin. Ft.		
11	S-606-B	GUARD RAIL,"W" BEAM, COMPLETE-IN-PLACE	237.5	Lin. Ft.		
12	S-606-C	GUARD RAIL, CABLE ANCHOR, TYPE 1	12.5	Lin. Ft.		
13	S-606-D	GUARD RAIL, BRIDGE END SECTION TYPE "I", THRIE BEAM, COMPLETE-IN-PLACE	4	Each		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-STP-BR-0553(6)B
Issaquena County , Mississippi

14	S-606-E	GUARD RAIL, TERMINAL END SECTION	2	Each		
15	S-617-A	RIGHT-OF-WAY MARKERS (TYPE II)	11	Each		
16	S-618-A	MAINTENANCE OF TRAFFIC	Lump Sum	Lump Sum		
17	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0	Sq. Yd.		
18	S-621-C	4" WIDE THERMOPLASTIC EDGE STRIPE (CONT. WHITE) (60 mil)	0.4	Mile		
19	S-621-E-1	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONT. YELLOW)(90 mil)	1850	Lin. Ft.		
20	S-630-C	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4	Each		
21	S-815-A	LOOSE RIPRAP (300LB.)	200	Ton		
22	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	350	Sq. Yd.		
Subtotal Roadway Items:						
Erosion Control Items						
23	901-S-212-A	AGRICULTURAL LIMESTONE	2	Ton		
24	S-212-B	COMMERCIAL FERTILIZER	1	Ton		
25	S-214-A	SEEDING	1	Acre		
26	S-215-A	VEGETATIVE MATERIALS FOR MULCH	2	Ton		
27	S-233-A	TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1950	Lin. Ft.		
28	907-237-A	WATTLES, 20"	200	Lin. Ft.		

SECTION 902
PROPOSAL SHEET

Project No. ERBR-STP-BR-0553(6)B
Issaquena County , Mississippi

Subtotal Erosion Control Items:						
Bridge Items						
29	S-803-A	TEST PILE	2	Each		
30	S-803-B	CONVENTIONAL STATIC PILE LOAD TEST	0	Each		
31	S-803-E	14" STEEL PILING	2200	Lin. Ft.		
32	S-803-F	22" PRE-FORMED PILE HOLE	500	Lin. Ft.		
33	901-S-804-A	BRIDGE CONCRETE, CLASS A	100	Cu. Yd.		
34	S-805-A	REINFORCEMENT	12900	Lbs.		
35	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	20	Each		
36	S-806-A	31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR	10	Each		
37	S-806-C	31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	10	Each		
38	S-806-G	PRECAST CONCRETE BARRIER RAIL	310	Lin.Ft.		
39	S-810-A	STRUCTURAL STEEL	4900	Lbs.		
40	S-815-A	LOOSE RIPRAP, 300 LB.	250	Ton		
41	S-815-E	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	410	Sq. Yd.		
Subtotal Bridge Items:						
Total Bid:						