

Section 901

ADVERTISEMENT

DeSoto County, Mississippi

Emergency Road and Bridge Repair Project No. **ERBR-STP-0906(4)B**

The Board of Supervisors of DeSoto County, Mississippi, will receive bids for the construction of public improvements along Starlanding Road, Emergency Road and Bridge Repair Project No. ERBR-STP-0906(4)B no later than **10:00 A.M., Local Time, August 14, 2019**, at the DeSoto County Administration Building, located at 365 Loshier Street, Suite 340, Hernando, MS 38632. All bids so received will be publicly opened and read aloud.

The work shall consist essentially of the following items:

Removal and replacement of an existing bridge located on Starlanding Road and Lake Cormorant Bayou. Other improvements include associated earthwork, stone base, and asphalt paving.

All other related items of work required to complete the project are as shown and specified in the Contract Documents.

The above general outline of features of the work does not in any way limit the responsibility of the contractor to perform all work and furnish all plant, labor, equipment and materials required by the specifications and the drawings referred to therein.

The attention of bidders is directed to the Contract Provisions governing selection and employment of labor.

The Board of Supervisors of DeSoto County hereby notifies all Bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged and women's business enterprises will be afforded the full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

Specifications and the drawings referenced to therein are on file in the Office of the County Engineer at 2373 Gwynn Road in Nesbit, Mississippi, and the Office of Procurement during normal business hours. Information concerning this bid can also be found on the Procurement Page @desotocountymiss.gov at no cost or from Central Bidding at [www.centralbidding.com](http://www.centralbidding.com) for a fee. All bids must comply with the specifications provided. DeSoto County reserves the right to amend the specifications, as necessary, and agrees to notify all having requested bid packets from the DeSoto County Office of Procurement.

Paper and Digital (PDF) copies of the specifications and drawings are available for pickup at the office of Waggoner Engineering, Inc. during normal business hours, at 2475 Memphis Street, Hernando, Mississippi, for a non-refundable fee of \$75.00. Checks shall be made payable to Waggoner Engineering, Inc.

Each bidder shall comply with the laws of the State of Mississippi for bidding procedures and licensing requirements. All bids submitted in excess of \$50,000 by a prime contractor or subcontractor to do any building, construction, repair, maintenance or related work must comply with Section 31-3-21, Mississippi Code of 1972, by securing a Certificate of Responsibility from the State Board of Public Contractors or by showing a statement to the effect that the bid is less than \$50,000 and Certificate of Responsibility provision does not apply, on the outside of the envelope. Bidders are to include their Certificate of Responsibility number on the outside of the envelope when applicable.

In accordance with Miss. Code Ann. Section 31-3-21(3), preference shall be given to resident contractors. Nonresident contractors submitting a bid shall attach thereto a copy of his resident state's current preference law, if any, pertaining to such state's treatment of nonresident contractors.

Each bid shall be accompanied by a Cashier's Check, Certified Check on a solvent bank or a Bidder's Bond issued by a Surety Company licensed to operate in the State of Mississippi, in the amount of five percent (5%) of the total bid price, payable to DeSoto County as bid security. Bidders shall also submit a current financial statement, if requested by the County. The successful bidder will be required to furnish a Performance Bond and a Payment Bond each in the amount of one hundred percent (100%) of the contract amount.

The proposal and contract documents in its entirety shall be submitted in a sealed envelope and deposited with the DeSoto County Office of Procurement, 365 Loshier Street, Suite 340, Hernando, MS 38632 prior to the hour and date above designated. **No stripped bids will be accepted.**

Electronic bid submissions can be submitted at [www.centralbidding.com](http://www.centralbidding.com). For any questions relating to the electronic submission process, please call Central Bidding at 225-810-4814. Electronic submissions will require the bidder to deliver their Certified Check or Bid Bond separately prior to the bid opening.

Work to be performed shall be in accordance with the "Mississippi Standard Specifications for State Aid Road and Bridge Construction, 2004", together with all amendments and/or special provisions and/or addenda to the standards duly approved and adopted, unless otherwise noted in these specifications.

The attention of Bidders is directed to the provisions of Subsection 102.07 pertaining to irregular proposals and rejection of bids.

THE BOARD OF SUPERVISORS, DESOTO COUNTY, MISSISSIPPI

WITNESS MY SIGNATURE, this the 8<sup>th</sup> day of July, 2019.

BY



Lee Caldwell, President



Misty Heffner, Chancery Clerk

DeSoto County Board of Supervisors

Board of Supervisors, DeSoto County

PUBLISH: **Clarion Ledger & DeSoto Times: July 16, 2019 and July 23, 2019**

PROJECT NUMBER: ERBR-STP-0906(4)B

COUNTY: DESOTO

PROJECT DESCRIPTION: STARLANDING ROAD BRIDGE

I (We) agree to complete the entire project within the specified contract time.

\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

BIDS WILL NOT BE CONSIDERED UNLESS THE BID CERTIFICATE LOCATED AT THE END OF THE BID SHEETS IS SIGNED

BID SCHEDULE						
LINE NO.	PAY ITEM NO.	PLAN QUANTITY	UNIT	DESCRIPTION	UNIT PRICE	ITEM TOTAL
ROADWAY ITEMS						
1	S-200-A	Lump Sum	LS	MOBILIZATION		
2	S-201-A	Lump Sum	LS	CLEARING AND GRUBBING		
3	S-202-B	1.0	UNIT	REMOVAL OF BRIDGE (Sta. 5+26)		
4	S-202-C	295.0	Lin. Ft.	REMOVAL OF FENCE AND BRICK ENTRANCE		
5	S-202-D	2762.0	Sq. Yd.	REMOVAL OF ASPHALT PAVEMENT AND GRANULAR BASE (ALL THICKNESSES)		
6	S-202-E	26.0	Lin. Ft.	REMOVAL OF PIPE (42" CMP)		
7	S-202-E	64.0	Lin. Ft.	REMOVAL OF PIPE (48" CPP)		
8	S-203-A	3383.0	Cu. Yd.	UNCLASSIFIED EXCAVATION, (PM)		
9	S-203-E1	3614.0	Cu. Yd.	BORROW EXCAVATION, CONTRACTOR FURNISHED, (FME) (CLASS 4)		
10	S-304-D	2325.0	Ton	CRUSHED STONE SIZE 610		
11	S-403-A	152.0	Ton	HOT MIX ASPHALT (ST) (9.5 mm)		
12	S-403-A	628.0	Ton	HOT MIX ASPHALT (ST) (19.0 mm)		
13	S-601-B	1.69	Cu. Yd.	CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES		
14	S-602-A	106.0	Lb.	REINFORCING STEEL		
15	S-603-C-A	48.0	Lin. Ft.	15" REINFORCED CONCRETE PIPE, CLASS III		
16	S-603-C-A	136.0	Lin. Ft.	48" REINFORCED CONCRETE PIPE, CLASS III		
17	S-603-C-B	4.0	Each	15" REINFORCED CONCRETE PIPE, END SECTION		
18	S-603-C-B	3.0	Each	48" REINFORCED CONCRETE PIPE, END SECTION		
19	S-606-B	275.0	Lin. Ft.	GUARDRAIL, W-BEAM		
20	S-606-D	4.0	Each	GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM		
21	S-606-E	4.0	Each	GUARDRAIL, TERMINAL END SECTION		

PROJECT NUMBER: ERBR-STP-0906(4)B

COUNTY: DESOTO

PROJECT DESCRIPTION: STARLANDING ROAD BRIDGE

BID SCHEDULE						
LINE NO.	PAY ITEM NO.	PLAN QUANTITY	UNIT	DESCRIPTION	UNIT PRICE	ITEM TOTAL
22	S-617-A	17.0	Each	RIGHT OF WAY MARKERS (TYPE I)		
23	S-618-A	Lump Sum	Lump Sum	MAINTENANCE OF TRAFFIC		
24	S-618-B	0	Sq. Ft.	ADDITIONAL CONSTRUCTION SIGNS	\$10.00	\$10.00
25	S-621-C	0.45	Mi.	4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)		
26	S-621-E-2	0.45	Mi.	4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)		
27	S-627-L	24.0	Each	TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS		
28	S-630-C	4.0	Each	REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)		
	SUBTOTAL ROADWAY ITEMS					
	EROSION CONTROL ITEMS					
29	901-S-228-A	2.20	Acre	HYDROSEEDING		
30	S-233-A	970.00	L.F.	TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)		
31	S-815-A	783.00	TON	LOOSE RIPRAP, 200 LB.		
32	S-815-E	715.00	Sq. Yd.	GEOTEXTILE UNDER RIPRAP, (TYPE V) (AOS 0.21-0.43)		
33	907-237-A	150.00	Lin. Ft.	WATTLES, 20"		
	SUBTOTAL EROSION CONTROL ITEMS					
	BRIDGE ITEMS - STA. 4+56 - 6+56					
34	S-803-A	2.00	Each	TEST PILES		
35	S-803-B	0.0	Each	CONVENTIONAL STATIC PILE LOAD TEST		
36	S-803-C	2,440	Lin. Ft.	18" PRESTRESSED CONCRETE PILING		
37	901-S-804-A	279.00	Cu. Yd.	BRIDGE CONCRETE, CLASS "A"		
38	901-S-804-C	596.25	Lin. Ft.	40' PRESTRESSED CONCRETE BEAM, TYPE 1+2		
39	901-S-804-C	398.75	Lin. Ft.	80' PRESTRESSED CONCRETE BEAM, TYPE III		
40	S-805-A	53,410.00	Lb.	REINFORCEMENT		
41	S-813-A	400.00	Lin. Ft.	CONCRETE RAILING		
42	S-815-A	1943.00	Ton	LOOSE RIPRAP, 300 Lbs.		
43	S-815-E	1725.00	Sq. Yd.	GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43		
	SUBTOTAL BRIDGE ITEMS					

TOTAL BID AMOUNT

\*\*SIGNATURE STATEMENT\*\*

BIDDER ACKNOWLEDGES THAT HE/SHE HAS CHECKED ALL ITEMS IN THIS PROPOSAL FOR ACCURACY AND CERTIFY THAT THE FIGURES SHOWN THEREIN CONSTITUTE THEIR OFFICIAL BID.

BIDDER'S SIGNATURE