

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
LOWNDES COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lowndes County, Mississippi at the Lowndes County Courthouse, Columbus, Mississippi, until 10:00 am on the 27th day of September, 2022 and shortly thereafter publicly opened for the construction of 0.363 miles of BRIDGE AND APPROACHES on the CANAL ROAD being known as Project No. ERBR-STP/BR-0044(35)B0 in Lowndes County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA.14+79 - 290' RT)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	14,105.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	28,707.000	CY
GRANULAR MATERIAL (LVM), (CLASS 3, GROUP B)	4,647.000	CY
MIXING, SHAPING AND COMPACTION	5,360.000	SY
HOT MIX ASPHALT, (ST) (9.5mm)	824.000	TON
ASPHALT FOR PRIME COAT (CSS-1)	1,608.000	GAL
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	2,499.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 56, TYPE CRUSHED STONE	96.000	CY
RUMBLE STRIPS, GROUND-IN	0.617	MI
24" REINFORCED CONCRETE PIPE, CLASS III	128.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	8.000	EA
GUARD RAIL, W BEAM	275.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	22.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 mil)	0.730	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	3,856.000	LF

(90 mil)		
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	49.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	2.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	4.960	TON
COMMERCIAL FERTILIZER (13-13-13)	3.720	TON
AMMONIUM NITRATE	2.490	TON
SEEDING	4.960	AC
VEGETATIVE MATERIALS FOR MULCH	9.920	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE	4,240.000	LF
WATTLES, 20"	190.000	LF
LOOSE RIPRAP, 200 LB.	2,637.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	2,550.000	LF
16" PRE-FORMED PILE HOLES	1,630.000	LF
BRIDGE CONCRETE, CLASS "A"	388.290	CY
100' PRESTRESSED CONCRETE BEAM TYPE IV	498.750	LF
40' PRESTRESSED CONCRETE BEAM TYPE I+2	993.750	LF
REINFORCEMENT	64,032.000	LB
CONCRETE RAILING	598.000	LF
LOOSE RIPRAP, 300 LB.	454.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	842.000	SY

OSARC 1947
AUG 25 2022
RECEIVED
51

PROJECT NO: ERBR STP/BR-0044(35)BO
LOWNDES COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 160 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Lowndes County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Robert L. Calvert, County Engineer for Lowndes County, Mississippi, P. O. Drawer 1078, West Point. The Cost is seventy-five dollars (\$75.00) for plans and seventy-five dollars (\$75.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lowndes County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Trip Hairston, President
Lowndes County Board of Supervisors

Publish: August 25, 2022
September 1, 2022