

## **NOTICE OF ADVERTISEMENT**

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT  
PROJECT NO. ERBR-STPBR-0005(23)B  
HICKORY FLAT-CORNERVILLE ROAD  
BENTON COUNTY, MISSISSIPPI**

**NOTICE TO CONTACTORS: Project No. ERBR-STPBR-0005(23)B Benton County, MS.** The Board of Supervisors of Benton County, MS will receive bids for the construction of **0.127 miles of Bridge and Approaches to Replace Bridge No. 49 on Hickory Flat-Cornersville Road.** This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids will be received until **10:00 AM on the 17th day of June, 2019** and shortly thereafter publicly opened at the **Benton County Courthouse, 190 Ripley Avenue, Ashland, MS.** Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Benton County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Kenneth P. Geno, Jr., Engineer of Record** of Cook Coggin Engineers, Inc., at [www.cceplanroom.com](http://www.cceplanroom.com) upon payment of \$100.00, which is non-refundable. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at [www.osarc.ms.gov/bid-calendar-erbf](http://www.osarc.ms.gov/bid-calendar-erbf). The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ricky Pipkin, President  
Benton County Board of Supervisors

Publish: *May 9<sup>th</sup> and May 16<sup>th</sup>, 2019*

## BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

**Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.**

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
<b>ERBR-STPBR-0005(23)B HICKORY FLAT-CORNERVILLE ROAD</b>					
<b>BASE BID ITEMS</b>					
<b>Roadway Items</b>					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 16+21	1.00	UN	\$	\$
S-203-A	Unclassified Excavation (FM)	669.00	CY	\$	\$
S-203-E-1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	1,467.00	CY	\$	\$
S-304-A	Granular Material (Class 5, Group "C")(LVM)(Includes 50% Shrinkage Factor)	168.00	CY	\$	\$
S-304-C	Crushed Stone Size 3/4" & Down (FM)	69.00	CY	\$	\$
S-310-D	Mixing, Shaping and Compaction	118.00	SY	\$	\$
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	109.00	TON	\$	\$
S-403-A	Hot Mix Asphalt, ST, 19 mm	15.00	TON	\$	\$
S-403-B	Hot Mix Asphalt, ST, 9.5 mm, Leveling	25.00	TON	\$	\$
S-406-A	Cold Milling of Bituminous Pavement, All Depths	444.00	SY	\$	\$
S-408-A	Asphalt for Prime Coat (MC-70) or (EA-1)	42.00	GAL	\$	\$
S-603-C-A	36" Reinforced Concrete Pipe, Class III	144.00	LF	\$	\$
S-606-B	Guardrail "W" Beam	375.00	LF	\$	\$
S-606-D	Guardrail Bridge End Section, Type I Thrie Beam (Complete)	4.00	EA	\$	\$
S-606-E	Guardrail, (Terminal End Section)	4.00	EA	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$

# BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-617-A	Right Of Way Markers, Type II	23.00	EA	\$	\$
S-618-A	Maintenance of Traffic	1.00	LS	\$	\$
S-618B	Additional Construction Signs	0.00	SF	\$ 10.00	\$ 0.00
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.255	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont.Yellow) (90 Mils)	1,350.00	LF	\$	\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	22.00	EA	\$	\$
<b><u>Erosion Control Items</u></b>					
901-S-212-A	Agricultural Limestone	3.00	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	1.50	TON	\$	\$
S-212-F	Ammonium Nitrate	0.38	TON	\$	\$
S-214-A	Seeding	1.50	AC	\$	\$
S-215-A	Vegetative Materials for Mulch	3.00	TON	\$	\$
S-226-A	Solid Sodding	100.00	SY	\$	\$
S-227-A	Excelsior Blanket	1,700.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	1,400.00	LF	\$	\$
S-815-A	Loose Riprap, 200 Lb	50.00	TON	\$	\$
907-234-F	Turbidity Barrier	180.00	LF	\$	\$
907-237-A	Wattles, 20"	160.00	LF	\$	\$

# BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
<b>Bridge Items 40' - 80' - 40' Prestressed Concrete Beam Spans</b>					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Pile	2.00	EA	\$	\$
S-803-B	Conventional Static Pile Load Test	0.00	EA	\$ 4000.00	\$ 0.00
S-803-E	14" Steel Piling	2,430.00	LF	\$	\$
901-S-804-A	Bridge Concrete, Class "A"	233.51	CY	\$	\$
901-S-804-C	40' Prestressed Concrete Beam Type I+2	397.50	LF	\$	\$
901-S-804-C	80' Prestressed Concrete Beam Type IV	398.75	LF	\$	\$
S-805-A	Reinforcement	35,873.00	LB	\$	\$
S-810-A	Structural Steel	10,935.00	LB	\$	\$
S-813-A	Concrete Railing	320.00	LF	\$	\$
S-815-A	Loose Riprap, 300 Lb	405.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	750.00	SY	\$	\$
<b>TOTAL BASE BID</b>					\$