

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
CLAY COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Clay County, Mississippi at the Clay County Courthouse, West Point, Mississippi, until 10:00 a.m. on the 22nd day of August, 2019 and shortly thereafter publicly opened for the construction of 0.249 miles of BRIDGE AND APPROACHES on the CARADINE-COUNTY LINE-ROAD being known as Project No. ERBR-STP/BR-0013(53)B in Clay County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 369+60.25)	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	2,930.000	CY
BORROW EXCAVATION (F.M.E.)	8,808.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GRANULAR MATERIAL (LVM)	2,782.000	CY
(CLASS 3, GROUP B)		
MIXING, SHAPING AND COMPACTION	3,151.000	SY
HOT MIX ASPHALT, (ST) (9.5mm)	483.000	TON
ASPHALT FOR PRIME COAT	945.000	GAL
(CSS-1)		
RUMBLE STRIPS, GROUND-IN	0.379	MI
36" REINFORCED CONCRETE PIPE,	32.000	LF
CLASS III		
36" REINFORCED CONCRETE PIPE,	2.000	EA
END SECTION		
GUARD RAIL, W BEAM	275.000	LF
GUARD RAIL, BRIDGE END	4.000	EA
SECTION, TYPE "1", THRIE-BEAM		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	16.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIP	0.500	MI
(CONTINUOUS WHITE) (60 mil)		
4" WIDE THERMOPLASTIC TRAFFIC	0.214	MI
STRIPE (SKIP YELLOW) (90 mil)		
4" WIDE THERMOPLASTIC TRAFFIC	1,510.000	LF
STRIPE (CONTINUOUS YELLOW)		
(90 mil)		
TWO-WAY YELLOW REFLECTIVE HIGH	24.000	EA
PERFORMANCE RAISED MARKERS		

SECTION 900  
PROJECT NO. ERBR-STP/BR-0013(53)B  
CLAY COUNTY

---

REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13-13-13)	2.250	TON
AMMONIUM NITRATE	1.500	TON
SEEDING	3.000	AC
VEGETATIVE MATERIALS FOR MULCH	6.000	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE 1) (AOS 0.15-0.84)	2,000.000	LF
WATTLES 20"	120.000	LF
LOOSE RIPRAP, 100 LB.	50.000	TON
LOOSE RIPRAP, 200 LB.	795.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
HP 14 X 89 STEEL PILING	2,145.000	LF
16" PRE-FORMED PILE HOLES	429.000	LF
BRIDGE CONCRETE, CLASS "A"	349.050	CY
40' PRESTRESSED CONCRETE BEAM TYPE I+2	954.000	LF
80' PRESTRESSED, CONCRETE BEAM TYPE III	319.000	LF
REINFORCEMENT	69,455.000	LB
CONCRETE RAILING	640.000	LF
LOOSE RIPRAP, 300 LB.	490.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP TYPE V, AOS 0.21-0.43	907.000	SY

RECEIVED  
JUL 24 2019  
OSARC 1947 51

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Clay County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Robert L. Calvert, County Engineer for Clay County, Mississippi, P. O. Drawer 1078, West Point. The Cost is seventy-five dollars (\$75.00) for plans and seventy-five dollars (\$75.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Clay County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

R.B. Davis, President  
Clay County Board of Supervisors

Publish: July 23, 2019

July 30, 2019

RECEIVED  
JUL 30 2019  
OSAND 1987 51