

NOTICE OF ADVERTISEMENT

**EMERGENCY ROAD AND BRIDGE REPAIR FUND PROJECT
PROJECT NO. ERBR-STPBR-0041(45)BO
COUNTY ROAD 941
LEE COUNTY, MISSISSIPPI**

NOTICE TO CONTACTORS: Project No. ERBR-STPBR-0041(45)BO Lee County, MS. The Board of Supervisors of Lee County, MS will receive bids for the construction of **0.217 miles of Bridge and Approaches to Replace Bridge No. 13 on County Road 941**. This project is funded by Mississippi Infrastructure Modernization Act of 2018's Emergency Road & Bridge Repair Fund. Sealed bids or electronic bids will be received until **10 AM on the 23rd day of July, 2019** and shortly thereafter publicly opened. **Sealed bids** will be received at the **Lee County Board of Supervisors Building, 300 West Main Street, Tupelo, MS** or **electronic bids** will be received via electronic online bid submission through **www.cceplanroom.com**. Plans, specifications & contract documents are on file in the Office of the Chancery Clerk of Lee County, Mississippi. Plans, specifications & contract documents may be viewed and/or secured from **Carrson Neal, Engineer of Record** of Cook Coggin Engineers, Inc., at **www.cceplanroom.com** upon payment of \$100.00, which is non-refundable. Plans, specifications & contract documents may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes **only**. Questions regarding electronic bidding shall be directed to Plan House Printing at (662) 407-0193. Project information is also available on the website of the Mississippi Office of State Aid Road Construction at **www.osarc.ms.gov/bid-calendar-erbf**. The award, if made, will be made to the lowest qualified bidder on the basis of qualified quantities. The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that minority business enterprises will be afforded full opportunity to submit bids and will not be discriminated against on the grounds of race, color, or national origin in consideration of the award. Bids will be accepted only under the name of the Bidder whose name appears on the official list of Planholders maintained by the Engineer of Record. Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Tony Roper, President
Lee County Board of Supervisors

Publish: June 14th and June 21st, 2019

BID SCHEDULE

Each bid item unit price shall include sales tax and all other applicable taxes and fees.

Bidder acknowledges that (1) each Unit Price Bid includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, (2) estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids, and (3) final payment for all Unit Price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

Write/Type unit prices and bid prices, as clearly as possible, in number format.

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
ERBR-STPBR-0041(45)BO COUNTY ROAD 941					
BASE BID ITEMS					
Roadway Items					
S-200-A	Mobilization	1.00	LS	\$	\$
S-201-A	Clearing & Grubbing	1.00	LS	\$	\$
S-202-B	Removal of Existing Bridge @ Sta. 154+01	1.00	UN	\$	\$
S-203-A	Unclassified Excavation (FM)	1,572.00	CY	\$	\$
S-203-E-1	Borrow Excavation (FME) (Contractor Furn.) (Cl.9)	5,023.00	CY	\$	\$
S-232-A	Geotextile Fabric Stabilization (Type V) (AOS <0.43)	3,900.00	SY	\$	\$
S-304-A	Granular Material (LVM)(Class 5, Group "C")	187.00	CY	\$	\$
S-304-C	Crushed Stone Size 3/4" & Down (FM)	1,080.00	CY	\$	\$
S-310-D	Mixing, Shaping and Compaction	2,585.00	SY	\$	\$
S-403-A	Hot Mix Asphalt, ST, 9.5 mm	390.00	TON	\$	\$
S-408-A	Asphalt for Prime Coat (EA-1) or (AE-P)	905.00	GAL	\$	\$
S-601-B	Class "B" Structural Concrete, Minor Structures	0.412	CY	\$	\$
S-603-C-A	24" Reinforced Concrete Pipe, Class III	80.00	LF	\$	\$
S-603-C-A	36" Reinforced Concrete Pipe, Class III	80.00	LF	\$	\$
S-603-C-B	24" Reinforced Concrete Pipe, End Section	2.00	EA	\$	\$
S-603-C-B	36" Reinforced Concrete Pipe, End Section	2.00	EA	\$	\$
S-603-C-D	22" X 13" Reinforced Concrete Arch Pipe, Class AIII	40.00	LF	\$	\$
S-603-PE	24" Corrugated Polyethylene Pipe	160.00	LF	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
S-603-PE	36" Corrugated Polyethylene Pipe	48.00	LF	\$	\$
S-603-PE	48" Corrugated Polyethylene Pipe	80.00	LF	\$	\$
S-606-B	Guardrail "W" Beam	137.50	LF	\$	\$
S-606-D	Guardrail Bridge End Section, Type I Thrie Beam (Complete)	4.00	EA	\$	\$
S-606-E	Guardrail, (Terminal End Section)	4.00	EA	\$	\$
S-607-A	Roadway Construction Surveying	1.00	LS	\$	\$
S-617-A	Right Of Way Markers, Type II	16.00	EA	\$	\$
S-618-A	Maintenance of Traffic	1.00	LS	\$ 10.00	\$ 0.00
S-618-B	Additional Construction Signs	-	SF	\$	\$
S-621-C	4" Wide Thermoplastic Edge Stripe (Cont. White) (60 Mils)	0.433	MI	\$	\$
S-621-E-1	4" Wide Thermoplastic Traffic Stripe (Cont. Yellow) (90 Mils)	2,290.00	LF	\$	\$
S-627-L	Two-Way Yellow Reflective High Performance Raised Markers	21.00	EA	\$	\$
S-630-C	Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	EA	\$	\$
S-630-D	Reflectorized Traffic Delineator Sign (Encapsulated Lens)	15.00	EA	\$	\$
Erosion Control Items					
901-S-212-A	Agricultural Limestone	5.00	TON	\$	\$
S-212-B	Commercial Fertilizer (13-13-13)	2.50	TON	\$	\$
S-212-F	Ammonium Nitrate	0.63	TON	\$	\$
S-214-A	Seeding	2.50	AC	\$	\$
S-215-A	Vegetative Materials for Mulch	5.00	TON	\$	\$
S-226-A	Solid Sodding	100.00	SY	\$	\$
S-233-A	Temporary Silt Fence (Type I or II) (AOS 0.15-0.84)	850.00	LF	\$	\$
S-815-A	Loose Riprap, 200 Lb	575.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	1,058.00	SY	\$	\$
237-A	Wattles, 20"	820.00	LF	\$	\$

BID SCHEDULE

Item No.	Item Description	Estimated Quantity	Unit	Bid Unit Price	Bid Price
Bridge Items 31' - 100' - 31' Prestressed Concrete Beam Spans					
S-607-B	Bridge Constuction Surveying	1.00	LS	\$	\$
S-803-A	Test Piles	2.00	EA	\$	\$
S-803-B	Loading Tests	-	EA	\$ 4000.00	\$ 0.00
S-803-E	12" Steel Piling	1,710.00	LF	\$	\$
S-803-F	18" Pre-formed Pile Holes	1,220.00	LF	\$	\$
901-S-804-A	Bridge Concrete, Class "A"	185.20	CY	\$	\$
901-S-804-C	31' Prestressed Concrete Beam Type I+2	307.50	LF	\$	\$
901-S-804-C	80' Prestressed Concrete Beam Type III	398.75	LF	\$	\$
S-805-A	Reinforcement	29,571.00	LB	\$	\$
S-813-A	Concrete Railing	284.00	LF	\$	\$
S-815-A	Loose Riprap, 200 Lb	342.00	TON	\$	\$
S-815-E	Geotextile Under Riprap, Type V, AOS <0.43	634.00	SY	\$	\$
TOTAL BASE BID					\$